EROSION AND SEDIMENT CONTROL, STORMWATER AND FLOODPLAIN MANAGEMENT APPROVED EROSION CONTROL | SEC-047126-2020 STORMWATER MGMT.

SWF-047129-2020 FLOOD STUDY DATE <u>01/26/2021</u> ENVIRONMENTAL CONSULTANT SIGNATURE

PROJECT NARRATIVE

THIS PROJECT IS LOCATED IN ROLESVILLE, NORTH CAROLINA AT ROLESVILLE ROAD. IT INVOLVES THE COMBINING OF SEPARATELY PROPOSED PROJECTS KNOWN AS KALAS FALLS, ROGERS FARM AND ONE OTHER TRACT KNOWN AS THE WATKINS PROPERTY. IT DRAINS TO TRIBUTARIES OF HARRIS BRANCH WHICH IS PART OF THE NEUSE RIVER BASIN. IT IS ALSO BOUNDED ON ALL SIDES BY MOSTLY UNDEVELOPED LAND. IT IS APPROXIMATELY 0.5 MILES NORTHWEST OF THE INTERSECTION OF MITCHELL MILL ROAD AND ROLESVILLE ROAD IN WAKE COUNTY, NORTH CAROLINA. THE TOTAL AREA OF THE PROJECT IS 282.726(EXCLUDES EXISTING ROW AND CEMETERY) ACRES. THE CURRENT PHASE IS 83.66

ATTENTION CONTRACTORS:

THE CONTRACTOR RESPONSIBLE FOR THE EXTENSION OF WATER, SEWER, AND / OR REUSE, AS APPROVED IN THESE PLANS, IS RESPONSIBLE FOR CONTACTING THE PUBLIC UTILITIES DEPARMENT AT (919) 996-4540 AT LEAST TWENTY FOUR HOURS PRIOR TO BEGINNING ANY OF THEIR CONSTRUCTION.


FAILURE TO NOTIFY BOTH CITY DEPARTMENTS IN ADVANCE OF BEGINNING CONSTRUCTION, WILL RESULT IN THE ISSUANCE OF MONETARY FINES, AND REQUIRE REINSTALLATION OF ANY WATER AND SEWER FACILITIES NOT INSPECTED AS A OF THE NOTIFICATION FAILURE.

FAILURE TO CALL FOR INSPECTION, INSTALL A DOWNSTEAM PLUG, HAVE PERMITTED PLANS ON THE JOB SITE, OR ANY OTHER VIOLATION OF THE CITY OF RALEIGH STANDARDS WILL RESULT IN A FINE AND POSSIBLE EXCLUSION FROM FUTURE WORK IN THE CITY OF RALEIGH.

- 1. ALL PUBLIC WATER AND SEWER MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF RALEIGH STANDARDS AND SPECIFICATIONS.

 2. CONTRACTOR SHALL CONTACT 811 (1-800-632-4949)
- TO LOCATE ALL EXISTING UTILITIES PRIOR TO THE START OF CONSTRUCTION. 3. CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF THE EXISTING UTILITIES AND NOTIFY THE PROJECT ENGINEER (919-469-1101) OF ANY
- 4. ALL BOUNDARY AND FIELD TOPOGRAPHY PROVIDED BY WITHERS & RAVENEL.
- 5. ALL CONDITIONS OF SUP 19-01 AND MA 19-02 R&PUD ARE APPLICABLE AND WILL BE MET.

CONSTRUCTION PHASE 1 FOR KALAS FALLS SITUATED AT ROLESVILLE ROAD, ROLESVILLE WAKE, NORTH CAROLINA



VICINITY MAP SCALE: 1"=1000'

THESE IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE FOLLOWING DRAWINGS AND THE STANDARD SPECIFICATIONS OF THE CITY OF RALEIGH, WAKE COUNTY, AND NCDOT.



PUBLIC IMPROVEME	ENTS PHASE 1
PUBLIC WATER (12")	3,719 LF
PUBLIC WATER (8")	723.67 LF
PUBLIC WATER (6")	556.31 LF
PUBLIC SEWER (12")	1,453 LF
PUBLIC SEWER (8")	8,483.28 LF
PUBLIC STREETS	8,202.99 LF
ROAD WIDENING	2,411 LF
TOTAL NO. OF LOTS	129
TOTAL DISTURBED ARE	EA 33.78 AC

	SHEET INDEX
CVR	COVER SHEET Updated
1.0	OVERALL EXISTING CONDITIONS
1.1-1.2	EXISTING CONDITIONS PHASE 1
2.0-2.1	EROSION CONTROL STAGE 1
2.2-2.7	EROSION CONTROL(50 SCALE)
3.0	GENERAL NOTES AND LEGENDS
3.1	SCHEDULE PLAN Updated
4.0	DRAINAGE PLAN OVERALL
4.1-4.6	GRADING & DRAINAGE PHASE 1 (50 SCALE) Updated 4.1 & 4.1
4.7	SCM 1A DETAIL
4.8	SCM 2A DETAIL
4.9	SCM 2B DETAIL
4.10	SCM 3D DETAIL
4.11	SCM 3E DETAIL
5.0	SITE PLAN OVERALL
5.1	SITE PLAN PHASE 1 OVERALL Updated
5.2-5.7	SITE PLAN PHASE 1 (50 SCALE) Updated 5.2 & 5.5
6.0	OVERALL UTILITIES PLAN Updated
6.1-6.6	UTILITY SHEET (50 SCALE) Updated 4.1 & 4.6
7.0-7.2	FALLS BLUFF DR PLAN AND PROFILE
8.0	DARTFORD GREEN PLACE AND OUTFALL A PLAN AND PROFILE
9.0	STONERIDGE BARN WAY PLAN AND PROFILE
10.0	HILL TOP CREST CT AND OUTFALL D PLAN AND PROFILE
11.0	TANSLEY CREST LOOP (E) PLAN AND PROFILE
12.0	TANSLEY CREST LOOP (W) PLAN AND PROFILE
13.0	FRIENDLY MILL LANE & OUTFALL E PLAN AND PROFILE
14.0	SANITARY SEWER OUTFALL A PLAN AND PROFILE
15.0	SANITARY SEWER OUTFALL C PLAN AND PROFILE
16.0	SANITARY SEWER OUTFALL G PLAN AND PROFILE (10+00-17+51
17.0	SANITARY SEWER OUTFALL G PLAN AND PROFILE (17+51.82-24+5)
18.0	ROLESVILLE RD SOTHERN SECTION EXISTINAG & IMPROVEMEN
18.1	ROLESVILLE RD NORTHERN SECTION EXISTINAG & IMPROVEMI
18.2	ROLESVILLE RD OFF-SITE STORM PLAN AND PROFILE
18.3	ROLESVILLE RD OFF-SITE STORM PLAN AND PROFILE
19.0	ROLESVILLE RD IMPROVEMENTS
20.0	TRANSPORTATION PLAN
X1	CROSS-SECTION STA: 9+57.35 - 11+50
X2	CROSS-SECTION STA: 12+00 - 14+00
Х3	CROSS-SECTION STA: 14+50 - 16+50
X4	CROSS-SECTION STA: 17+00 - 19+00
X5	CROSS-SECTION STA: 19+50 - 21+50
X6	CROSS-SECTION STA: 22+00 - 22+50
X7	CROSS-SECTION STA: 37+50 - 39+00
X8	CROSS-SECTION STA: 39+50 - 41+50
X9	CROSS-SECTION STA: 42+00 - 44+00
X10	CROSS-SECTION STA: 44+50 - 46+50
X11	CROSS-SECTION STA: 47+00
CD1-CD5	EROSION CONTROL DETAIL
CD6-CD8	WATER DETAIL
CD9-CD11	SANITARY SEWER DETAIL
CD12-CD19	STORM DETAIL
,	KALAS FALLS OS1 LANDSCAPE PLAN EXHIBIT NEW

PROPRTY OWNER: PHASE 1	DR HORTON INC. CENTRAL CAROLINA DIVISION CONTACT: MIKE BROWN 7208 FALLS OF NEUSE ROAD STE. 201 RALEIGH, NC 27615
PROPERTY OWNER: REMAINING PHASES	MITCHELL MILL ROAD INVESTORS LLC CONTACT KARL BLACKLEY 105 WESTON ESTATES WAY CARY, NC 27513 919-481-3000
SURVEYOR:	WITHERS RAVENEL CONTACT: MATT TIMLIN 115 MACKENAN DRIVE CARY, NC 27511 919-469-3340
BUFFER/WETLAND:	WITHERS RAVENEL CONTACT: TROY BEASLEY 115 MACKENAN DRIVE CARY, NC 27511 919-469-3340

BUFFER/WETLAND:	CONTACT: TROY BEASLEY 115 MACKENAN DRIVE CARY, NC 27511 919-469-3340
	SITE PERMITTING APPROVAL
Water and Sewer	Permits (If applicable)
this plan. The mate	consents to the connection and extension of the City's Public Sewer System as show rial and Construction methods used for this project shall conform to the standards a e City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permi
this plan. The mat	consents to the connection and extension of the City's Public Water System as sho erial and Construction methods used for this project shall conform to the standard ne City's Public Utilities Handbook. City of Raleigh Public Utilities Department Pe
collection system	consents to the connection to its public sewer system and extension of the private as shown on this plan. The material and constructions methods used for this project indards and specifications of the City's Public Utilities Handbook.
City of Raleigh Pul	dic Utilities Department Permit k
CITY	F RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer


SHEET NO. **CVR**


JOB NUMBER: CHECKED BY: DRAWN BY:


EDS


9/19/2019


Z:\Jobs\9900\Watkins Property\dwg_Working Dwgs\Phase 1\01. CVR.dwg





























OWNER SHALL OBTAIN NCG01 PERMIT. THERE MAY BE A FEE FOR THIS

SCHEDULE A PRE-CONSTRUCTION CONFERENCE WITH THE WATERSHED MANAGER, OBTAIN LAND DISTURBING PERMIT. CONTACT JEEVAN NEUPANE, P. E. (919-819-8907).

3. TREE PROTECTION FENCES, SILT FENCES AND CONSTRUCTION ENTRANCE SHALL BE INSTALLED AS SHOWN ON THE EROSION CONTROL SHEETS. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED ALL RESULTING BARE AREAS IMMEDIATELY AFTER CONSTRUCTION. ALL MAINTENANCE PADS SHALL BE CLEARED BUT THE STONE REQUIRED SHOULD NOT BE INSTALLED UNTIL JUST BEFORE THE PAD IS NEEDED.

4. CONSTRUCT EROSION CONTROL MEASURES INCLUDING SILT DITCHES LEADING TO THEM AS SHOWN ON THE EROSION CONTROL SHEETS. CONSTRUCT DIVERSION DITCHES AS SHOWN. EACH DIVERSION DITCH SHALL HAVE THE LINING INSTALLED THE SAME DAY AS THE SECTION IS CONSTRUCTED. THE PIPE FROM 200A TO 200 SHALL BE INSTALLED AT THE SAME TIME AS SB#201 TO CARRY SEDIMENT WATER UNDER FUTURE DITCH CARRYING CLEAN DIVERTED WATER

- OBTAIN CERTIFICATE OF COMPLIANCE THROUGH INSPECTION BY WATERSHED MANAGER.
- GENERAL GRADING MAY BEGIN.

THE GRADING OF FALLS BLUFF DR. BEYOND TANSLEY CREST LOOP (WEST INTERSECTION) SHALL BE DELAYED TO PROVIDE AN USABLE SLOPE FOR MATERIALS AND EQUIPMENT TO ACCESS THE CONSTRUCTION OF THE SEWER LINE JUST BEYOND THE CREEK. WHEN THE SEWER LINE IS FINISHED THE GRADING MAY BE DONE AS SHOWN ON THE PLANS.

- CLEAN SEDIMENT BASINS WHEN ONE-HALF FULL
- SEED AND MULCH DENUDED AREA INCLUDING ANY CUT/FILL SLOPES WITHIN FOURTEEN (14) DAYS AFTER FINISHED GRADES ARE ESTABLISHED.
- 10. MAINTAIN SOIL EROSION CONTROL MEASURES UNTIL PERMANENT GROUND IS ESTABLISHED.
- 11. AS EACH CATCH BASIN OR YARD INLET IS INSTALLED, IT SHALL HAVE INLET PROTECTION INSTALLED. THIS IS TO REMAIN IN PLACE UNTIL ALL AREAS WHICH DRAIN TO IT ARE STABILIZED OR PAVED.
- 12. WHEN ALL CONTRIBUTARY AREAS ARE STABILIZED, OBTAIN APPROVAL FROM THE WATERSHED MANAGER TO CLOSE EACH SEDIMENT BASIN.
- 13. CLEAN SEDIMENT FROM SEDIMENT BASIN WHICH IS TO BE CONVERTED TO A WET POND AND REMOVE THE SKIMMER. INSTALL PLANTINGS AS REQUIRED. CLOSE THE DRAIN VALVE.
- 14. REQUEST FINAL APPROVAL BY WATERSHED MANAGER AFTER VEGETATION IS ESTABLISHED..
- REMOVE SOIL EROSION CONTROL MEASURES AND STABILIZE THESE AREAS.
- THE OWNER IS TO FINALIZE THE NCG01 PERMIT

Y:\Jobs\9900\Watkins Property\Documents\Schedules\ConSeq, Ph1.docx 11/19/20, Rev. 12/7/20

Required Wake County Basin Removal Sequence

- 1. Schedule a site meeting with the Environmental Consultant to determine if a basin can be removed. Install silt fencing or other temporary erosion control measures as needed prior to removal of
- 2. Remove Basin(s) and associated temporary diversion ditches. If culvert pipes need to be extended, perform this operation at this time. Fine grade area in preparation for seeding.
- Perform seedbed preparation, seed, mulch and asphalt tack any resulting bare areas immediately.
- 4. Install velocity dissipators and/or level spreaders as required on the Erosion Control Plan.
- 5. When site is fully stabilized, call Environmental Consultant for approval of removing remaining temporary erosion control measures and advice on when site can be issued a Certificate of Completion.

Note: A meeting should also be scheduled with the Environmental Consultant to determine when a basin may be converted for stormwater use. Some municipalities may also require this.

NOTES FOR CONSTRUCTION:

- 1. PLANS FOR INFRASTRUCTURE ONLY.
- 2. ALL CONSTRUCTION MUST BE PERFORMED IN ACCORDANCE WITH CURRENT CITY OF RALEIGH STANDARD SPECS AND DETAILS, WAKE COUNTY SPECIFICATIONS, NCDOT SPECIFICATIONS AND TOWN OF ROLESVILLE
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF EXISTING CONDITIONS. CONTRACTOR SHALL NOTIFY ENGINEER OF DISCREPANCIES BETWEEN FIELD CONDITIONS AND THESE DRAWINGS.
- 4. THERE ARE NO 100 YEAR FLOOD PLAINS PER FEMA MAP WITHIN PROPERTY
- 5. CONTRACTOR WILL KEEP STREETS CLEAN AT ALL TIMES, OR A WASH STATION WILL BE REQUIRED. 6. ALL CATCH BASINS SHALL HAVE INLET PROTECTION
- 7. ALL CUT AND FILL SLOPES MUST BE STABILIZED WITHIN 14 DAYS OF ANY PHASE OF GRADING, WITH SOME SLOPES TO BE STABALIZED WITHIN 7 DAYS AS SHOWN ON CHART TO THE LEFT AND ON THE
- 8. TREE PROTECTION FENCING ON THIS PROJECT WILL BE INSTALLED AND INSPECTED BEFORE THE
- GRADING PERMIT IS ISSUED. " A PRE-CONSTRUCTION CONFERENCE MAY BE REQUIRED BEFORE GRADING PERMIT IS ISSUED.
- 10. PERMANENT GROUND COVER WILL BE ESTABLISHED IN 15 WORKING DAYS OR 90 CALENDAR DAYS WHICHEVER IS SHORTER.
- 11. THE AREA DESIGNATED SHALL BE USED FOR TOPSOIL STOCKPILE.
- 12. THIS PROJECT IS IN THE NEUSE RIVER WATERSHED. PHASE 1 AREA = 83.66 ACRES
- 13. WETLANDS ON THIS PROJECT ARE AS SHOWN.
- 14. ALL CONSTRUCTION TO BE IN ACCORDANCE WITH CITY OF RALEIGH STANDARDS AND SPECIFICATIONS, WAKE COUNTY STANDARDS AND WITH N.C.D.O.T., WHERE APPLICABLE.
- 15. MINIMUM CORNER CLEARANCE FROM THE CURB LINE OF INTERSECTING STREETS SHALL BE AT LEAST TWENTY (20) FEET FROM THE POINT OF TANGENCY.

GENERAL NOTES:

- A. ALL TREE PROTECTION FENCING SHALL BE MAINTAINED UNTIL ALL SITE WORK IS COMPLETED THE FENCING SHALL BE REMOVED PRIOR TO THE FINAL SITE INSPECTION FOR THE CERTIFICATE OF OCCUPANCY (CO)
- B. ALL TREE PROTECTION FENCING SHALL BE MAINTAINED UNTIL ALL SITE WORK IS COMPLETED. THE FENCING SHALL REMAIN UNTIL ISSUANCE OF CERTIFICATE OF OCCUPANCY (CO).
- C. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH ALL CITY OF RALEIGH STANDARDS AND SPECIFICATIONS.
- D. WITHIN THE SIGHT TRIANGLES SHOWN ON ALL SITE PLAN AND LANDSCAPE PLAN SHEETS, NO OBSTRUCTION BETWEEN 2 FEET AND 8 FEET IN HEIGHT ABOVE THE CURB LINE ELEVATION SHALL BE LOCATED IN WHOLE OR PART. $\,$ OBSTRUCTIONS INCLUDE, BUT ARE NOT LIMITED TO, ANY BERM, FOLIAGE, FENCE, WALL SIGN, PARKED CAR, OR OTHER OBJECT. ALL STREET TREES FALLING WITHIN THE SIGHT TRIANGLES SHOWN ON THIS PLAN SHALL BE LIMBED UP BETWEEN 2
- F MINIMUM CORNER CLEARANCE FROM THE CURB LINE OF INTERSECTING STREETS SHALL BE AT LEAST 20 FEET FROM THE POINT OF TANGENCY OF THE CURB. NO DRIVEWAYS SHALL ENCROACH ON THIS MINIMUM CORNER CLEARANCE.
- F. ALL STREETS SHOWN ON THESE PLANS HAVE FULL WIDTH OF RIGHT-OF-WAY CLEARED AND GRADED WITHIN 50 FEET OF ALL STREET INTERSECTIONS. THE FULL WIDTH OF RIGHT-OF-WAY SHALL BE CLEARED AND GRADED ALONG ALL MAJOR, MINOR AND SENSITIVE AREA
- G. WHEEL CHAIR ACCESS RAMPS WILL BE PROVIDED IN ACCORDANCE WITH RALEIGH STANDARD DRAWING STD. #20.11. WHERE SIDEWALK IS NOT REQUIRED ALONG THE PUBLIC RIGHT-OF-WAY, CURB IS TO BE DEPRESSED AT ALL RAMP LOCATIONS SHOWN ON STD. #20.11.
- H. ALL INDIVIDUAL LOTS SHALL HAVE AN EROSION CONTROL PLAN SUBMITTED PRIOR TO CONSTRUCTION OF HOUSES THERE UPON. IF MULTIPLE LOTS WITH A TOTAL DISTURBED AREA OF MORE THAN 12,000 SF ARE TO BE BUILT UPON AT ONE TIME, A COORDINATED EROSION CONTROL PLAN SHALL BE SUBMITTED.

REQUIRED WAKE COUNTY CONSTRUCTION SEQUENCE*

- SCHEDULE A PRECONSTRUCTION CONFERENCE WITH THE WATERSHED MANGER, JEEVAN NEUPANE, PE (919)819-8907.
- OBTAIN A LAND-DISTURBING PERMIT
- INSTALL GRAVEL CONSTRUCTION PAD. TEMPORARY DIVERSIONS. SILT FENCE. SEDIMENT BASINS OR OTHER MEASURES AS SHOWN ON THE APPROVED PLAN. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS, BERMS AND BASINS IMMEDIATELY AFTER CONSTRUCTION
- CALL JEEVAN NEUPANE, PE (919)819-8907FOR AN ONSITE INSPECTION BY THE WATERSHED MANAGER TO
- OBTAIN A CERTIFICATE OF COMPLIANCE.
- BEGIN CLEARING AND GRUBBING. MAINTAIN DEVICES AS NEEDED. ROUGH GRADE SITE. INSTALL STORM SEWER, IF SHOWN, AND PROTECT INLETS WITH BLOCK AND GRAVEL INLET CONTROLS, SEDIMENT TRAPS OR OTHER APPROVED MEASURES AS SHOWN ON THE PLAN. BEGIN
- CONSTRUCTION, BUILDING, ETC. STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH VEGETATION, PAVING, DITCH
- LININGS, ETC. SEED AND MULCH DENUDED AREAS PER GROUND STABILIZATION TIME FRAMES. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CALL
- JEEVAN NEUPANE,PE (919)819—8907 FOR AN INSPECTION BY THE WATERSHED MANAGER.
- IF SITE IS APPROVED, REMOVE TEMPORARY DIVERSIONS, SILT FENCE, SEDIMENT BASINS, ETC., AND SEED OUT OR STABILIZE ANY RESULTING BARE AREAS. ALL REMAINING PERMANENT EROSION
- CONTROL DEVICES, SUCH AS VELOCITY DISSIPATORS, SHOULD NOW BE INSTALLED. WHEN VEGETATION HAS BECOME ESTABLISHED, CALL FOR A FINAL SITE INSPECTION BY THE
- WATERSHED MANAGER, JEEVAN NEUPANE, PE (919) 819-8907. OBTAIN A CERTIFICATE OF COMPLETION.

SEEDBED PREPARATION

- CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.
- . RIP THE ENTIRE AREA TO 6-INCH DEPTH.
- 3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM.
- APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW *).
- . CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP
- . SEED ON FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.
- . INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, RE-ESTABLISHED FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.
- . CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.
- *APPLY: AGRICULTURAL LIMESTONE 2 TONS/ACRE (3 TONS/ACRE IN CLAY SOILS) FERTILIZER - 1,000 LB/ACRE - 10-10-10 SUPERPHOSPHATE - 500 LB/ACRE - 20% ANALYSIS MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW ANCHOR - ASPHALT EMULSION @ 300 GALS/ACRE

NPDES Stormwater Discharge Permit for Construction Activities (NCGO1 NCDENR/Division of Energy, Mineral and Land Resource STABILIZATION TIMEFRAMES SITE AREA DESCRIPTION STABILIZATION TIMEFRAME EXCEPTIONS Perimeter dikes, swales, ditches, slopes 7 days If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed. Slopes steeper than 3:1 7 days for slopes greater than 50' in length 14 days None, except for perimeters and HQW Zones

Slopes 3:1 or flatte

Maintenance Requirements For Stockpile Areas

practical).

- 1. Seeding or covering stockpiles with tarps or mulch is required and will
- reduce erosion problems. Tarps should be keyed in at the top of the slope to keep water from running underneath the plastic.
- 2. If a stockpile is to remain for future use after the project is complete
- (builders, etc.), the financial responsible party must notify Wake County of a new responsible party for that stockpile.
- 3. The approved plan shall provide for the use of staged seeding and
- mulching on a continual basis while the stockpile is in use.
- 4. Establish and maintain a vegetative buffer at the toe of the slope (where

STOCKPILE DESIGN CRITERIA A. A 25-FOOT TEMPORARY MAINTENANCE AND ACCESS EASEMENT SHALL BE AROUND ALL PROPOSED STOCKPILES (EROSION CONTROL MEASURES SURROUNDING THE STOCKPILE SHALL BE SHOWN AT THE OUTER LIMIT OF THIS EASEMENT). STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25'FROM ADJACENT A NOTE SHALL BE PROVIDED ON THE APPROVED PLAN THAT STOCKPILE HEIGHT STOCKPILE SLOPES SHALL BE 2:1 OR FLATTER. APPROVED BMPS SHALL BE SHOWN ON A PLAN TO CONTROL ANY POTENTIAL SEDIMENT LOSS FROM A STOCKPILE STOCKPILING MATERIALS ADJACENT TO A DITCH, DRAINAGEWAY, WATERCOURSE, WETLAND, STREAM BUFFER, OR OTHER BODY OF WATER SHALL BE AVOIDED ALTERNATIVE LOCATION IS DEMONSTRATED TO BE UNAVAILABLE. ANY CONCENTRATED FLOW LIKELY TO AFFECT THE STOCKPILE SHALL BE DIVERTED TO AN APPROVED BMP OFF-SITE SPOIL OR BORROW AREAS MUST BE IN COMPLIANCE WITH WAKE UDO AND STATE REGULATIONS. ALL SPOIL AREAS OVER AN ACRE ARE REQUIRED HAVE AN APPROVED SEDIMENT CONTROL PLAN. DEVELOPER/CONTRACTOR SHALL WAKE COUNTY OF ANY OFFSITE DISPOSAL OF SOIL, PRIOR TO DISPOSAL. FILL OF FEMA FLOODWAYS AND NON-ENCROACHMENT AREAS ARE PROHIBITED EXCEPT OTHERWISE PROVIDED BY SUBSECTION 14-19-2 OF THE WAKE COUNTY UNIFIED DEVELOPMENT ORDINANCE (CERTIFICATIONS AND PERMITS REQUIRED). MAINTENANCE REQUIREMENTS TO BE NOTED ON THE PLAN SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE OF A NEW RESPONSIBLE PARTY FOR THAT STOCKPILE. K. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE. ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE PRACTICAL)

SEEDBED PREPARATION

- 1. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.
- 2. RIP THE ENTIRE AREA TO 6-INCH DEPTH.
- 3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM.
- 4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW *).
- 5. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP.
- 6. SEED ON FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING
- EQUIPMENT OR CULTIPACK AFTER SEEDING.
- 7. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH. 8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED.
- RE-ESTABLISHED FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES. 9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.
- *APPLY: AGRICULTURAL LIMESTONE 2 TONS/ACRE (3 TONS/ACRE IN CLAY SOILS) FERTILIZER - 1,000 LB/ACRE - 10-10-10 SUPERPHOSPHATE - 500 LB/ACRE - 20% ANALYSIS MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW ANCHOR - ASPHALT EMULSION @ 300 GALS/ACRE

SEEDING SCHEDULE

SHOULDERS, SIDE DITCHES, SLOPES (Maximum 3:1)

Date	Type*	Planting Rate
Aug 15 - Nov 1	Tall Fescue or Hard Fescue	300 lb./acre
Nov 1 - Mar 1	Tall Fescue and Abriuzzi Rye or Annual Rye	300 lb./acre
Mar 1 — Apr 15	Tall Fescue or Hard Fescue	300 lb./acre
Apr 15 — June 30	Hulled common Bermuda grass, Weeping Love Grass	25 lb./acre
July 15 - Aug 15	Tall Fescue <u>and</u> ***Browntop Millet *** <u>or</u> Sorghum—Sudan Hybrids	35 lb./acre

Consult Erosion Control Officer or NRCS for additional alternatives for vegetating denuded areas. The above vegetation rates are those which do well under local conditions; other seeding rate combinations are possible.

***<u>Temporary</u> — Reseed according to optimum season for desired permanent vegetation. Do not allow temporary cover to grow over 12 inches in height before mowing to keep fescue from being shaded out.

*Bahia grass shall not be used in City maintained areas.

SHOULDERS, SIDE DITCHES, SLOPES Slopes (3:1 and 2:1) (not mowed)

Date	Type*	Planting Rate
Mar 1 — June 1	Sericea Lespedeza (scarified)	50 lb./acre
Mar 1 — Apr 15	and Add Tall Fescue or	120 lb./acre
Mar 1 — June 30	Add Weeping Love Grass or	10 lb./acre
Mar 1 — June 30	Add Hulled Common Bermuda grass	25 lb./acre
June 1 — Sept 1	***Tall Fescue <u>and</u> ***Browntop Millet *** <u>or</u> Sorghum—Sudan Hybrids	120 lb./acre 35 lb./acre 30 lb./acre
Sept 1 — Mar 1	Sericea Lespedeza (unhulled/unscarified) and Tall Fescue Add Abruzzi Rye or Annual Rye	70 lb./acre 120 lb./acre 25 lb./acre

Consult Erosion Control Officer or NRCS for additional alternatives for vegetating denuded areas. The above vegetation rates are those which do well under local conditions; other seeding rate combinations are possible.

***<u>Temporary</u> — Reseed according to optimum season for desired permanent vegetation. Do not allow temporary cover to grow over 12 inches in height before mowing to keep fescue from being shaded out.

*Bahia grass shall not be used in City maintained areas.

Z:\Jobs\9900\Watkins Property\dwg_Working Dwgs\Phase 1\02. 3.0-3.1 General Notes And Schedules.dwg

EXISTING	NAME	PROPOSED
	- WATER LINE	
	- GAS LINE	
	- OVERHEAD ELECTRIC	
	- UNDERGROUND ELECTRIC	
	- OVERHEAD TELEPHONE	
	- UNDERGROUND TELEPHONE	
-	— STORM DRAIN	
	- SANITARY SEWER	
	FORCE MAIN	
	CURB & GUTTER LINE	
	SWALE/DITCH LINE	
	- STREAM LINE	
X	FENCE LINE	
	TREE LINE	
	FLOW LINE	
	TEMP DIVERSION LINE	
	CLEARING LIMITS	
	TREE FENCE	CONT. TO SECURE OF THE SECURE
	SILT FENCE LINE	
	- MINOR CONTOUR LINE	
320	- INDEX CONTOUR LINE	320
	 CENTERLINE 	***************************************
	- ADJACENT PROPERTY LINE	
	PROPERTY LINE	
	- RIGHT-OF-WAY LINE	
	- EASEMENT LINE	
	BUFFER ZONE LINE	- Aller Anna
	RIPARIAN BUFFER	
	100 YR. FLOOD ELEV.	Market and the second s
	BUILDING RESTRICTION FLOOD LINE	
	MATCH LINE	
	PHASE LINE	
	LEVEL SPREADER	
	LEVEL SPREADER	

LINETYPE LEGEND

UTILITY LEGEND SYMBOL

ABBREV.	SYMBOL	NAME
ARV PP	9	AIR RELEASE VALVE UTILITY POLE
WVPR	₩V	PROPOSED WATER VALVE
WVEX BOAPR BOA EX WLCROSS WLTEE	GV BOAO → H H	EXISTING WATER VALVE PROPOSED BLOW OFF ASSEMBLY EXISTING BLOW OFF ASSEMBLY WATERLINE CROSS WATERLINE TEE
FHPR	¾	PROPOSED FIRE HYDRANT
FHEX		EXISTING FIRE HYDRANT
MHPR MHEX		PROPOSED MAN HOLE EXISTING MAN HOLE
FESPR FESEX		PROPOSED FLARED END SECTION EXISTING FLARED END SECTION
REDPR REDEX		PROPOSED REDUCER EXISTING REDUCER
SANSERV		EXIST. SAN SEWER SERV
SANSERV	<u> </u>	PROPOSED SAN SEWER SERV CLEAN OUT
WSPR		PROPOSED WATER SERVICE
	COPP .	PROPOSED POWER POLE
	○	PROPOSED LIGHT POLE

	LOT IMPERV	IOUS AREAS
LOT SIZE;	IMPERVIOUS AREA	A: LOT NUMBERS;
50'-59'	3,650 S.F.	243-261
60'-69'	3,920 S.F.	44-48,236-242,262-269
70'-79'	4,650 S.F.	1-9,21-28,29-43,66-74
80'-99'	5,400 S.F.	10-20,49-59,75-86,90-9
100'/+	5,750 S.F.	60-65,87-89

SCM CONVERSION SEQUENCE

- WHEN ALL CONTRIBUTARY AREAS TO THE STORMWATER CONTROL MEASURE (SCM) HAVE BEEN STABILIZED CONTACT THE EROSION CONTROL OFFICER FOR PERMISSION TO CONVERT THE SEDIMENT BASIN TO A SCM.
- REMOVE ALL SEDIMENT FROM THE BASIN AND RESTORE GRADES TO DESIGNED CONFIGURATION, IF NEEDED.
- CONSTRUCT FOREBAY DIVIDERS AS SHOWN. MAKE ANY REPAIRS, ETC. NECESSARY TO THE OUTLET STRUCTURE. OUTLET PIPE, EMERGENCY OVERFLOW, ETC. EXAMINE RIP-RAP TO
- SEE IF REFRESHING OR CLEANING OF ROCK IS NECESSARY. REMOVE SKIMMER AND CLOSE OUTLET VALVE. CONTACT EROSION CONTROL OFFICER FOR APPROVAL CONTACT A LICENSED SURVEYOR FOR SURVEY OF AS-BUILT

CONDITIONS. NOTIFY ENGINEER-OF-RECORD FOR PREPARATION OF AS-BUILT DRAWINGS. Y:\Jobs\9900\Watkins Property\Documents\Reports\SCM Conversion

2/15/21 Sequence.docx

SITE PERMITTING APPROVAL

Water and Sewer Permits (If applicable) The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on

specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and

this plan. The material and Construction methods used for this project shall conform to the standards and

specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer

collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh Public Utilities Department Permit #

SHEET NO.

ら

JOB NUMBER:

CHECKED BY:

DRAWN BY:

OLE!

JRH

EDS

9/19/2019

3.0

Ditch Section (For Bottom Width = 0) (Not To Scale)

Trapezoidal Ditch / Swale Section (Not To Scale)

		SWALE DRAINAGE CHART-PHASE ONE											
Ditch I.D.	D.A., Ac.	c	i10, in/hr	Q10, cfs	Left Side Slope, Z Z:1	Right Side Slope, Z Z:1	Avg. Ditch Slope, %	Bottom Width	Ditch Lining	Manning, n *	Q10 Flow Depth, ft	Flow Velocity V10, fps	Calc.Shear Stress, ps
DS 1	0.31	0.30	7.22	0.66	3.00	3.00	3.8	0.00	Reinforced Mesh(Grass)	0.022	0.26	3.20	0.62
DS 2A	1.58	0.40	7.22	4.56	3.00	3.00	5.5	2.00	RipRap	0.037	0.38	3.88	1.29
DS 2B	1.18	0.40	7.22	3.41	3.00	3.00	5.5	2.00	RipRap	0.037	0.32	3.56	1.11
DS 2C	0.74	0.40	7.22	2.14	3.00	3.00	4.7	2.00	RipRap	0.037	0.26	2.93	0.77
DS 2D	3.32	0.40	7.22	9.59	3.00	3.00	2.2	2.00	RipRap	0.037	0.69	3.43	0.94
DS 3A	0.30	0.45	7.22	0.99	3.00	3.00	2.5	0.00	Reinforced Mesh(Grass)	0.022	0.35	3.18	0.55
DS 3B	0.95	0.48	7.22	3.29	3.00	3.00	1.5	1.00	Reinforced Mesh(Grass)	0.022	0.43	3.37	0.40
DS 3C	2.20	0.44	7.22	6.99	3.00	3.00	0.5	4.00	Reinforced Mesh(Grass)	0.022	0.50	2.52	0.16
DS 4A	1.40	0.44	7.22	4.45	3.00	3.00	0.5	2.00	Reinforced Mesh(Grass)	0.022	0.53	2.37	0.16
DS 4B	0.70	0.46	7.22	2.32	3.00	3.00	0.7	2.00	Reinforced Mesh(Grass)	0.022	0.34	2.22	0.15
DS 5A	2.40	0.32	7.22	5.54	3.00	3.00	1.8	2.00	Reinforced Mesh(Grass)	0.022	0.42	3.99	0.48
DS 5B	3.60	0.32	7.22	8.32	3.00	3.00	5.8	2.00	RipRap	0.037	0.50	4.69	1.83
DS 5C	6.00	0.33	7.22	14.30	3.00	3.00	2.0	2.00	RipRap	0.037	0.85	3.68	1.06
DS 6A	1.18	0.44	7.22	3.75	3.00	3.00	4.5	1.00	RipRap	0.037	0.45	3.56	1.26
DS 6B	2.21	0.44	7.22	7.02	3.00	3.00	4.5	2.00	RipRap	0.037	0.50	4.11	1.40
DS 6C	3.95	0.46	7.22	13.12	3.00	3.00	1.7	3.00	RipRap	0.037	0.75	3.32	0.80
DS 7A	0.20	0.45	7.22	0.65	3.00	3.00	1.2	0.00	Reinforced Mesh(Grass)	0.022	0.32	2.08	0.24
DS 7B	0.51	0.48	7.22	1.77	3.00	3.00	12.0	0.00	RipRap	0.037	0.37	4.29	2.77
DS 7C	0.78	0.46	7.22	2.59	3.00	3.00	4.0	0.00	RipRap	0.037	0.52	3.12	1.30
DS 7D	2.05	0.41	7.22	6.07	3.00	3.00	1.2	2.00	RipRap	0.037	0.55	3.04	0.41
DS 8A	0.52	0.38	7.22	1.43	3.00	3.00	4.0	0.00	Reinforced Mesh(Grass)	0.022	0.35	3.98	0.86
DS 8B	1.87	0.40	7.22	5.40	3.00	3.00	7.0	0.00	RipRap	0.037	0.57	4.37	2.47
DS 9	2.18	0.34	7.22	5.35	3.00	3.00	1.5	1.00	Reinforced Mesh(Grass)	0.022	0.54	3.84	0.51
DS 10	1.25	0.48	7.22	4.33	3.00	3.00	5.2	1.00	RipRap	0.037	0.47	3.93	1.53
DS 11	0.95	0.45	7.22	3.09	3.00	3.00	0.8	2.00	Reinforced Mesh(Grass)	0.022	0.39	2.54	0.19
DS 12	2.33	0.31	7.22	5.22	3.00	3.00	1.0	3.00	Reinforced Mesh(Grass)	0.022	0.41	3.07	0.26
DS 12A	0.95	0.45	7.22	3.09	3.00	3.00	0.8	2.00	Reinforced Mesh(Grass)	0.022	0.39	2.54	0.19
DS 13	1.05	0.45	7.22	3.41	3.00	3.00	7.0	1.00	RipRap	0.037	0.40	4.16	1.75
DS 14A	0.76	0.50	7.22	2.74	3.00	3.00	7.0	1.00	RipRap	0.037	0.35	3.86	1.53
DS 14B	0.90	0.46	7.22	2.99	3.00	3.00	4.0	0.00	RipRap	0.037	0.55	3.24	1.37
DS 15A	0.05	0.20	7.22	0.07	3.00	3.00	1.5	0.00	Reinforced Mesh(Grass)	0.022	0.15	1.39	0.14
DS 15B	0.28	0.38	7.22	0.77	3.00	3.00	9.0	0.00	RipRap	0.037	0.30	3.23	1.68
DS 15C	1.07	0.48	7.22	3.71	3,00	3.00	1.5	1.00	Reinforced Mesh(Grass)	0.022	0.46	3.50	0.43
DS 16	3.56	0.42	7.22	10.80	3.00	3.00	4.0	3.00	RipRap	0.037	0.55	4.29	1.37
DS 18A	0.44	0.55	7.22	1.75	3.00	3.00	1.0	0.00	Reinforced Mesh(Grass)	0.022	0.49	2.52	0.31
DS 18B	0.61	0.49	7.22	2.16	3.00	3.00	6.0	0.00	RipRap	0.037	0.46	3.52	1.72
DS 18C	0.67	0.30	7.22	1.45	3.00	3.00	1.0	0.00	Reinforced Mesh(Grass)	0.022	0.46	2.42	0.29
DS 18D	2.58	0.29	7.22	5.40	3.00	3.00	5.0	1.00	RipRap	0.037	0.52	4.08	1.62
DS 19	0.10	0.20	7.22	0.14	3.00	3.00	3.5	0.00	Reinforced Mesh(Grass)	0.022	0.15	2.12	0.33
DS 20	0.76	0.46	7.22	2.52	3.00	3.00	2.5	0.00	Reinforced Mesh(Grass)	0.022	0.47	3.88	0.73
DS 21A	0.80	0.54	7.22	3.12	3.00	3.00	1.3	1.00	RipRap	0.037	0.55	2.15	0.45
DS 21B	1.75	0.54	7.22	6.82	3.00	3.00	8.0	1.00	RipRap	0.037	0.52	5.16	2.60
DS 21C	2.13	0.53	7.22	8.15	3.00	3.00	12.0	2.00	RipRap	0.037	0.42	6.09	3.14
DS 21D	2.22	0.53	7.22	8.17	3.00	3.00	20.0	2.00	RipRap	0.037	0.36	7.26	4.54
DS 21E	2.52	0.50	7.22	9.10	3.00	3.00	4.3	3.00	RipRap	0.037	0.50	4.22	1.34
DS 22A	0.46	0.34	7.22	1.13	3.00	3.00	2.3	0.00	Reinforced Mesh(Grass)	0.037	0.35	3.05	0.50
DS 22B	1.90	0.28	7.22	3.84	3.00	3.00	1.0	2.00	Reinforced Mesh(Grass)	0.022	0.41	2.92	0.36
DS 23A	0.20	0.28	7.22	0.29	3.00	3.00	15.0	0.00	RipRap	0.022	0.20	3.17	1.87
DS 23B	1.15	0.46	7.22	3.82	3.00	3.00	2.0	1.00	Reinforced Mesh(Grass)	0.037	0.43	3.90	0.54
DS 23C	2.20	0.49	7.22	7.78	3.00	3.00	6.0	1.00	RipRap	0.022	0.59	4.80	2.21

Shear Stress=62.4(d)(Slope)

American Green Product (SC150BN): 70% Agri Straw & 30% Coconut Fiber with net; n=.022; Alowable Shear = 1.8 lb/s.f. Ref. Chow, V.T., Open Channel Hydraulics

*Grass-Fescue Lined; n=0.030; Good for V10 <4.0 fps

*Class B Riprap, 6" size; flow d < 2'; n=.037 *Coconut Fiber with net,n=0.02 (Mesh)

* Reinforced mesh linings where required per schedule above shall be North American Green model SC150BN or engineer approved equal and stabilized per manufacturers

Phase 1 Lot Areas

·····	,			,
LOT	SQUARE		LOT	<u>SQUARE</u>
NUMBER	FOOTAGE(SF)		NUMBER	FOOTAGE(S
-101110			1137113	<u>E)</u>
1	12,302		38	26,069
2	11,823		39	13,268
3	12,685		40	11,807
4	11,860		41	11,611
5	12,472		42	11,416
6	11,215		43	11,387
7	10,485		44	9,386
8	9,760		45	10,035
9	12,514	i da indire de la	46	9,087
10	16,836		47	9,103
11	26,326		48	10,702
12	23,748		49	13,150
13	14,031		50	13,304
14	10,240		51	14,902
15	10,668		52	16,621
16	11,948	Tally the second of the second	53	22 <i>,</i> 782
17	12,191		54	30,245
18	12,530		55	20,316
19	11,660		56	16,282
20	12,445		57	15,912
21	13,301		- 58	15,280
22	11,703		59	15,719
23	12,106		60	17,893
24	12,401		61	17,189
25	13,653		62	21,253
26	11,390		63	23,387
27	11,536		64	24,741
28	13,024		65	21,648
29	10,884		66	10,644
30	12,218		67	9,322
31	11,794	and the second of the second o	68	10,220
32	11,492		69	11,248
- 33	12,321		70	16,193
34	10,672		71	15,691
35	12,289		72	15,229
36	22,066		73	13,593
37	21,627		74	12,671

	1.07	<u>SQUARE</u>	
	LOT	FOOTAGE(SF	
	<u>NUMBER</u>)	
	75	13,603	
	76	13,659	
	77	14,283	
	78	14,098	
	79	12,800	
	80	12,800	
	81	12,549	
	82	10,868	
	83	11,715	
	84	13,687	
	85	11,867	
	86	12,952	
	87	15,621	
	88	16,829	
	89	20,972	
	90	26,460	
	91	23,983	
	92	25,886	
	93	16,970	
	94	13,478	
	95	13,514	
	236	14,310	
	237	13,261	
	238	13,988	
	239	12,571	
-17	240	9,789	
	241	9,769	
	242	11,085	
	243	9,616	
	244	8,250	
	245	8,250	
	246	8,950	
	247	9,988	
	248	11,480	
	249	12,244	
	250	12,929	

251 11,150

LOT NUMBER	SQUARE FOOTAGE(S F)	
252	8,341	3
253	7,912	
254	7,743	
255	7,74 5	
256	7,750	
257	7,750	
258	7,750	
259	7,753	
260	7,747	
261	9,168	
262	11,491	
263	10,075	
264	10,075	
265	10,075	
266	10,075	
267	10,075	
268	10,075	
269	10,075	

Downstream Structure	Upstream Structure	Pipe Size (in)	Length (ft)	Slope (%)	Downstream Rim Elev (ft)	Rim Elev (ft)	Downstream Invert (ft)	Upstream Invert (ft)	Q(10) Downstream Velocity (fps)
CB 104	CB 113	24	41.00	1.46	375.40	375.40	370.83	371.43	3.11
CB 104 A	CB 104	24	9.00	0.56	375.41	375.40	370.78	370.83	3.80
CB 113	CB 113 A	18	9.00	0.56	375.40	375.41	371.63	371.68	0.87
CB 113	FES INLET 114	18	21.22	1.77	375.40	371.96	371.63	372.00	2.23
CB 115	CB 104 A	24	141.50	0.49	377.42	375.41	370.08	370.78	3.64
CB 115	CB 120	15	225.66	3.88	377.42	386.20	371.73	380.48	10.41
CB 116	CB 117	15	45.96	1.00	386.20	388.01	381.29	381.75	3.31
CB 117	CB 118	15	27.00		388.01	388.01	381.95	382.22	2.92
CB 118	CB 119	15	45.96	1.00	388.01	388.76	382.42	382.88	2.11
CB 119	CB 119 A	15	41.00		388.76	388.76	383.08	383.49	2.05
CB 120	CB 116	15	41.00	1.00	386.20	386.20	380.68	381.09	3.60
CB 120	CB 121	15	45.95	0.50	386.20	387.58	381.79	382.02	4.10
CB 121	CB 122	15	27.00	0.52	387.58	387.58	382.22	382.36	2.12
CB 201	CB 201 A	24	74.47	4.86	369.20	371.70	362.52	366.14	3.60
CB 201 A	CB 202	24	27.00	1.25	371.70	371.70	366,34	366.68	3.75
CB 202	CB 202 A	24	196.53	1.47	371.70	375.74	366,88	369.76	3.72
CB 202 A	CB 202 B	24	42.53	0.53	375.74	378.17	370.16	370.39	4.54
CB 202 B	CB 202 C	24	27.00	1.02	378.17	378.17	370.59	370.86	3.91
CB 202 C	CB 203	18	36.28	2.48	378.17	377.61	371.36	372.46	4.34
CB 203	CB 204	15		0.50	377.61	378.11	372.46	372.64	0.66
CB 203	CB 205	15	97.02	1.30	377.61	379.65	372.46	373.72	4.10
CB 205	CB 206	15	70.24		379.65	381.08	373.92	374.97	3.98
CB 205 CB 206	YI 205 A CB 207	15 15	70.24	1.49	379.65 381.08	381.32 382.52	373.92 375.17	374.35 376.22	0.70 2.80
CB 206 CB 207 CB 213	YI 206 A YI 207 A	15 15	21.99	2.00	381.08 382.52	383.00 384.00	374.97 376.42	375.41 376.86	0.40 0.74
CB 214 CB 215	CB 214 CB 215 CB 216	18 18 15	92.63 110.85 136.23	3.89 3.34 1.15	371.13 374.86 377.69	374.86 377.69 379.16	365.87 369.68 373.78	369.48 373.38 375.34	3.76 3.45
CB 215	CB 218	15	27.00	0.52	377.69	377.69	373.58	373.72	0.96
CB 216	CB 217	15	69.92		379.16	379.84	375.54	376.06	2.18
CB 222 CB 222	CB 223 CB 225	18 15	62.62	1.84	381.79 381.79	381.17 383.00	374.20 374.20	375.35 378.70	8.74 10.45
CB 223	CB 228 FES 224	18	59.69	1.50	381.17 381.17	380.88 376.96	375.55 375.75	376,45 376,50	1.84
CB 225	CB 226	15	146.54	2.50	383.00	387.31	378.90	382.56	3.30
CB 226	CB 227	15	41.00		387.31	387.31	382.76	383.41	2.22
CB 228	CB 229	15 15	55.11 41.00	0.64	380.88 380.88	381.13 380.88	376.85 376.65	377.20 377.06	1.32
CB 230	CB 231	15	112.70	0.50	380.88	381.90	377.26	377.82	1.87
CB 251	CB 252	15	57.16		320.54	318.11	314.01	314.30	3.64
CB 254 CB 254	CB 255 YI 254 A	24	182.54 33.11	5.20	325.63 325.63	338.10 319.00	320.50 315.11	330.00 316.00	14.60 5.18
CB 255	CB 256	24	45.96	3.89	338.10	341.00	330.80	332.59	5.11
CB 256	CB 257	24	27.00	4.46	341.00	341.00	332.99	334.19	5.54
CB 257	CB 258	15	45.96	8.06	341.00	345.38	336.19	339,90	11.06
CB 257	CB 260	24	94.58	2.00	341.00	342.84	336.19	338,08	9.10
CB 258	CB 259	15	41.00	0.50	345.38	345.38	340.10	340.31	1.48
CB 260	YI 261	15	168.55	5.43	342.84	362.62	339.46	348.62	8.29
CB 260	YI 262	18	23.71	0.56	342.84	343.57	338.58	338.71	5.64
CB 263	CB 265	15	154.37	9.37	349.99	363.87	343.29	357.76	13.82
CB 263	YI 264	15	25.16	0.51	349.99	345.84	341.33	341.46	0.76
CB 265	CB 267	15	55.36	7.29	363.87	368.39	358.97	363.00	2.34
CB 265	YI 266	15	11.81	1.14	363.87	364.18	357.96	358.09	1.49
CB 302	CB 303	24	27.00	0.52	339.11	339.11	333.61	333.75	5.84
CB 303	CB 303 A	18	9.00	0.50	339.11	339.13	334.25	334.30	4.25
CB 303	CB 308	18	84.35	1.48	339.11	339.56	334.25	335.50	3.13
CB 303 A	CB 304	18	20.09	3.01	339.13	339.25	334.50	335.10	4.01
CB 304	CB 305	18	60.43	1.24	339.25	340.41	335.30	336.05	4.18
CB 305	CB 306	15	27.00	0.50	340.41	340.42	336.25	336.39	0.85
CB 305	CB 307	15	88.24	4.18	340.41	343.78	336.25	339.94	3.61
CB 307	CB 313	15	160.00	3.00	343.78	349.80	340.14	344.94	2.85
CB 308	CB 309	15	27.00	0.50	339.56	339.56	335.70	335.84	0.79
CB 308	CB 310	15	110.55	0.50	339.56	340.22	335.70	336.25	3.47
CB 310	CB 311	15	54.00		340.22	340.53	336.35	336.67	2.47
CB 310	YI 310 A	15	26.79	0.50	340.22	344.00	336.35	336.79	0.70
CB 311	CB 312	15	31.99		340.53	340.70	336.77	336.93	1.90
CB 313	YI 313 A	15	21.39	0.76	349.80	352.00	345.14	345.57	2.03
CB 315	CB 316	24	41.00		354.12	354.11	348.75	349.06	6.79
CB 316 CB 317	CB 317 CB 318	24	196.59 38.72	1.76	354.11 358.45	358.45 358.71	349.26 352.92	352.72 353.50	4.48 5.03
CB 318	CB 319	24	42.29	1.14	358.71	358.67	353.70	354.18	4.94
CB 319	CB 320	24	47.54	1.47	358.67	360.47	354.38	355.08	3.92
CB 320	CB 321	18	120.75	1.75	360.47	363.13	355.58	357.69	6.13
CB 321	CB 322 CB 323	15 18	44.32 85.22	0.73	363.13 363.13	363.51 365.47	357.89 357.89	358.22 359.59	0.67
CB 323	CB 324 CB 325	18 18	89.57 119.73	4.00	365.47 369.41	369.41 376.01	359.79 363.57	363.37 369.86	4.34 4.48
CB 325 CB 326	CB 326 CB 327	18	45.79 27.00	2.75	376.01 377.17	377.17 377.17	370.06 371.52	371.32 371.79	3.65 3.27
CB 327	CB 328	18	45.96	3.00	377.17	379.89	371.99	373.37	2.37
CB 328	CB 329	15	41.00	0.50	379.89	379.89	373.57	373.78	1.68
CB 753	CB 753 A	18	16.50	8.63	383.65	383.62	374.88	376.30	2.88
CB 753	HW 760	30	44.50	7.69	383.65	381.05	374.88	378.30	8.68
CB 753 A	CB 761	18	62.46	0.75	383.62	383.94	376.50	376.97	3.70
CB 757	CB 758	15	122.86	2.24	384.77	385.54	378.09	380.84	2.44
CB 757	CB 759	15	136.87	1.07	384.77	382.27	378.09	379.56	1.40
CB 757	FES 757 A	36	39.53	3.92	384.77	380.99	378.69	380.24	6.10
CB 758	FES 758 A	15	11.74	1.79	385.54	384.54	381.04	381.25	3.22
CB 759	CB 760	15	145.97	0.60	382.27	383.37	379.76	380.64	0.58
CB 761	CB 762	18	102.70	1.25	383.94	384.76	377.17	378.45	3,44
CB 762	CB 763	18	206.12	1.25	384.76	388.39	378.65	381.23	2,44
CB 771	CB 772	15	210.54	1.00	381.90	383.94	377.40	379.51	5.87
CB 771	CB 778	18	325.30	0.50	381.90	379.16	371.20	372.83	1.20
CB 772	CB 773	15	114.57	0.60	383.94	384.81	379.71	380.40	4.79
CB 773	CB 774	15	230.11		384.81	386.51	380.60	381.87	3.83
CB 774 CB 775	CB 775 CB 776	15 15	239.72	1.33	386.51 389.92	389.92 391.73	382.07 385.46	385.26 387.87	3.39 3.04
CB 776 CB 778	CB 777 CB 779	15 15	200.00	0.50	391.73 379.16	393.92 378.06	388.07 373.08	389.07 374.08	2.34
FES 200 FES 210	YI 131 YI 200 A	36 24	71.85	1.00	374.72 339.09	373.70 346.39	369.50 337.50	369.79 339.23	7.32
FES 210 FES 250 FES 250 A	YI 211 CB 251	36 15	82.81 30.18	0.99	340.80 315.56	346.50 320.54	337.50 313.50	338.33 313.80	10.27 4.90
FES 250 A	CB 254	36	59.36	1.03	318.97	325.63	313.50	314.11	9.17
FES 301	YI 301 A	24	30.32	0.49	313.98	311.96	306.50	306.65	6.65
FES 314	CB 315	24	57.61	2.00	350.15	354.12	344.50	345.65	10.03
FES 314 FES 5	JB 6 JB 751	18 54	26.54 108.29	-	350.15 371.24 369.98	354.12 374.96 376.40	369.00 369.00	345.65 369.53 369.65	8.45 9.64
FES 770 FES OS 1	CB 771 OS 1	18 18	250.89 55.00	1.00	369.76 371.25	376.40 381.90 371.25	368.50 365.62	371.00 365.90	6.56 4.57
FES SCM 2A FES SCM 2B	OS SCM 2A OS SCM 2B	42 24	80.04 100.00	0.62	336.00 311.66	340.50 317.50	332.50 309.50	333.00 310.00	8.71 3.91
FES SCM 3D	OS SCM 3D	18	60.00	3.33	339.31	348.75	339.00	341.00	5.73
FES SCM 3E	OS SCM 3E	18		1.79	303.50	310.00	302.00	303.00	4.61
JB 301-B	JB 301-C	24	72.00	8.37	328.09	335.64	317.32	323.35	16.05
JB 301-C	CB 302	24	71.36	9.33	335.64	339.11	324.75	331.41	4.32
JB 6	YI 7	18	208.42	0.95	374.96	377.90	370.60	372.58	6.37
JB 751	JB 752	42	191.24		376.40	378.05	370.15	371.55	6.57
JB 751	JB 754	42	267,49		376.40	385.67	369.85	371.00	5.52
JB 752	CB 753	36	233,12		378.05	383.65	371.75	374.68	6.46
JB 754	JB 755	36	140.09	1.50	385.67	381.75	371.95	373.35	9.98
JB 755	JB 756	36	115.52		381.75	385.67	373.55	375.28	6.31
JB 756	CB 757	36	53.83	5.59	385.67	384.77	375,48	378.49	6,56
YI 131	CB 115	36	21.54	0.42	373.70	377.42	369,89	369.98	3,94
YI 200 A	YI 200 B	24	36.16	7.85	346.39	348.50	341.33	344.17	15.55
YI 200 B	YI 200 C	24	117.71	7.59	348.50	362.50	346.37	355.30	15.36
YI 200 C	CB 201	24	49.50	7.98	362.50	369.20	357.50	361.45	15.66
YI 200 C YI 211 YI 211	YI 212 YI 219	18 24	84.74 154.31	9.90	346.50 346.50	369.20 364.69 354.00	357.50 341.00 340.20	361.45 349.39 348.80	15.66 15.34 5.85
YI 212	CB 213	18	86.00	6.12	364.69	371.13	357.31	362.57	12.91
YI 219	YI 220	24	95.43		354.00	360.50	349.00	354.80	5.15
YI 220 YI 221	YI 221 CB 222	24	210.27 130.00	5.38	360.50 370.40	370.40 381.79	355.00 366.52	366.32 368.10	5.53 4.91
YI 262	CB 263	18	118.34	·•	343.57	349.99	338.90	341.09	4.35

			R	IP-RAP PADS				
Date:	6/14/21		Kalas Falls	Phase 1				
Y:\9900/Watkins			i	Z. 10.000.000.000.000.000.000.000.000.000				
			gan and announced and an area	g NYSDOT M	ethod			
OUTLET	PIPE DIA.	VELOCITY	ZONE	STONE	STONE	WIDTH	LENGTH	DEPTH
NO.	(IN.)	(FPS)		SIZE	CLASS	(FT.)*	(FT.)	(IN.)
FES5	18	8.49	2	6"	В	6	9	18
FES101	24	6.48	2	6"	В	8	12	18
FES220	24	6.26	2	6"	В	8	12	18
FES770	18	11.69	3**	13"	1	6.5	12	24
FES SCM1A	18	4.45	1	3"	A	5.5	6	12
FES SCM2A	42	8.71	3**	13"	1 1	15.25	28	24
FES SCM2B	24	2.90	2**	6"	В	8	12	18
FES SCM3D	18	5.73	1	3"	A	5.5	6	12
FES SCM3E	18	4.61	2**	6"	В	6	9	18
FES750	54	9.70	3	13"	1	19.5	36	24
FES 130	36	6.69	2	6"	В	12	18	18
FES 250A	36	9.17	2	6"	В	12	18	18
FES 200	24	7.30	2	6"	В	8	12	18
FES 210	3.5	10.21	3	13"	4	4.0	7.4	7.4
	36	10.31	 		1	13	24	24
FES 301	24	6.66	2	6"	В	8	12	18
FES 314	24	10.04	2	6"	В	8	12	18
FES 250	15	4.90	1	3"	Α	4.75	5	12
*DS width, u				****			ground slope	

			RIP-F	RAP PADS,	PHASE 1			
Date:	8/21/2023			ine in the part				
Z:\Jobs\9900	\Watkins Prop	erty\Document	s\Schedules	\Ph 1. Mass G	rading\Sedime	ent Basin Rip-	Rap Pads, Ph. 1	JRH Rev 0821
			Using	NYSDOT IV	lethod			y tilly and its
OUTLET	PIPE DIA.	VELOCITY	ZONE	STONE	STONE	WIDTH	LENGTH	DEPTH
NO.	(IN.)	(FPS)		SIZE	CLASS	(FT.)*	(FT.)	(IN.)
			1.426					
SB#111	24	2.89	1	3"	А	7.5	8	12
SB#211	30	3.81	1	3"	A	9.25	10	12
SB#212	24	3.06	1	3"	Α	7.5	8	12
SB#213	24	3.70	1	3"	Α	7.5	8	12
SB#215	24	3.21	1	3"	Α	7.5	8	12
SB#218	24	3.26	1	3"	Α	7.5	8	12
SB#314	24	3.02	1	3"	Α	7.5	8	12
			······································					
Other**				3"	Α	3	6	12
*Downstr	eam width	, use 3 x pip	e diamete	er upstrear	n.			
**All sed	ment basir	s without ri	sers but v	vith a skim	mer			

Sediment Basin/Sediment Trap Schedule

Kalas Falls Phase 1, Part 2

Cells in Bold Text have been added since Jan 2023 for Mass Grading, Others were Approved prior to Jan 2023


Z:\9900\Watkins Property\Documents\Schedules\Ph. 1 Mass Grading\Compiled Previous & New Sediment Basin Schedule Ph. 1, Part 2-JRH Rev 082123


						JRH rev 082123						
Basin	Basin Bottom Top of Top of Spillway		Weir	Sediment	Bas	in Dimensi	ons	Skimmer	Skimmer	Anti-		
No.	Elev.	Dam	Riser	Elev.	Length	Basin	At Top	At Emerg	At Bott.	Size	Hole	Flotation
		Elev.	Elev.			Туре	of Dam	Spillway	of Basin		Size	Size*
SB#103	366.00	371.00	N/A	369.50	10'	Skimmer	64'x124'	58'x118'	44'x104'	3	1.25	N/A
SB#104	366.00	371.00	N/A	369.50	10'	Skimmer	49'x89'	43'x83'	29'x69'	2	1	N/A
SB#111	384.00	389.00	N/A	387.50	10'	Riser/Barrel: 15"/24"	31'x55'	25'X49'	11'x35'	N/A	N/A	24"x24"x7.5"
SB#205	344.00	349.00	N/A	347.50	10'	Skimmer	50'x94'	44'x88'	30'x74'	2	1	N/A
SB#210	387.00	391.00	N/A	389.50	10'	Skimmer	22'x47'	16'x33'	2'x19'	1.5	0.5	N/A
SB#210A	377.00	382.00	N/A	380.50	10'	Skimmer	39'X73'	33'X67'	19'X53'	2	0.75	N/A
SB#211	367.00	372.00	369.50	370.50	10'	Riser/Barrel: 24"/30"	45'x86'	39'x80'	25'x66	N/A	N/A	30"x30"x12"
SB#213	368.00	373.00	370.50	371.50	10'	Riser/Barrel: 18"/24"	42'x80	36'x74'	22'x60'	N/A	N/A	24"x24"x11"
SB#215	370.00	375.00	372.50	373.50	10'	Riser/Barrel: 18"/24"	36'X66'	30'X60'	16'X46'	N/A	N/A	24"x24"x11"
SB#216	345.00	350.00	N/A	348.50	10'	Skimmer	21'x36'	15'x30'	1'x16'	1.5	0.5	N/A
SB#218	306.50	311.50	309.00	310.50	10'	Riser/Barrel: 15"/24"	34'x55'	28'X59'	14'X45'	N/A	N/A	24"x24"x8"
SB#219	328.00	333.00	N/A	331.50	10'	Wake Custom: Rock / Gravel Filter	37'X68'	31'X62'	17'X48'	N/A	N/A	N/A
SB#306	342.00	347.00	N/A	345.50	10'	Skimmer	45'X84'	39'X78'	25'X64'	2	1	N/A
SB#307	309.00	314.00	N/A	312.50	10'	Skimmer	46'X86'	40'X80'	26'X66'	2	1	N/A
SB#310	365.00	370.00	N/A	368.50	10'	Skimmer	27'x49'	21'x43'	7'x29'	1.5	0.75	N/A
SB#311	363.00	368.00	N/A	366.50	10'	Skimmer	21'x36'	15'x30'	1'x16'	1.5	0.5	N/A
SB#313	330.00	355.00	N/A	33.50	10'	Skimmer	26'x49'	20'x43'	6'x29'	1.5	0.5	N/A
SB#314	331.50	336.50	334.00	335.00	10'	Skimmer	29'x55'	23'x49'	9'X36'	1.5	0.75	N/A
										n digeleji. J		
SB#101	Refer to Sheet 4.7 Kalas Falls Phase 1 for Geometrics of Construction, Risers, Spillway, etc.							2	1.5	N/A		
SB#201	Refer to Sheet 4.8 Kalas Falls Phase 1 for Geometrics of Construction, Risers, Spillway, etc.								3	1.5	N/A	
SB#202	Refer to Sheet 4.9 Kalas Falls Phase 1 for Geometrics of Construction, Risers, Spillway, etc.							4	2	N/A		
SB#304		······		***************************************		eometrics of Construction, Risers, Spillway, etc.				3	1.5	N/A
SB#305	Refer	to Sheet	4.11 Kala	s Falls Phas	se 1 for Ge	eometrics of Construction, Risers, Spillway, etc.				3	1.75	N/A


Z:\Jobs\9900\Watkins Property\dwg_Working Dwgs\Phase 1\02. 3.0-3.1 General Notes And Schedules.dwg





JOB NUMBER: 9900 CHECKED BY: JRH DRAWN BY: EDS 9/19/2019 DATE:










































































PROPOSED LINETYPE LEGEND	EXISTING LINETYPE LEGEND UTILITY LEGEND	6.3 6.
PROPOSED BUILDING SETBACK PROPOSED EASEMENT PROPOSED 3'/5' CORUE PROPOSED RIGHT OF WAY PROPOSED ROAD CL PROPOSED 30" CURB AND GUTTER PROPOSED SANITARY SEWER PROPOSED WATERLINE	PROPERTY BOUNDARY EXISTING TREE LINE EXISTING WETLAND EXISTING 50' NRB CENTERLINE OF STREAM EXISTING WATER ELEVATION EXISTING RIGHT OF WAY PROPOSED MANHOLE OR J PROPOSED SEWER SERVIC PROPOSED TARCH BASIN PROPOSED FLARED END S PROPOSED FIRE HYDRANT PROPOSED WATER SERVIC PROPOSED WATER SERVIC PROPOSED WATER VALVE	SECTION T CE
30' COR UTILITY EASEMENT FUTURE FUTURE FUTURE FOR BOLD FO	WORMAT (17) 40 (15) 150 (15) 1	
S.S. OUTFALL TO BE BUILT WITH PH. 1. (333) (333) (333) (330) (205)	EXISTING WETLANDS 2: BLDG. RESTRICTION	
FUTURE 234 SCM 3C SCM EASEMENT FUTURE 233 FUTUR PART OS4	PUBLIC ASSEMENT ASSEMENT	
232 FUTURE PHASE 3	S.S. OUTFALL TO- IBE BUILT WITH PH. 1. Self- Graph 25415 Application of the content of the con	GENERAL NOTE: 1. NO DRAINAGE IN THE PHASE 3 AREA WHICH INCLUDES THE CULVERT CROSSING IS TO BE CONSTRUCTED WITH PHASE 1. 2. NO ADDITIONAL UTILITY EXTENSIONS IN THE PHASE 3 AREA ARE INCLUDED WITH THIS PHASE. THE ONLY UTILITY EXTENSION IN THE PHASE 3 AREA TO BE CONSTRUCTED WITH PHASE 1 IS MH200-MH206.
230 20' DRAINAGE EASEMENT 230 8"X8"X8" 3-8" G.V. PARK 18783 63 18793 63 18793 63	BND OF PH.1 S.S. END OF PH.1 S.S. END OF PH.1 S.S. CONSTRUCTION PI 204.36/36 (208)	GRAPHIC SCALE 1"=50' O 50 100 150 The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit# S—4824
228	Proposed 30 COR S.S. EASEMENT	The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #


JOB NUMBER: 9900
CHECKED BY: JRH
DRAWN BY: BAH
DATE: 9/19/2019


SHEET NO.


6.6


City of Raleigh Development Approval

Raleigh Water Review Officer










FALLS BLUFF DR. 41' B-B (60' ROW) STA. 33+00-40+00



GENERAL NOTE:

1. ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH IS TO BE SDR 26
WITH #67 STONE FOR THE FIRST FOOT OF BACKFILL ABOVE THE PIPE
CROWN UNLESS OTHERWISE NOTED.

		60.0' PUBLIC ROW	
2. L MAX	0.02	5.5	2. 1 May
	PAVEMENT DESIGN: 8" CABC OTE: 3" S9.5B	CL 30" CONCRETE CURB & GUTTER	

1. NORMAL CROWN OF 0.02 UNLESS OTHERWISE DIRECTED 2. ASPHALT WILL BE INSTALLED AT A MIN. 1.5" LIFTS. TYPICAL SECTION

JOB NUMBER: 9900

CHECKED BY: JRH DRAWN BY: BAH 4/24/2020

Utilities Handbook: City of Raleigh Public Utilities Department Permit # <u>W—3784</u>

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION ectronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any


The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public


The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The $material \ and \ Construction \ methods \ used \ for this \ project \ shall \ conform \ to \ the \ standards \ and \ specifications \ of \ the \ City's \ Public$


Utilities Handbook. City of Raleigh Public Utilities Department Permit $\#_S-4824$

Raleigh Water Review Officer

modification to this approval once issued will invalidate this approval. City of Raleigh Development Approval








OUTFALL 'D'

OUTFALL "D" MH150 THRU 126





The City of Raleigh consents to the connection and extension of the City's **Public Sewer System** as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. **City of Raleigh Public Utilities Department Permit #** _S—4824_

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

GENERAL NOTE:

1. ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH IS TO BE SDR 26 WITH #67 STONE FOR THE FIRST FOOT OF BACKFILL ABOVE THE PIPE CROWN UNLESS OTHERWISE NOTED.

Raleigh Water Review Officer

Its valid only upon the signature of a City of

10.0

JOB NUMBER: 9900

BAH


4/24/2020


Associatesvd., Suite 2 919-469-


CHECKED BY: JRH

DRAWN BY:


DATE:







ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH IS TO BE SDR 26 WITH #67 STONE FOR THE FIRST FOOT OF BACKFILL ABOVE THE PIPE CROWN UNLESS OTHERWISE NOTED.



DATE: 4/24/2020

JOB NUMBER: 9900

CHECKED BY: JRH DRAWN BY: BAH

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # <u>S-4824</u>


The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # <u>W-3784</u> CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


lectronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans, Any work authorized by this approval must roceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any nodification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

14.0





GENERAL NOTE:

1. ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH IS TO BE SDR 26
WITH #67 STONE FOR THE FIRST FOOT OF BACKFILL ABOVE THE PIPE
CROWN UNLESS OTHERWISE NOTED.

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Publi Utilities Handbook. City of Raleigh Public Utilities Department Permit # <u>S-4824</u>

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook: City of Raleigh Public Utilities Department Permit # <u>W-3784</u> CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must oceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval,

City of Raleigh Development Approval

SEAL 9810

JOB NUMBER: 9900 CHECKED BY: JRH

4/24/2020


DRAWN BY: DATE:


160


1. ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH IS TO BE SDR 26 WITH #67 STONE FOR THE FIRST FOOT OF BACKFILL ABOVE THE PIPE CROWN UNLESS OTHERWISE NOTED. 1. ALL SANITARY SEWER PIPE GREATER THAN 12' DEPTH
IS TO BE SDR 26 WITH #67 STONE FOR THE FIRST FOOT
OF BACKFILL ABOVE THE PIPE CROWN UNLESS
OTHERWISE NOTED.
2. NO DRAINAGE IN THE PHASE 3 AREA WHICH INCLUDES
THE CULVERT CROSSING IS TO BE CONSTRUCTED WITH 3. NO ADDITIONAL UTILITY EXTENSIONS IN THE PHASE 3
AREA ARE INCLUDED WITH THIS PHASE. THE ONLY
UTILITY EXTENSION IN THE PHASE 3 AREA
TO BE CONSTRUCTED WITH PHASE 1 IS MH200-MH206. -FUTURE PHASE 3 SEWER EXTENTION. OUTFALL "G" MH204A THRU 206 SANITARY S PLAN FUTURE RD. GRADE— PHASE 3 MANHOLE 205 (4 STA. - 22+63.59 GROUND 340.26 TOP 341.76 MANHOLE 207 STA. - 26+16. GROUND 343.6 TOP 345.10 ~~____ MANHOLE 204A (STA. - 19+63.59 GROUND 340.11 JOB NUMBER: 9900 DIA. CHECKED BY: JRH DRAWN BY: DATE: 4/24/2020 683 MANHOL STA. – GROUND TOP 33 ____ 163.66 LF OF 12" PVC @ 0.52% 188.95 LF OF 12" PVC @ 0.52% 300.0 LF OF 12" DIP @ 0.94% 3333 3344 44... INV OUT 323.03 INV IN 323.23 The City of Raleigh consents to the connection and extension of the City's **Public Sewer System** as shown on this plan. The naterial and Construction methods used for this project shall conform to the standards and specifications of the City's Public Itilities Handbook. City of Raleigh Public Utilities Department Permit # <u>S—4824</u> SEAL ⁽ 9810 The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The NOINE EN naterial and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # _W — 3784 _
CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION 6.15-21 lectronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City o Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval mus SHEET NO. proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Ar modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval


Raleigh Water Review Officer









CB 771 TO FES 770







395 390 PROPOSED GRADE 385 EXISTING GRADE 10 YR. HGL 25 YR. HGL 375 42' RCP III @ 0.58% 191 24LF 48"RCP III @ 0.60% 108.29LF 370 365 365 10+00 +50 11+00 +50 12+00 +50 13+00



1832 ROI JOB NUMBER: CHECKED BY: DRAWN BY: DATE:




FES 757 TO FES 750







JOB NUMBER: CHECKED BY: DRAWN BY: DATE: 0


1832 RO WAKE CO





18.3





































CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

*** 3 Days Before Digging ***
North Carolina 811
811 or 1-800-632-4949
Remote Ticket Entry
http://nc811.org/remoteticketentry.htm

SHEET NO.:

JOB NUMBER: 9900

DRAWN BY: EDS

CHECKED BY:

SHEET TITLE:

DATE:

X11

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


KALAS FALLS
PHASE 1
1832 ROLESVILLE ROAD
WAKE COUNTY, NC


9/19/2019


CROSS-SECTION


STA:


47+00























SITE PERMITTING APPROVAL

Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # S-4824

- The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # <u>W-3784</u>
- The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. my work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval ____


811 or 1-800-632-4949 Raleigh Water Review Officer Remote Ticket Entry http://nc811.org/remoteticketentry.ht

North 81 Carolina www.nc.811.019 *** 3 Days Before Digging ' North Carolina 811

SHEET NO .:








STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE (EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSEI ARCHITECTS AND ENGINEERS. REPRODUCTIO OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


32 W


CHECKED BY: DRAWN BY: DATE: SHEET TITLE:


JOB NUMBER:


KALAS FALLS CIVIL DETAILS

























Water and Sewer Permits (If applicable) The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # S-4824

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # W-3784

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

North 81 Carolina North Carolina 811

811 or 1-800-632-4949

Remote Ticket Entry ttp://nc811.org/remoteticketentry.h SHEET NO.:

AMERICAN ENGINEERING **ASSOCIATES** & SOUTHEAST

DETAIL SELECTION ONLY


STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE O EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


> ROA, ROLAKE


1832 WA


JOB NUMBER: CHECKED BY: DRAWN BY:


> SHEET TITLE: KALAS FALLS **CIVIL DETAILS**























Water and Sewer Permits (If applicable)

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit # ____W-3784_____

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval ____

Raleigh Water Review Officer


North 81 Carolina *** 3 Days Before Digging * North Carolina 811

811 or 1-800-632-4949

Remote Ticket Entry

http://nc811.org/remoteticketentry.

CIVIL DETAILS



STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE O EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

KALAS FALLS

JOB NUMBER:


CHECKED BY:


DRAWN BY:

SHEET TITLE:

DATE:

SHEET NO.: CD3





*Horizontal staple spacing should be altered if necessary to allow staples to secure the critical points along the channel surface.

Instructions

- 1. Prepare soil before installing rolled erosion control products (RECPs), including any necessary application of lime, fertilizer, and seed. Ground surface must be free of debris, rocks, clay clods and raked smooth sufficient to allow intimate contact of the RECP with the soil over the entirety of the installation
- 2. Begin at the top of the channel by anchoring the RECPs in a 6" (15 cm) deep X 6" (15 cm) wide trench with approximately 12" (30 cm) of RECPs extended beyond the up-slope portion of the trench. Use ShoreMax mat at the channel/culvert outlet as supplemental scour protection as needed. Anchor the RECPs with a row of staples/stakes/pins approximately 12" (30 cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Apply seed to the compacted soil and fold the remaining 12" (30 cm) portion of RECPs back over the seed and compacted soil. Secure RECPs over compacted soil with a row of staples/stakes/pins spaced approximately 12" (30 cm) apart across the width
- 3. Roll center RECPs in direction of water flow in bottom of channel. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes/pins in appropriate locations as shown in the staple pattern guide. 4. Place consecutive RECPs end-over-end (Shingle style) with

of the RECPs.

- a 4"- 6" (10 15 cm) overlap. Use a double row of staples staggered 4" apart and 4" on center to secure RECPs. 5. Full length edge of RECPs at top of side slopes must be anchored with a row of staples/stakes/pins spaced at S_T apart in a 6" (15 cm) deep X 6"(15 cm) wide trench. Backfill and compact the trench after stapling.
- 6. Adjacent RECPs must be overlapped approximately 4"- 6" (10 - 15 cm) and secured with staples/stakes/pins at S_T . 7. In high flow channel applications a staple check slot is recommended at 30 to 40 foot (9 -12m) intervals. Use a double row of staples staggered 6" (15 cm) apart and 12" (30 cm) on center over entire width of the channel.
- 8. The terminal end of the RECPs must be anchored with a row of staples/stakes/pins spaced at S_T apart in a 6" (15 cm) deep X 6" (15 cm) wide trench. Backfill and compact the trench after stapling.
- 9. Fasteners should provide a minimum of twenty pounds of pullout resistance. Six-inch (10 cm) X one-inch (2.5 cm) eleven gauge staples are typically adequate. In loose soils, longer staples may be necessary, twist pins can provide the greatest pullout resistance. In hard or rocky soils, straight pins may by used where staples or twist pins are refused, provided the minimum pullout requirements are met. Bio-degradable fasteners shall not be used with VMax (TRM) or TMax (HPTRM) materials.

Staple Pattern Guide Unroll Underneath Roll Overlap

Pin / Staple / Twist Pin, as

	Staple Pattern
Dimension	E La
W_{T}	20" (50 cm)
L _T	20" (50 cm)
S _T	18" (45 cm)
Nominal Frequency	3.8 / SY

Direction ENGINEERING ASSOCIATES SOUTHEAST appropriate for field conditions

12" (30 cm)

SITE PERMITTING APPROVAL

The City of Raleigh consents to the connection and extension of the City's Public Sewer System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and

specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection and extension of the City's **Public Water System** as shown on

this plan. The material and Construction methods used for this project shall conform to the standards and

specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

The City of Raleigh consents to the connection to its public sewer system and extension of the private sewer

conform to the standards and specifications of the City's Public Utilities Handbook.

collection system as shown on this plan. The material and constructions methods used for this project shall

Water and Sewer Permits (If applicable)

City of Raleigh Public Utilities Department Permit # _

<u>S-4824</u>

____W-3784____

Instructions

- 1. Prepare soil before installing rolled erosion control products (RECPs), including any necessary application of lime, fertilizer, and seed. Ground surface must be free of debris, rocks, clay clods and raked smooth sufficient to allow intimate contact of the RECP with the soil over the entirety of the installation.
- 2. Begin at the top of the slope by anchoring the RECPs in a 6" (15 cm) deep X 6" (15 cm) wide trench Anchor the RECPs with a row of staples/stakes/pins spaced at S_T apart in the bottom of the trench. Backfill and compact the trench after stapling and fold the roll over downslope. Secure RECPs over compacted soil with a row of staples/stakes/pins spaced at S_T apart across the width of the RECPs.
- 3. Roll the RECPs (A) down or (B) horizontally across the slope. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes/pins in appropriate locations as shown in the staple pattern guide. RollMax RECPs and ECBs should utilize Staple Pattern C, TRMs and VMax materials should utilize Staple Pattern D.
- 4. The edges of parallel RECPs must be stapled with approximately 4" - 6" (10 - 15 cm) overlap. 5. Consecutive RECPs spliced down the slope must overlapped with the upstream mat atop the downstream mat (shingle style). The overlap should
- be 4" 6" (10 15 cm). 6. At the terminal end, secure each mat across the width with a row of staples/stakes/pins spaced at S_T . If exposed to flow, foot traffic, wind uplift or other disruption, trench the terminal end in as shown in
- 7. Fasteners should provide a minimum of twenty pounds of pullout resistance. Six-inch (10 cm) X one-inch (2.5 cm) eleven gauge staples are typically adequate. In loose soils, longer staples may be necessary, twist pins can provide the greatest pullout resistance. In hard or rocky soils, straight pins may by used where staples or twist pins are refused, provided the minimum pullout requirements are met. Bio-degradable fasteners shall not be used with VMax (TRM) or TMax (HPTRM) materials.

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.


Any work authorized by this approval must proceed in accordance with the plans kept on file with the

City. This electronic approval may not be edited once issued. Any modification to this approval once

Raleigh Water Review Officer

issued will invalidate this approval.

City of Raleigh Development Approval



Staple Pattern

Guide

Pin / Staple / Twist Pin, as

appropriate for field conditions

Roll Overlap

Underneath

	Staple Pattern		
Dimension	C	D	
W _T	30" (75 cm)	24" (60 cm)	
L _T	30" (75 cm)	20" (50 cm)	
S _T	18" (45 cm)	18" (45 cm)	
Nominal Frequency	1.7 / SY	3.0 / SY	
Application	ECB (Degradable)	TRM (Permanent)	
*Note: Staple Pattern A and B used prior to 8/201 have been discontinued.			

Direction

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE O EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSEI ARCHITECTS AND ENGINEERS. REPRODUCTIO THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED

STIPULATION FOR REUSE

AND MAY BE CONTRARY TO THE LAW.

JOB NUMBER: CHECKED BY: DRAWN BY: DATE:

KALAS FALLS **CIVIL DETAILS**

CD4

Carolina (1) North Carolina 811 811 or 1-800-632-4949

Remote Ticket Entry

http://nc811.org/remoteticketentry.l

SHEET NO.:

ShoreMax

STEEP CHANNEL CHUTE/SPILLWAY DETAIL

' ShoreMax mats can be installed over a variety of underlayments including: sod, turf reinforcement mats (TRMs), geotextiles, and in some cases erosion control blankets (ECBs).

Prepare soil before installing erosion control products, including any necessary application of lime, fertilizer, and seed (when installing TRM or ECB underlayment).

Install turf reinforcement mat (TRM) over prepared soils according to manufacturer's recommendations Place ShoreMax mat in the bottom of the channel over the installed TRM (figure 1). The ShoreMax mat should be installed up to the appropriate elevation on the side slope as determined by the engineer. When using multiple panels, connect the panels using the Integrated Panel Interlock

4. For channels carrying continuous water flows, an appropriate geotextile should be placed under the ShoreMax mat for submerged applications (figure 1b). Place staples/anchors in the appropriate pattern. Perimeter staples can be shared between two adjacent panels. In soft or

for additional details. 5. At beginning of channel and areas where significant concentrated flows are directed onto the ShoreMax mat, place 1 staple/pin per linear foot along the leading edge of the ShoreMax system, resulting in 1 staple/pin on each corner and gridline (figure 3).

Drawn on: 5-4-17

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

If no daily rain gauge observations are made during weekend or

holiday periods, and no individual-day rainfall information is

attended days (and this will determine if a site inspection i

needed). Days on which no rainfall occurred shall be recorded as

"zero." The permittee may use another rain-monitoring device

below. When adverse weather or site conditions would cause the safety of the inspection

personnel to be in jeopardy, the inspection may be delayed until the next business day on

greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be

performed upon the commencement of the next business day. Any time when inspections

Inspection records must include:

which it is safe to perform the inspection. In addition, when a storm event of equal to or

Daily rainfall amounts

approved by the Division.

Identification of the measures inspected

. Name of the person performing the inspection

Indication of whether the measures were operating

Description, evidence, and date of corrective actions taken.

Evidence of indicators of stormwater pollution such as oil

Description, evidence, and date of corrective actions taken

sible sedimentation is found outside site limits, then a recor

Actions taken to clean up or stabilize the sediment that has left

sheen, floating or suspended solids or discoloration,

3. An explanation as to the actions taken to control future

If the stream or wetland has increased visible sedimentation or

Description, evidence and date of corrective actions taken, and

Regional Office per Part III, Section C, Item (2)(a) of this permit

Records of the required reports to the appropriate Division

stream has visible increased turbidity from the construction

The phase of grading (installation of perimeter E&SC

drainage facilities, completion of all land-disturbing

activity, construction or redevelopment, permanen

Documentation that the required ground stabilization

timeframe or an assurance that they will be provided as

measures have been provided within the required

measures, clearing and grubbing, installation of storm

activity, then a record of the following shall be made:

5. Description of maintenance needs for the measure,

Identification of the discharge outfalls inspected,

Name of the person performing the inspection

i. Indication of visible sediment leaving the site,

event > 1.0 inch in | 2. Description, evidence, and date of corrective actions taken, and

Date and time of the inspection,

Date and time of the inspection

of the following shall be made

the site limits.

ground cover).

soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

SECTION A: SELF-INSPECTION

(1) Rain gauge

naintained in

good working

(2) E&SC

Measures

discharge

(4) Perimeter of

wetlands onsite

or offsite

(where

accessible)

(6) Ground

stabilization

measures

were delayed shall be noted in the Inspection Record.

(during normal

business hours)

At least once per

and within 24

hours of a rain

24 hours

(3) Stormwater At least once per

7 calendar days

7 calendar days

event > 1.0 inch in

hours of a rain

and within 24

hours of a rain

and within 24

hours of a rain

event > 1.0 inch in

After each phase

of grading

24 hours

24 hours

event ≥ 1.0 inch in

Self-inspections are required during normal business hours in accordance with the table

Item to Document

(d) The maintenance and repair

1. E&SC Plan Documentation The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Documentation Requirements

Complete, date and sign an inspection report.

(a) Each E&SC measure has been installed | Initial and date each E&SC measure on a copy and does not significantly deviate from the of the approved E&SC plan or complete, date locations, dimensions and relative elevations | and sign an inspection report that lists each E&SC measure shown on the approved E&SC shown on the approved E&SC plan. plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation. (b) A phase of grading has been completed. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase Initial and date a copy of the approved E&SC (c) Ground cover is located and installed in accordance with the approved E&SC plan or complete, date and sign an inspection eport to indicate compliance with approved ground cover specifications.

requirements for all E&SC measures have been performed. Initial and date a copy of the approved E&SC (e) Corrective actions have been taken to E&SC measures. plan or complete, date and sign an inspection report to indicate the completion of the corrective action 2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

(a) This General Permit as well as the Certificate of Coverage, after it is received.

(b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

shall not commence until the E&SC plan authority has approved these items, (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include

properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems, (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,

(e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

SELF-INSPECTION, RECORDKEEPING AND REPORTING SELF-INSPECTION, RECORDKEEPING AND REPORTING

> **SECTION C: REPORTING** 1. Occurrences that Must be Reported

Permittees shall report the following occurrences: (a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if: They are 25 gallons or more,

 They are less than 25 gallons but cannot be cleaned up within 24 hours, They cause sheen on surface waters (regardless of volume), or

• They are within 100 feet of surface waters (regardless of volume).

PART III

Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

(e) Noncompliance with the conditions of this permit that may endanger health or the

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800)

Reporting Timeframes (After Discovery) and Other Requirements (a) Visible sediment • Within 24 hours, an oral or electronic notification deposition in a Within 7 calendar days, a report that contains a description of the stream or wetland sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sedimentrelated causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. (b) Oil spills and Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and release of hazardous location of the spill or release. substances per Item 1(b)-(c) above A report at least ten days before the date of the bypass, if possible (c) Anticipated The report shall include an evaluation of the anticipated quality and bypasses [40 CFR 122.41(m)(3)] effect of the bypass (d) Unanticipated Within 24 hours, an oral or electronic notification Within 7 calendar days, a report that includes an evaluation of the bypasses [40 CFR 122.41(m)(3)] quality and effect of the bypass. (e) Noncompliance • Within 24 hours, an oral or electronic notification with the conditions | • Within 7 calendar days, a report that contains a description of the of this permit that noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not may endanger health or the been corrected, the anticipated time noncompliance is expected to environment[40 continue: and steps taken or planned to reduce, eliminate, and (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal CFR 122.41(I)(7)1 prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6). • Division staff may waive the requirement for a written report on a

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/

DETAIL

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

PH: 800-772-204

www.nagreen.com

pplementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

5401 St. Wendel - Cynthiana Rd.

Poseyville, IN 47633

Required Ground Stabilization Timeframes many calendar Timeframe variations Site Area Description days after ceasing land disturbance (a) Perimeter dikes, swales, ditches, and None perimeter slopes High Quality Water (HQW) Zones If slopes are 10' or less in length and are (c) Slopes steeper than not steeper than 2:1, 14 days are -7 days for slopes greater than 50' in ength and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, (d) Slopes 3:1 to 4:1 ditches, perimeter slopes and HQW -10 days for Falls Lake Watershed 7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones (e) Areas with slopes -10 days for Falls Lake Watershed unless flatter than 4:1

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

there is zero slope

GROUND STABILIZATION SPECIFICATION

without temporary grass seed

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below

- Permanent Stabilization Temporary grass seed covered with straw or
 Permanent grass seed covered with straw or other mulches and tackifier other mulches and tackifiers Hydroseeding Geotextile fabrics such as permanent soil Rolled erosion control products with or reinforcement matting
- Appropriately applied straw or other mulch
 Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion

Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- . Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures. Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging Store flocculants in leak-proof containers that are kept under storm-resistant cover

EQUIPMENT AND VEHICLE MAINTENANCE Maintain vehicles and equipment to prevent discharge of fluids.

consult an independent professional for further design guidance.

- Provide drip pans under any stored equipment Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- Collect all spent fluids, store in separate containers and properly dispose as
- hazardous waste (recycle when possible)
- Remove leaking vehicles and construction equipment from service until the problem

Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff
- from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow. Dispose waste off-site at an approved disposal facility

9. On business days, clean up and dispose of waste in designated waste containers.

- PAINT AND OTHER LIQUID WASTI Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available
- 3. Contain liquid wastes in a controlled area. 4. Containment must be labeled, sized and placed appropriately for the needs of site. 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place
- on a gravel pad and surround with sand bags. Provide staking or anchoring of portable toilets during periods of high winds or in high
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

ACTUAL LOCATION DETERMINED CLEARLY MARKED SIGNAGE 2. THE CONCRETE WASHOUT NOTING DEMCE (18"X24" MIN.) STRUCTURES SHALL BE MAINTAINED I ACTUAL LOCATION DETERMINED IN FIELDONCRETE WHEN THE LIQUID AND/OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY TO PROVIDE ADEQUATE 2. THE CONCRETE WASHOUT STRUCTURES HOLDING CAPACITY WITH A MINIMUM 12 INCHES OF FREEBOARD. AND/OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY. 3.CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARY MARKED WITH SIGNAGE NOTING DEVICE. 3.CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARY MARKED WITH SIGNAGE NOTING DEVICE. BELOW GRADE WASHOUT STRUCTURE NOT TO SCALE ABOVE GRADE WASHOUT STRUCTURE

ONSITE CONCRETE WASHOUT STRUCTURE WITH LINER

CONCRETE WASHOUTS


- Do not discharge concrete or cement slurry from the site. Dispose of, or recycle settled, hardened concrete residue in accordance with local
- and state solid waste regulations and at an approved facility. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within
- lot perimeter silt fence. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two
- types of temporary concrete washouts provided on this detail. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must
- be pumped out and removed from project. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary
- products, follow manufacturer's instructions. 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.

4. Do not stockpile these materials onsite.

- AZARDOUS AND TOXIC WASTE Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment. 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.



Water and Sewer Permits (If applicable) The City of Raleigh consents to the connection and extension of the City's **Public Sewer System** as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit# Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

www.nagreen.com

The City of Raleigh consents to the connection and extension of the City's Public Water System as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

Poseyville, IN 47633

The City of Raleigh consents to the connection to its public sewer system and extension of the **private sewer** City of Raleigh Development Approval collection system as shown on this plan. The material and constructions methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #

erosion control products (RECPs) including any necessary application o lime, fertilizer, and seed.

.Begin at the top of the channel by anchoring the RECPs in a 6"(15cm) deep X 6"(15cm) wide trench with approximately 12"(30cm) of RECPs extended beyond the up-slope portion of the trench. Use ShoreMax mat at the channel/culvert outlet as supplementa scour protection as needed. Anchor the RECPs with a row of staples/stakes approximately 12"(30cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Appl seed to the compacted soil and fold the remaining 12"(30cm) portion of RECP back over the seed and compacted soil Secure RECPs over compacted so with a row of staples/stakes spaced approximately 12" apart across the width of the RECPs.

securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern Place consecutive RECPs end-over-en-(Shingle style) with a 4"-6" overlap. Us a double row of staples staggered 4'

apart and 4" on center to secure . Full length edge of RECPs at top of side slopes must be anchored with a row of staples/stakes approximately 12"(30cm) apart in a 6"(15cm) deep X 6"(15cm) wide trench. Backfill and compact the trench after stapling Adjacent RECPs must be overlappe approximately 2"-5" (5-12.5cm)

(Depending on RECPs type) and In high flow channel applications staple check slot is recommended at 30 to 40 foot (9 -12m) intervals. Use a double row of staples staggered 4"(10cm) apart and 4"(10cm) on center over entire width of the channel.

. The terminal end of the RECPs must b anchored with a row of staples/stakes approximately 12" (30cm) apart in 6"(15cm) deep X 6"(15cm) wide trench Backfill and compact the trench after

Drawn on: 5-4-17

Raleigh Water Review Officer

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.

City. This electronic approval may not be edited once issued. Any modification to this approval once

issued will invalidate this approval.

Any work authorized by this approval must proceed in accordance with the plans kept on file with the

North 8 Carolina

*** 3 Days Before Digging *** North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentr

SHEET NO.:

JOB NUMBER

DRAWN BY:

SHEET TITLE:

KALAS FALLS

CIVIL DETAILS

AMERICAN

FNGINFFRING

SOUTHEAST

DETAIL SELECTION ONLY

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR U

ON THE SPECIFIC SITE, NAMED HEREOI

CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO

SUITABLE FOR USE ON A DIFFERENT

USE OF THIS DRAWING FOR REFERENCE

EXAMPLE ON ANOTHER PROJECT REQUIRES

THE SERVICES OF PROPERLY LICENSE

ARCHITECTS AND ENGINEERS. REPRODUCTION

THIS DRAWING FOR REUSE ON

ANOTHER PROJECT IS NOT AUTHORIZED


AND MAY BE CONTRARY TO THE LAW.

PROJECT SITE OR AT A LATER TIME

ASSOCIATES

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19



AMERICAN

American Engineering Associates - Southeast, P.A.

4020 Westchase Boulevard, Suite 450

AMERICAN ASSOCIATES ASSOCIATES SOUTHEAST OF AUTHORITIES OF AUTHORI

SEAL 9810

OF AUTOMORE PROPERTY OF AUTOMORE PROPERT

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES

THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


FHASE 1


1832 ROLESVILLE RO
WAKE COUNTY, NO


JOB NUMBER:
CHECKED BY:
DRAWN BY:
DATE:


KALAS FALLS
CIVIL DETAILS


SHEET NO.:













STIPULATION FOR REUSE


THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE O EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


ROAJ, NC


KALAS FALLS **CIVIL DETAILS**
















ON THE SPECIFIC SITE, NAMED HEREON ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


JOB NUMBER:

CHECKED BY: DRAWN BY:

> SHEET TITLE: KALAS FALLS CIVIL DETAILS








STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OF EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


JOB NUMBER: CHECKED BY: DRAWN BY:

DATE: SHEET TITLE:


KALAS FALLS CIVIL DETAILS

SHEET NO.: CD15










STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES
THE SERVICES OF PROPERLY LICENSED
ARCHITECTS AND ENGINEERS, REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

JOB NUMBER: CHECKED BY DRAWN BY:

SHEET TITLE: KALAS FALLS **CIVIL DETAILS**

SHEET NO.:

CD16





AMERICAN

Engineering Associates - Southeast, P.A.

20 Westchase Boulevard, Suite 450

919-469-1101





STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

ALAS FALLS
PHASE 1
ROLESVILLE ROAD
AKE COUNTY, NC

JOB NUMBER: CHECKED BY: DRAWN BY:


DATE:
SHEET TITLE:


KALAS FALLS CIVIL DETAILS


*** 3 Days Before Digging ***

SHEET NO.:

*** 3 Days Before Digging ***
North Carolina 811
811 or 1-800-632-4949
Remote Ticket Entry
http://nc811.org/remoteticketentry.htm







GENERAL LANDSCAPE NOTES

- All plant material shall conform with the standards set forth by the american association of nurserymen, american
- 2. Locate all existing utilities prior to installation of plant material, notify owner of any discrepancies between field
- conditions and those shown on the plan. Contractor engaged in landscape installation shall be a landscape contractor registered in the state.
- shall be removed prior to the certificate of occupancy (co) inspection is scheduled 5. Verification of total quantities as shown on the plant list shall be the responsibility of the contractor and the total
- quantities shall be as shown on the plan.
- 6. All plant groupings shall be mulched as one bed. 4" Pine Bark Mulch shall be used around all plantings.
- Apply pre-emergent herbicide to all new planting beds at manufacturer's recommended rate prior to installation of mulch.
- 8. Establish positive drainage in all planting beds and away from buildings. 9. Do not install plant material in impervious soils, (i.e. holes which, when filled with water, do not completely drain within
- 10. Lawn areas shall be seeded with Bermuda 95% coverage (based on a per square yard sample) shall be attained prior to
- final inspection. see detail sheet for rates and specifications for additional information. 11. The tree protection fence shall be maintained on the site until all site work is completed and the final site inspection prior
- to the certificate of occupancy (co) is scheduled. the fencing shall be removed prior to final site inspection for the co. 12. Landscape sub-contractor (under gc contract) shall be responsible for watering all plants and lawn areas at his cost from his own water source including during periods of drought until the plants and lawn meet final completion. Plant materials
- or areas of grass which perish shall be re-established by the contractor at no expense to the owner. 13. General contractor shall be responsible for keeping all equipment & subcontractors away from seeded areas. If damage occurs, through no fault of the owner, areas shall be regraded and reseeded immediately at no additional cost to the
- owner. Contractor shall water and maintain those areas until they are at 95% coverage at final completion. 14. General lawn areas shall be seeded with Bermuda. All 3:1 slopes shall be stabilized with biodegradable erosion control
- 15. Install permanent seeding along all roadside ditches and channels within construction limits of project. see erosion control plans for additional information
- 16. Areas damaged from plant relocation or other activities of landscape contractor to be reseeded and established at no additional cost to the owner.
- 17. Mulch and no-mow mixes shall be replenished as needed, especially after heavy rain events. If no-mow mix germinates at a rate of less than 90%, other species shall be removed and the area re-seeded.
- 18. Plants shall be watered at least 2 times per week unless soil is moist based on core sample or moisture meter reading. Water more frequently during establishment. Landscape Contractor (under GC contract) shall be responsible for watering all plants at his cost from his own water source including during periods of drought until the plants and lawn meet final
- 19. Remove (either manually or with pesticide treatment) all weeds in mulch areas, plant beds, tree rings, and hardscape areas: including but not limited to nutsedge, grasses, invasive plants, and any non-desirable plant material. This treatment
- shall occur monthly until the end of the warranty / maintenance period. 20. Mulch line smooth continuous curves.
- 21. All trees not within a plant bed to be treated with a 6-ft diameter mulch ring (typ).

- TOPSOIL / PLANTING MIX MINIMUM REQUIREMENTS:
 - TOPSOIL/PLANTING MIX SHOULD BE NATURAL, FERTILE, AGRICULTURAL SOIL CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH. IT SHOULD BE UNIFORM COMPOSITION THROUGHOUT. WITH ADMIXTURE OF SUBSOIL, IT SHOULD BE FREE OF STONES, LUMPS, LIVE PLANTS AND THEIR ROOTS, STICKS AND OTHER EXTRANEOUS MATTER. TOPSOIL SHOULD NOT BE USED WHILE IN A FROZEN OR MUDDY
- TOPSOIL/PLANTING MIX SHALL HAVE AN ACIDITY RANGE OF PH 5.5-7.0 AND THE FOLLOWING COMPOSITION:

CLAY (RED CLAY, WELL PULVERIZED) MINIMUM 10%; MAXIMUM 35%

5 - 8%

COMPOST*/ORGANIC MINIMUM 5%; MAXIMUM 10% MINIMUM 30%; MAXIMUM 50%

COARSE SAND (FREE OF ROCKS, 0.5 TO 1.0 MM F) MINIMUM 30%; MAXIMUM 45% ORGANIC MATERIAL SUCH AS SAWDUST OR LEAF MOLD THAT HAS COMPLETED THE

DECOMPOSITION PROCESS RECOMMENDATIONS:

PROPER GROWTH:

ALL PLANTING AREAS SHOULD BE TESTED FOR PROPER DRAINAGE. DRAINAGE SHOULD BE CORRECTED AS NECESSARY TO INSURE PROPER TREE GROWTH AND SURVIVAL. THE FOLLOWING LEVEL OF NUTRIENT ELEMENTS IS RECOMMENDED FOR

CALCIUM MAGNESIUM

MRS. GAYLE STALLINGS HAS

APPROVED THE PLANTING

DESIGN AND PLANT LIST

QTY REMARKS

CONTAINER QTY REMARKS

Single Straight Leader

Fully Rooted

Fully Rooted

Fully Rooted Fully Rooted

Fully Rooted

Fully Rooted

Fully Rooted Fully Rooted

Fully Rooted

Fully Rooted

Fully Rooted

Fully Rooted

Fully Rooted

Fully Rooted

62

195

116

26

AA' CROSS SECTION

Scale: 1"=5'

661

CONT

3" Cal.

2" Cal.

2" Cal.

2" Cal.

2.5" Cal.

3" Cal.

3 gal.

1 gal.

1 gal.

1 gal.

2.5" Cal. B&B

B&B

B&B

B&B

B&B

B&B

SPACING CONTAINER SPACING QTY REMARKS

24" o.c.

24" o.c.

24" o.c.

25' BUFFER

POTASSIUM

CARO °ĂMERICAN ° **ENGINEERING** ASSOCIATES SOUTHEAST C-3881 **PRELIMINARY**

FOR INFORMATION, ONLY

STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE

ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES TH SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION F THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED

AND MAY BE CONTRARY TO THE LAW.

KALAS FALLS AMENITY AREA & STALLINGS BERM

IOB NUMBER: CHECKED BY: DRAWN BY: 04-14-21

SHEET TITLE: PLANTING

PLAN North Carolina.

North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry

http://nc811.org/remoteticketentry.h