
CONSTRUCTION INFRASTRUCTURE DRAWING SUBMITTAL FOR

THE PRESERVE AT **MOODY FARM**

SITUATED AT

O ROLESVILLE ROAD AND O **AMAZON TRAIL**

WAKE COUNTY, NORTH CAROLINA



THESE IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE FOLLOWING DRAWINGS AND THE STANDARD SPECIFICATIONS OF THE CITY OF RALEIGH, WAKE COUNTY, TOWN OF ROLESVILLE AND NCDOT.

SCALE: 1"=1000'

REQUIRED APPROVALS					
PERMIT	PERMIT NUMBER:				
POND REMOVAL PERMIT	SEC-063778-2021				
TOWN OF ROLESVILLE PROJECT NUMBER	PR22-01				
TOWN OF ROLESVILLE CONSTRUCTION DOCUMENTS	TBD				
WAKE COUNTY EROSION CONTROL	TBD				
WAKE COUNTY STORMWATER	TBD				
CITY OF RALEIGH WATER	TBD				
CITY OF RALEIGH SEWER	TBD				

PROPRTY OWNER:	HOLLINGSWORTH, W.C., JR. AND HOLLINGSWORTH, LAURA W. P.O.BOX 61 LOUISBURG NC 27549-0061 PIN 1767284925 AND MOODY, BENNY LAWRENCE AND MOODY, JEFFREY LYNN 1716 ROLESVILLE RD, WAKE FOREST NC 27587-9677 PIN: 1767284304
DEVELOPER:	CARUSO HOMES CONTACT: CHISTY BECK 206 HIGH HOUSE RD STE 205 CARY, NC 27513 919-678-5698
SURVEYOR:	WITHERS RAVENEL CONTACT: MATT TIMLIN 115 MACKENAN DRIVE CARY, NC 27511 919-469-3340
BUFFER/WETLAND:	WITHERS RAVENEL CONTACT: TROY BEASLEY 115 MACKENAN DRIVE CARY, NC 27511 919-469-3340

	SION CONTROL, STORMWATER D FLOODPLAIN MANAGEMENT
APF	PROVED
ERC	SION CONTROL S
STO	RMWATER MGMT. 🗆 S
FLO	OD STUDY 🗆 S
DAT	E
WAKE COUNTY	ENVIRONMENTAL CONSULTANT SIGNATURE

TA 20-01 WAS ADAPTED 9-15-20, PERMITTING THE " DWELLING- SINGLE FAMILY DETACHED" USE IN THE R-3 DISTRICT, AND ESTABLISHED: MINIMUM LOT AREA OF 10,000 SF; MINIMUM LOT WIDTH 65'; FRONT YARD SETBACK OF 25'; SIDE YARD SETBACK OF 10'; CORNER YARD SETBACK OF 15'; REAR YARD SETBACK OF 25'

SHEET TITLE COVER
COVER OVERALL EXISTING CONDITIONS AND DEMOLITION PLAI
GENERAL NOTES
GENERAL NOTES
OVERALL EC STAGE 1
EC STAGE 1 - AREA A EC STAGE 1 - AREA B
EC STAGE 1 - AREA B EC STAGE 1 - AREA C
EC STAGE 1 - AREA D
OVERALL EC STAGE 2
EC STAGE 2 - AREA A
EC STAGE 2 - AREA B
EC STAGE 2 - AREA C
EC STAGE 2 - AREA D NPDES PLAN
OVERALL SITE PLAN
SITE PLAN A
SITE PLAN B
SITE PLAN C
SITE PLAN D
PHASING PLAN OPEN SPACE AND LAND USE PLAN
OVERALL DRAINAGE PLAN
DRAINAGE PLAN A
DRAINAGE PLAN B
DRAINAGE PLAN C
DRAINAGE PLAN D
POST DRAINAGE AREA MAP
OVERALL UTILITIES PLAN UTILITY PLAN A
UTILITY PLAN B
UTILITY PLAN C
UTILITY PLAN D
SCHEDULE
SCHEDULE
SCM 1 SCM 2
SCM 2 SCM 3
SCM 4
SCM 5
CULVERT CROSSING
MULBERRY PLAN AND PROFILE
MULBERRY PLAN AND PROFILE
TANSLEY CREST LOOP PLAN AND PROFILE VINTAGE VINERY CT PLAN AND PROFILE
CUL-DE-SAC AND STUB PLAN AND PROFILES
SEWER OUTFALL
SEWER OUTFALL
SEWER OUTFALL
SEWER OUTFALL
STORM OUTFALL PLAN AND PROFILES
EROSION CONTROL DETAILS EROSION CONTROL DETAILS
EROSION CONTROL DETAILS
EROSION CONTROL DETAILS
EROSION CONTROL DETAILS
UTILITY DETAILS
UTILITY DETAILS
UTILITY DETAILS
UTILITY DETAILS UTILITY DETAILS
DRAINAGE DETAILS
DRAINAGE DETAILS DRAINAGE DETAILS
SITE DETAILS
SITE DETAILS
SITE DETAILS
SITE DETAILS
LANDSCAPE PLAN
BUFFER PLAN

SHEET INDEX

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024 SHEET TITLE:

CVR

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE

DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME.

USE OF THIS DRAWING FOR REFERENCE (

USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRADY TO THE LAW

AND MAY BE CONTRARY TO THE LAW.

SERVE

COVER

Carolina (SHEET NO.:

*** 3 Days Before Digging ** North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry

City. This electronic approval may not be edited once issued. Any modification to this approval once http://nc811.org/remoteticketentry

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the

City of Raleigh Development Approval

issued will invalidate this approval.

Raleigh Water Review Officer

SITE INFORMATION

1767284925 AND 1767284304

51.78 AC

24.69 AC

6.54 AC 0.27 AC

0.14 AC

10,000 SF

1.6 UNIT/AC.

10% / 5 AC.

UTILITIES PRIOR TO THE START OF CONSTRUCTION.

PROJECT ENGINEER (919-469-1101) OF ANY CONFLICTS.

1. PERMITTED USE LIMITED TO "DWELLING - SINGLE FAMILY."

AND BORDERING THE SHORE PROPERTY (PIN. 1767-38-1953).

3. ALL BOUNDARY AND FIELD TOPOGRAPHY PROVIDED BY WITHERS & RAVENEL.

OPEN SPACE LOTS AND SCM'S WILL BE OWNED AND MAINTAINED BY HOA.

37% / 18.81 AC

2.5 AC (50% OF 5 AC)

CONTRACTOR SHALL CONTACT NORTH CAROLINA ONE CALL (1-800-632-4949) TO LOCATE ALL EXISTING

4. THE ZONING ENTITLEMENTS ACHIEVED/FACILITATING THIS PRELIM PLAT IS MA 21-05, APPROVED 12-7-2021 AS TOWN BOARD AGENDA ITEM B.2 ON THE CONSENT AGENDA; IT INCLUDES 5 CONDITIONS AND A

. ALL PROPOSED STREETS WILL BE DEDICATED TO TOWN AND THUS OWNED AND MAINTAINED BY TOWN.

2. CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF THE EXISTING UTILITIES AND NOTIFY THE

5. PLEASE SEE APPROVED WITH MA 21-05 BY TOWN BOARD OF COMMISSIONERS - SHEET NUMBER MA.

2. ALL DWELLINGS TO BE CONSTRUCTED ON RAISED FOUNDATIONS WITH CRAWLSPACES. NO

3.DEVELOPMENT TO INCORPORATE A PUBLIC GREENWAY AS SHOWN ON THE SKETCH PLAN

INCORPORATING OPTION 2 TOGETHER WITH WAYFINDING SIGNAGE AND CONSTRUCTION OF A 10' OFF-SITE MULTI-USE PATH ALONG WOODLYN PARK DRIVE, CONNECTING THIS GREENWAY TO THE

4. PRIOR TO COMPLETION OF THE ON-SITE GREENWAY, A 6' SOLID BOARD FENCE SHALL BE ERECTED

ALONG THE PROPERTY BOUNDARY LINE FRONTING THE EASTERN TERMINUS OF THE GREENWAY

5. ON-SITE CONSTRUCTION SHALL NOT COMMENCE UNTIL THE KALAS FALLS ROLESVILLE ROAD

R-3 CZ

REAL ESTATE ID

PIN NUMBERS

DEED BOOK

DEEDED ACREAGE

EXISTING ZONING

AREA IN LOTS

AREA IN ROW

EXISTING ROW DEDICATED ROW

> TOTAL LOTS MIN LOT SIZE

MIN LOT WIDTH FRONT SETBACK REAR SETBACK SIDE SETBACK CORNER SETBACK

OPEN SPACE REQ.

OPEN SPACE PROVIDED

ACTIVE REQUIRED

ACTIVE SHOWN

LF OF PUBLIC STREETS 5,531 LF

CONCEPT PLAN DRAWING.

ON-SLAB CONSTRUCTION.

ZONING CONDITIONS (CASE # MA-21-05)

PROPOSED KALAS FALLS GREENWAY.

WIDENING PROJECT IS COMPLETE.


TOTAL PROJECT ACREAGE | 48.28 AC

P.O.BOX 61 LOUISBURG NC 27549-0061

HOLLINGSWORTH, W.C., JR. AND HOLLINGSWORTH, LAURA W.

MOODY, BENNY LAWRENCE AND MOODY, JEFFREY LYNN 1716 ROLESVILLE RD, WAKE FOREST NC 27587-9677

DB:017552 PG:02100 AND DB:014297 PG:01583



GENERAL NOTES:

- A. ALL TREE PROTECTION FENCING SHALL BE MAINTAINED UNTIL ALL SITE WORK IS COMPLETED. THE FENCING SHALL BE REMOVED PRIOR TO THE FINAL SITE INSPECTION FOR THE CERTIFICATE OF OCCUPANCY (CO).
- B. ALL TREE PROTECTION FENCING SHALL BE MAINTAINED UNTIL ALL SITE WORK IS COMPLETED. THE FENCING SHALL REMAIN UNTIL ISSUANCE OF CERTIFICATE OF OCCUPANCY (CO).
- C. WITHIN THE SIGHT TRIANGLES SHOWN ON ALL SITE PLAN AND LANDSCAPE PLAN SHEETS, NO OBSTRUCTION BETWEEN 2 FEET AND 8 FEET IN HEIGHT ABOVE THE CURB LINE ELEVATION SHALL BE LOCATED IN WHOLE OR PART. OBSTRUCTIONS INCLUDE, BUT ARE NOT LIMITED TO, ANY BERM, FOLIAGE, FENCE, WALL SIGN, PARKED CAR, OR OTHER OBJECT. ALL STREET TREES FALLING WITHIN THE SIGHT TRIANGLES SHOWN ON THIS PLAN SHALL BE LIMBED UP BETWEEN 2 FEET AND 8 FEET IN HEIGHT ABOVE THE CURB LINE ELEVATION.
- D. MINIMUM CORNER CLEARANCE FROM THE CURB LINE OF INTERSECTING STREETS SHALL BE AT LEAST 20 FEET FROM THE POINT OF TANGENCY OF THE CURB. NO DRIVEWAYS SHALL ENCROACH ON THIS MINIMUM CORNER CLEARANCE.
- E. ALL STREETS SHOWN ON THESE PLANS HAVE FULL WIDTH OF RIGHT-OF-WAY CLEARED AND GRADED WITHIN 50 FEET OF ALL STREET INTERSECTIONS. THE FULL WIDTH OF RIGHT-OF-WAY SHALL BE
- CLEARED AND GRADED ALONG ALL MAJOR, MINOR AND SENSITIVE AREA THOROUGHFARES. F. WHEEL CHAIR ACCESS RAMPS WILL BE PROVIDED IN ACCORDANCE WITH STANDARD DRAWING SHOWN ON SHEET CD19. WHERE SIDEWALK IS NOT REQUIRED ALONG THE PUBLIC RIGHT-OF-WAY, CURB IS TO BE DEPRESSED AT ALL RAMP LOCATIONS SHOWN ON THE STANDARD DETAIL.
- G. ALL INDIVIDUAL LOTS SHALL HAVE AN EROSION CONTROL PLAN SUBMITTED PRIOR TO CONSTRUCTION OF HOUSES THERE UPON. IF MULTIPLE LOTS WITH A TOTAL DISTURBED AREA OF MORE THAN 12,000 SF ARE TO BE BUILT UPON AT ONE TIME, A COORDINATED EROSION CONTROL PLAN SHALL BE SUBMITTED.
- H. ALL PUBLIC WATER AND SEWER MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH
- THE CITY OF RALEIGH STANDARDS AND SPECIFICATIONS. CONTRACTOR SHALL CONTACT NORTH CAROLINA ONE CALL (1-800-632-4949) TO LOCATE ALL
- EXISTING UTILITIES PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF THE EXISTING UTILITIES AND NOTIFY THE
- PROJECT ENGINEER (919-469-1101) OF ANY CONFLICTS. K. ALL BOUNDARY AND FIELD TOPOGRAPHY PROVIDED BY WITHERS & RAVENEL.
- L. PHASE LINES SHOWN ARE SPECIFICALLY FOR ESTABLISHING LOTS THROUGH PLATTING PROCESS.

STANDARD UTILITY NOTES (AS APPLICABLE):

- 1. ALL MATERIALS & CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH CITY OF RALEIGH DESIGN STANDARDS, DETAILS & SPECIFICATIONS (REFERENCE: CORPUD HANDBOOK, CURRENT EDITION)
- 2. UTILITY SEPARATION REQUIREMENTS
- A) A DISTANCE OF 100' SHALL BE MAINTAINED BETWEEN SANITARY SEWER & ANY PRIVATE OR PUBLIC WATER SUPPLY SOURCE SUCH AS AN IMPOUNDED RESERVOIR USED AS A SOURCE OF DRINKING WATER. IF ADEQUATE LATERAL SEPARATION CANNOT BE ACHIEVED, FERROUS SANITARY SEWER PIPE SHALL BE SPECIFIED & INSTALLED TO WATERLINE SPECIFICATIONS. HOWEVER, THE MINIMUM SEPARATION SHALL NOT BE LESS THAN 25' FROM A PRIVATE WELL OR 50' FROM A PUBLIC WELL
- B) WHEN INSTALLING WATER &/OR SEWER MAINS, THE HORIZONTAL SEPARATION BETWEEN UTILITIES SHALL BE 10'. IF THIS SEPARATION CANNOT BE MAINTAINED DUE TO EXISTING CONDITIONS, THE VARIATION ALLOWED IS THE WATER MAIN IN A SEPARATE TRENCH WITH THE ELEVATION OF THE WATER MAIN AT LEAST 18" ABOVE THE TOP OF THE SEWER & MUST BE APPROVED BY THE PUBLIC UTILITIES DIRECTOR ALL DISTANCES ARE MEASURED FROM OUTSIDE DIAMETER TO OUTSIDE DIAMETER
- C) WHERE IT IS IMPOSSIBLE TO OBTAIN PROPER SEPARATION, OR ANYTIME A SANITARY SEWER PASSES OVER A WATERMAIN, DIP MATERIALS OR STEEL ENCASEMENT EXTENDED 10' ON EACH SIDE OF CROSSING MUST BE SPECIFIED & INSTALLED TO WATERLINE SPECIFICATIONS
- D) 5.0' MINIMUM HORIZONTAL SEPARATION IS REQUIRED BETWEEN ALL SANITARY SEWER & STORM SEWER FACILITIES, UNLESS DIP MATERIAL IS SPECIFIED FOR SANITARY SEWER MAINTAIN 18" MIN. VERTICAL SEPARATION AT ALL WATERMAIN & RCP STORM DRAIN CROSSINGS; MAINTAIN 24" MIN. VERTICAL SEPARATION AT ALL SANITARY SEWER & RCP STORM DRAIN CROSSINGS. WHERE ADEQUATE SEPARATIONS CANNOT BE ACHIEVED, SPECIFY DIP MATERIALS & A CONCRETE CRADLE HAVING 6" MIN. CLEARANCE (PER CORPUD DETAILS W-41 & S-49)
- E) ALL OTHER UNDERGROUND UTILITIES SHALL CROSS WATER & SEWER FACILITIES WITH 18" MIN. VERTICAL SEPARATION REQUIRED
- 3. ANY NECESSARY FIELD REVISIONS ARE SUBJECT TO REVIEW & APPROVAL OF AN AMENDED PLAN &/OR PROFILE BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT PRIOR TO
- 4. CONTRACTOR SHALL MAINTAIN CONTINUOUS WATER & SEWER SERVICE TO EXISTING RESIDENCES & BUSINESSES THROUGHOUT CONSTRUCTION OF PROJECT. ANY NECESSARY SERVICE INTERRUPTIONS SHALL BE PRECEDED BY A 24 HOUR ADVANCE NOTICE TO THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT
- 5. 3.0' MINIMUM COVER IS REQUIRED ON ALL WATER MAINS & SEWER FORCEMAINS. 4.0' MINIMUM COVER IS REQUIRED ON ALL REUSE MAINS
- 6. IT IS THE DEVELOPER'S RESPONSIBILITY TO ABANDON OR REMOVE EXISTING WATER & SEWER SERVICES NOT BEING USED IN REDEVELOPMENT OF A SITE UNLESS OTHERWISE DIRECTED BY THE CITY OF RALEIGH PUBLIC UTILITIES DEPARTMENT. THIS INCLUDES ABANDONING TAP AT MAIN & REMOVAL OF SERVICE FROM ROW OR EASEMENT PER CORPUD HANDBOOK PROCEDURE
- 7. INSTALL ¾" COPPER* WATER SERVICES WITH METERS LOCATED AT ROW OR WITHIN A 2'X2' WATERLINE EASEMENT IMMEDIATELY ADJACENT. NOTE: IT IS THE APPLICANT'S RESPONSIBILITY TO PROPERLY SIZE THE WATER SERVICE FOR EACH CONNECTION TO PROVIDE ADEQUATE FLOW & PRESSURE
- 8. INSTALL 4" PVC* SEWER SERVICES @ 1.0% MINIMUM GRADE WITH CLEANOUTS LOCATED AT ROW OR EASEMENT LINE & SPACED EVERY 75 LINEAR FEET MAXIMUM
- 9. PRESSURE REDUCING VALVES ARE REQUIRED ON ALL WATER SERVICES EXCEEDING 80 PSI; BACKWATER VALVES ARE REQUIRED ON ALL SANITARY SEWER SERVICES HAVING BUILDING DRAINS LOWER THAN 1.0' ABOVE THE NEXT UPSTREAM MANHOLE
- 10. ALL ENVIRONMENTAL PERMITS APPLICABLE TO THE PROJECT MUST BE OBTAINED FROM NCDWQ, USACE &/OR FEMA FOR ANY RIPARIAN BUFFER, WETLAND &/OR FLOODPLAIN IMPACTS (RESPECTIVELY) PRIOR TO CONSTRUCTION.
- 11. NCDOT / RAILROAD ENCROACHMENT AGREEMENTS ARE REQUIRED FOR ANY UTILITY WORK (INCLUDING MAIN EXTENSIONS & SERVICE TAPS) WITHIN STATE OR RAILROAD ROW PRIOR TO CONSTRUCTION
- 12. GREASE INTERCEPTOR / OIL WATER SEPARATOR SIZING CALCULATIONS & INSTALLATION SPECIFICATIONS SHALL BE APPROVED BY THE CORPUD FOG PROGRAM COORDINATOR PRIOR TO ISSUANCE OF A BUILDING PERMIT.
- 13. CROSS-CONNECTION CONTROL PROTECTION DEVICES ARE REQUIRED BASED ON DEGREE OF HEALTH HAZARD INVOLVED AS LISTED IN APPENDIX-B OF THE RULES GOVERNING PUBLIC WATER SYSTEMS IN NORTH CAROLINA. THESE GUIDELINES ARE THE MINIMUM REQUIREMENTS. THE DEVICES SHALL MEET AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE) STANDARDS OR BE ON THE UNIVERSITY OF SOUTHERN CALIFORNIA APPROVAL THE DEVICES SHALL BE INSTALLED AND TESTED (BOTH INITIAL AND PERIODIC TESTING THEREAFTER) IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS OR THE LOCAL CROSS-CONNECTION CONTROL PROGRAM, WHICHEVER IS MORE STRINGENT.

NOTES FOR CONSTRUCTION:

- 1. PLANS FOR INFRASTRUCTURE ONLY.
- 2. ALL CONSTRUCTION MUST BE PERFORMED IN ACCORDANCE WITH CURRENT CITY OF RALEIGH STANDARD SPECS AND DETAILS, WAKE COUNTY SPECIFICATIONS, NCDOT SPECIFICATIONS AND TOWN OF ROLESVILLE SPECIFICATIONS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF EXISTING CONDITIONS. CONTRACTOR SHALL NOTIFY ENGINEER OF DISCREPANCIES BETWEEN FIELD CONDITIONS AND THESE DRAWINGS.
- 4. THERE ARE NO 100 YEAR FLOOD PLAINS PER FEMA MAP WITHIN PROPERTY.
- 5. CONTRACTOR WILL KEEP STREETS CLEAN AT ALL TIMES, OR A WASH STATION WILL BE REQUIRED.
- 6. ALL CATCH BASINS SHALL HAVE INLET PROTECTION.
- 7. ALL CUT AND FILL SLOPES MUST BE STABILIZED WITHIN 14 DAYS OF ANY PHASE OF GRADING, WITH SOME SLOPES TO BE STABALIZED WITHIN 7 DAYS AS SHOWN ON CHART TO THE LEFT AND ON THE EC SHEETS.
- 8. TREE PROTECTION FENCING ON THIS PROJECT WILL BE INSTALLED AND INSPECTED BEFORE THE GRADING PERMIT IS ISSUED.
- A PRE-CONSTRUCTION CONFERENCE MAY BE REQUIRED BEFORE GRADING PERMIT IS ISSUED. PERMANENT GROUND COVER WILL BE ESTABLISHED IN 15 WORKING DAYS OR 90 CALENDAR DAYS WHICHEVER IS SHORTER.
- 10. THE AREA DESIGNATED SHALL BE USED FOR TOPSOIL STOCKPILE.
- 11. THIS PROJECT IS IN THE NEUSE RIVER WATERSHED. 12. WETLANDS ON THIS PROJECT ARE AS SHOWN.
- 13. MINIMUM CORNER CLEARANCE FROM THE CURB LINE OF INTERSECTING STREETS SHALL BE AT LEAST TWENTY (20) FEET FROM THE POINT OF TANGENCY.

EROSION & SEDIMENT CONTROL NOTES:

STAGE 1 E&SC CONSTRUCTION SEQUENCE:

- 1. THE OWNER SHALL OBTAIN NCG01 PERMIT AND PAY ANY FEE THAT MAYBE ASSOCIATED WITH THIS PERMIT.
- 2. SCHEDULE A PRE-CONSTRUCTION CONFERENCE WITH THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL QUALITY (NCDEQ)/TOWN OF ROLESVILLE, OBTAIN LAND DISTURBING PERMIT.
- 3. ENSURE THAT ALL LIMITS OF DISTURBANCE, SURFACE WATERS, AND RIPARIAN BUFFERS ARE FLAGGED PRIOR TO INSTALLATION OF EROSION CONTROL MEASURES. WETLANDS PRESENT ON SITE ARE NOT TO BE IMPACTED DURING CONSTRUCTION ACTIVITIES.
- 4. TREE PROTECTION FENCES, SILT FENCES AND CONSTRUCTION ENTRANCES SHALL BE INSTALLED AS SHOWN ON THE EROSION CONTROL PLANS. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES INCLUDING STOCKPILE LOCATIONS. STOCKPILE LOCATIONS SHOULD BE ENCLOSED BY SILT FENCE AS SHOWN ON THE PLANS. SEED ALL RESULTING BARE AREAS IMMEDIATELY AFTER CONSTRUCTION.
- 5. CONSTRUCT SCMs #1-#5 AS SEDIMENT BASINS BY OMITTING FOREBAY DIVIDERS AND CONNECTING SKIMMERS TO THE DRAINPIPE. THE FINAL PIPE AND STRUCTURE FOR EACH POND IS TO BE INSTALLED WITH STAGE 1 EROSION CONTROL AND SERVE THE TEMPORARY SEDIMENT BASINS AND ACT AS INLETS FOR THE TEMPORARY DIVERSION DITCHES. SEE EROSION AND SEDIMENT CONTROL PLANS FOR MORE DETAIL. FOLLOWING THE COMPLETION OF THE INITIAL CONSTRUCTION STAGE, THE INLET STRUCTURES MUST BE CLEANED AND HAVE INLET PROTECTION INSTALLED AS SHOWN ON THE STAGE 2 EROSION AND SEDIMENT CONTROL PLANS. THE SEDIMENT BASINS SHALL BE FULLY CONSTRUCTED PRIOR TO THE INSTALLATION OF ANY TEMPORARY DIVERSION
- 6. CONTRACTOR TO INSTALL BRIDGEMAT AS SHOWN ON EROSION AND SEDIMENT CONTROL PLANS FOR CREEK CROSSING. SEE SHEET C8.5 FOR DETAILED CREEK CROSSING CONSTRUCTION SEQUENCE.
- 7. CALL FOR INSPECTION BY NCDEQ/TOWN OF ROLESVILLE FOR APPROVAL BEFORE PROCEEDING TO STAGE 2 CONSTRUCTION.
- 8. ADDITIONAL MEASURES OR DITCH EXTENSIONS MAY BE REQUIRED BY THE NCDEQ/TOWN OF ROLESVILLE EROSION CONTROL FIELD INSPECTOR TO ROUTE RUNOFF TO SEDIMENT BASINS BASED ON FIELD CONDITIONS AND THESE MEASURES SHALL BE INSTALLED UPON THE INSPECTOR'S DETERMINATION.

STAGE 2 E&SC CONSTRUCTION SEQUENCE:

- GENERAL SITE GRADING MAY BEGIN.
- INSTALL STORM DRAINAGE PIPE SYSTEMS.
- 3. AS EACH CATCH BASIN OR YARD INLET IS INSTALLED, IT SHALL HAVE INLET PROTECTION INSTALLED. THIS IS TO REMAIN IN PLACE UNTIL THE DRAINAGE AREA(S) HAVE BEEN STABILIZED OR PAVED.
- 4. CLEAN SEDIMENT BASINS WHEN ONE-HALF FULL.
- 5. SEED AND MULCH DENUDED AREA INCLUDING ANY CUT/FILL SLOPES WITHIN FOURTEEN (14) DAYS AFTER FINISHED GRADES ARE ESTABLISHED.
- 6. MAINTAIN SOIL EROSION CONTROL MEASURES UNTIL PERMANENT GROUND IS ESTABLISHED.
- 7. UTILITIES (WATER, ELECTRIC, GAS, CABLE TV, TELEPHONE, ETC.) WILL BE INSTALLED **DURING THIS PHASE.**
- 8. WHEN ALL CONTRIBUTORY AREAS ARE STABILIZED, OBTAIN APPROVAL FROM THE NCDEQ/TOWN OF ROLESVILLE TO CONVERT THE SEDIMENT BASINS (SB) TO PERMANENT STORMWATER CONTROL MEASURES (SCM). SEE RECOMMENDED INSTRUCTIONS TO CONVERT SEDIMENT BASINS TO PERMANENT STORMWATER CONTROL MEASURES ON THIS SHEET OF THE PROJECT CONSTRUCTION DRAWINGS.
- 9. REQUEST APPROVAL BY NCDEQ/TOWN OF ROLESVILLE AFTER VEGETATION IS ESTABLISHED TO REMOVE REMAINING EROSION CONTROL MEASURES.
- 10. REMOVE REMAINING SOIL EROSION CONTROL MEASURES AND STABILIZE THE RESULTING BARE AREAS. CONTACT NCDEQ/TOWN OF ROLESVILLE TO REQUEST FINAL INSPECTION TO CLOSE LAND DISTURBANCE PERMIT.
- 11. THE OWNER IS TO FINALIZE THE NCG01 PERMIT.

REQUIRED WAKE COUNTY BASIN REMOVAL SEQUENCE

- 1. SCHEDULE A SITE MEETING WITH THE ENVIRONMENTAL CONSULTANT TO DETERMINE IF A BASIN CAN BE REMOVED. INSTALL SILT FENCING OR OTHER TEMPORARY EROSION CONTROL MEASURES AS NEEDED PRIOR TO REMOVAL OF THE BASIN
- TO BE EXTENDED, PERFORM THIS OPERATION AT THIS TIME. FINE GRADE AREA IN PREPARATION **FOR SEEDING** 3. PERFORM SEEDBED PREPARATION, SEED, MULCH AND ASPHALT TACK ANY RESULTING BARE

2. REMOVE BASIN(S) AND ASSOCIATED TEMPORARY DIVERSION DITCHES. IF CULVERT PIPES NEED

- AREAS IMMEDIATELY. 4. INSTALL VELOCITY DISSIPATORS AND/OR LEVEL SPREADERS AS REQUIRED ON THE EROSION
- 5. WHEN SITE IS FULLY STABILIZED, CALL ENVIRONMENTAL CONSULTANT FOR APPROVAL OF REMOVING REMAINING TEMPORARY EROSION CONTROL MEASURES AND ADVICE ON WHEN SITE CAN BE ISSUED A CERTIFICATE OF COMPLETION.

NOTE: A MEETING SHOULD ALSO BE SCHEDULED WITH THE ENVIRONMENTAL CONSULTANT TO DETERMINE WHEN A BASIN MAY BE CONVERTED FOR STORMWATER USE. SOME MUNICIPALITIES MAY ALSO REQUIRE THIS

SCM CONVERSION SEQUENCE:

- 1. WHEN ALL CONTRIBUTORY AREAS TO THE STORMWATER CONTROL MEASURE (SCM) HAVE BEEN STABILIZED CONTACT THE EROSION CONTROL OFFICER FOR PERMISSION TO CONVERT THE SEDIMENT BASIN (SB) TO A SCM.
- 2. REMOVE ALL SEDIMENT FROM THE BASIN AND RESTORE GRADES TO DESIGNED CONFIGURATION, IF NEEDED.
- 3. CONSTRUCT FOREBAY DIVIDERS AS SHOWN ON THE PLANS.
- 4. REMOVE TEMPORARY BAFFLES FROM THE BASIN
- 5. MAKE ANY REPAIRS NECESSARY TO THE OUTLET STRUCTURE, OUTLET PIPE, EMERGENCY OVERFLOW, ETC. EXAMINE RIP-RAP TO SEE IF REFRESHING OR CLEANING OF ROCK IS NECESSARY.
- 6. INSTALL SHELF PLANTINGS AS SHOWN ON THE PLANS. CHECK THAT ALL SLOPES ARE PROPERLY STABILIZED.
- 7. BE SURE THAT THE TRASH RACKS ARE IN PLACE AND PROPERLY FUNCTIONING. REMOVE SKIMMER AND CLOSE OUTLET VALVE.
- 8. CONTACT EROSION CONTROL OFFICER FOR APPROVAL
- 9. CONTACT A LICENSED SURVEYOR FOR SURVEY OF AS-BUILT CONDITIONS. NOTIFY ENGINEER-OF-RECORD FOR PREPARATION OF AS-BUILT DRAWINGS.

REQUIRED WAKE COUNTY CONSTRUCTION SEQUENCE*

- 1. SCHEDULE A PRECONSTRUCTION CONFERENCE WITH THE WATERSHED MANGER. OBTAIN A LAND-DISTURBING PERMIT.
- 2. INSTALL GRAVEL CONSTRUCTION PAD, TEMPORARY DIVERSIONS, SILT FENCE, SEDIMENT BASINS OR OTHER MEASURES AS SHOWN ON THE APPROVED PLAN. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS, BERMS AND BASINS IMMEDIATELY AFTER CONSTRUCTION.
- 3. CALL FOR AN ONSITE INSPECTION BY THE WATERSHED MANAGER TO OBTAIN A CERTIFICATE OF
- 4. BEGIN CLEARING AND GRUBBING. MAINTAIN DEVICES AS NEEDED. ROUGH GRADE SITE.
- 5. INSTALL STORM SEWER, IF SHOWN, AND PROTECT INLETS WITH BLOCK AND GRAVEL INLET CONTROLS, SEDIMENT TRAPS OR OTHER APPROVED MEASURES AS SHOWN ON THE PLAN. BEGIN CONSTRUCTION, BUILDING, ETC.
- STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH VEGETATION, PAVING, DITCH LININGS, ETC. SEED AND MULCH DENUDED AREAS PER GROUND STABILIZATION TIME FRAMES.
- 7. WHEN CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED COMPLETELY, CALL FOR AN INSPECTION BY THE WATERSHED MANAGER.
- 8. IF SITE IS APPROVED, REMOVE TEMPORARY DIVERSIONS, SILT FENCE, SEDIMENT BASINS, ETC., AND SEED OUT OR STABILIZE ANY RESULTING BARE AREAS. ALL REMAINING PERMANENT EROSION CONTROL DEVICES, SUCH AS VELOCITY DISSIPATORS, SHOULD NOW BE INSTALLED.
- WHEN VEGETATION HAS BECOME ESTABLISHED, CALL FOR A FINAL SITE INSPECTION BY THE WATERSHED MANAGER. OBTAIN A CERTIFICATE OF COMPLETION.

STOCKPILE DESIGN CRITERIA

- A. A 25-FOOT TEMPORARY MAINTENANCE AND ACCESS EASEMENT SHALL BE SHOWN AROUND ALL PROPOSED STOCKPILES (EROSION CONTROL MEASURES SURROUNDING THE STOCKPILE SHALL BE SHOWN AT THE OUTER LIMIT OF THIS EASEMENT).
- B. STOCKPILE FOOTPRINTS SHALL BE SETBACK A MINIMUM OF 25' FROM ADJACENT
- PROPERTY LINES. C. A NOTE SHALL BE PROVIDED ON THE APPROVED PLAN THAT STOCKPILE HEIGHT SHALL
- NOT EXCEED 35 FEET.
- STOCKPILE SLOPES SHALL BE 2:1 OR FLATTER. APPROVED BMPS SHALL BE SHOWN ON A PLAN TO CONTROL ANY POTENTIAL
- SEDIMENT LOSS FROM A STOCKPILE STOCKPILING MATERIALS ADJACENT TO A DITCH, DRAINAGEWAY, WATERCOURSE, WETLAND, STREAM BUFFER, OR OTHER BODY OF WATER SHALL BE AVOIDED UNLESS AN
- ALTERNATIVE LOCATION IS DEMONSTRATED TO BE UNAVAILABLE. ANY CONCENTRATED FLOW LIKELY TO AFFECT THE STOCKPILE SHALL BE DIVERTED TO AN
- OFF-SITE SPOIL OR BORROW AREAS MUST BE IN COMPLIANCE WITH WAKE COUNTY UDO AND STATE REGULATIONS. ALL SPOIL AREAS OVER AN ACRE ARE REQUIRED TO HAVE AN APPROVED SEDIMENT CONTROL PLAN. DEVELOPER/CONTRACTOR SHALL NOTIFY WAKE COUNTY OF ANY OFFSITE DISPOSAL OF SOIL, PRIOR TO DISPOSAL. FILL OF FEMA FLOODWAYS AND NON-ENCROACHMENT AREAS ARE PROHIBITED EXCEPT AS OTHERWISE PROVIDED BY SUBSECTION 14-19-2 OF THE WAKE COUNTY UNIFIED DEVELOPMENT ORDINANCE (CERTIFICATIONS AND PERMITS REQUIRED).

MAINTENANCE REQUIREMENTS TO BE NOTED ON THE PLAN

- I. SEEDING OR COVERING STOCKPILES WITH TARPS OR MULCH IS REQUIRED AND WILL REDUCE EROSION PROBLEMS. TARPS SHOULD BE KEYED IN AT THE TOP OF THE SLOPE
- TO KEEP WATER FROM RUNNING UNDERNEATH THE PLASTIC. J. IF A STOCKPILE IS TO REMAIN FOR FUTURE USE AFTER THE PROJECT IS COMPLETE (BUILDERS, ETC.), THE FINANCIAL RESPONSIBLE PARTY MUST NOTIFY WAKE COUNTY OF A NEW RESPONSIBLE PARTY FOR THAT STOCKPILE.
- K. THE APPROVED PLAN SHALL PROVIDE FOR THE USE OF STAGED SEEDING AND MULCHING ON A CONTINUAL BASIS WHILE THE STOCKPILE IS IN USE.

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.

Any work authorized by this approval must proceed in accordance with the plans kept on file with the

City. This electronic approval may not be edited once issued. Any modification to this approval once

issued will invalidate this approval.

City of Raleigh Development Approval

ESTABLISH AND MAINTAIN A VEGETATIVE BUFFER AT THE TOE OF THE SLOPE (WHERE

JOB NUMBER: 21-002 CHECKED BY: JK

DRAWN BY: RC & SM

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON

CONTEMPORANEOUSLY WITH ITS ISSUE

DATE AS LISTED, HEREON. AND IT IS NO

SUITABLE FOR USE ON A DIFFERENT

PROJECT SITE OR AT A LATER TIME

USE OF THIS DRAWING FOR REFERENCE (

EXAMPLE ON ANOTHER PROJECT REQUIRES

THE SERVICES OF PROPERLY LICENSE ARCHITECTS AND ENGINEERS, REPRODUCTION

OF THIS DRAWING FOR REUSE ON

ANOTHER PROJECT IS NOT AUTHORIZED

AND MAY BE CONTRARY TO THE LAW.

FARM

ERV

 \propto

DATE: 12/02/2024

SHEET TITLE:

GENERAL NOTES

C2.0

North (Carolina) SHEET NO.

*** 3 Days Before Digging * North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry

http://nc811.org/remoteticketentry

Raleigh Water Review Officer

° AMERICAN °

ENGINEERING

ASSOCIATES

C-3881

ろう SOUTHEAST

MAINTENANCE OF EROSION CONTROL MEASURES

SILT FENCE MAINTENANCE - INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFGER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL AREAS. IMMEDIATELY. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE TAKEN IN THE WINTER TO PREVENT THE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING SKIMMER FROM PLUGGING WITH ICE. THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

SILT FENCE OUTLETS - SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EVERY SIGNIFICANT RAINFALL. IF DAMAGED, THEY SHALL HAVE FABRIC, POSTS OR WIRE BACKING REPLACED TO RESTORE TO ORIGINAL CONDITION.

TREE PROTECTION FENCE MAINTENANCE - CONTINUE TO CARE FOR THE SITE UNTIL THE NEW OWNER TAKES POSSESSION. TAKE THESE STEPS AFTER ALL MATERIALS AND EQUIPMENT HAVE BEEN REMOVED FROM THE SITE:

•REMOVE TREE PROTECTION ZONE FENCES.

•PRUNE ANY DAMAGED TREES. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, REPAIR ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM IMMEDIATELY.

REPAIR ROOTS BY CUTTING OFF THE DAMAGED AREAS AND PAINTING THEM WITH TREE PAINT SPREAD PEAT MOSS OR MOIST TOPSOIL OVER EXPOSED ROOTS.

•REPAIR DAMAGE TO BARK BY TRIMMING AROUND THE DAMAGED AREA AS SHOWN IN

FIGURE 6.05D, TAPER THE CUT TO PROVIDE DRAINAGE, AND PAINT WITH TREE PAINT.

•CUT OFF ALL DAMAGED TREE LIMBS ABOVE THE TREE COLLAR AT THE TRUNK OR MAIN BRANCH. USE THREE SEPARATE CUTS AS SHOWN IN FIGURE 6.05D TO AVOID PEELING BARK FROM HEALTHY AREAS OF THE TREE.

•CONTINUE MAINTENANCE CARE. PAY SPECIAL ATTENTION TO ANY STRESSED, DISEASED, OR INSECT-INFESTED TREES. REDUCE TREE STRESS CAUSED BY UNINTENDED CONSTRUCTION DAMAGE BY OPTIMIZING PLANT CARE WITH WATER, MULCH, AND FERTILIZER WHERE APPROPRIATE. CONSULT YOUR TREE EXPERT IF NEEDED.

INFORM THE PROPERTY OWNER ABOUT THE MEASURES EMPLOYED DURING CONSTRUCTION, WHY THOSE MEASURES WERE TAKEN, AND HOW THE EFFORT CAN BE CONTINUED.

CONSTRUCTION ENTRANCE - MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.

SOIL STOCKPILE AREAS/OTHER GRASSED AREAS MAINTENANCE - GRASS AREAS SHALL BE RESEEDED AS NECESSARY. SOIL STOCKPILE AREAS SHALL BE SEEDED WHEN THEIR USE IS COMPLETE.

TEMPORARY SEDIMENT TRAP - INSPECT TEMPORARY SEDIMENT TRAPS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (½ INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT, AND RESTORE THE TRAP TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE PART OF THE GRAVEL FACING THAT IS IMPAIRED BY SEDIMENT.

CHECK THE STRUCTURE FOR DAMAGE FROM EROSION OR PIPING. PERIODICALLY CHECK THE DEPTH OF THE SPILLWAY TO ENSURE IT IS A MINIMUM OF 1.5 FEET BELOW THE LOW POINT OF THE EMBANKMENT. IMMEDIATELY FILL ANY SETTLEMENT OF THE EMBANKMENT TO SLIGHTLY ABOVE DESIGN GRADE. ANY RIPRAP DISPLACED FROM THE SPILLWAY MUST BE REPLACED IMMEDIATELY.

AFTER ALL SEDIMENT-PRODUCING AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS AND STABILIZE PROPERLY (REFERENCES: SURFACE STABILIZATION).

SEDIMENT BASINS - INSPECT TEMPORARY SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN IT ACCUMULATES TO ONE-HALF THE DESIGN DEPTH. PLACE REMOVED SEDIMENT IN AN AREA WITH SEDIMENT CONTROLS.

CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT, MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE RISER AND POOL AREA.

CONCRETE WASHOUT - IT SHALL BE CLEANED PERIODICALLY AS NEEDED. IF THE PLASTIC LINER IS DAMAGED, IT SHALL BE REPLACED.

BAFFLES - INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.

BE SURE TO MAINTAIN ACCESS TO THE BAFFLES. SHOULD THE FABRIC OF A BAFFLE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.

REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL, TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE BAFFLES.TAKE CARE TO AVOID DAMAGING THE BAFFLES DURING CLEANOUT AND REPLACE IF DAMAGED DURING CLEANOUT OPERATIONS. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE DESIGNED STORAGE DEPTH.

AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. REMOVE ALL BAFFLE MATERIALS AND UNSTABLE SEDIMENT DEPOSITS. BRING THE AREA TO GRADE, AND STABILIZE IT.

ROLLED EROSION CONTROL PRODUCTS -

1.INSPECT ROLLED EROSION CONTROL PRODUCTS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (1/2 INCH OR GREATER) RAIN FALL EVENT REPAIR IMMEDIATELY.

2.GOOD CONTACT WITH THE GROUND MUST BE MAINTAINED, AND EROSION MUST NOT OCCUR BENEATH THE RECP.

3.ANY AREAS OF THE RECP THAT ARE DAMAGED OR NOT IN CLOSE CONTACT WITH THE GROUND SHALL BE REPAIRED AND STAPLED. 4.IF EROSION OCCURS DUE TO POORLY CONTROLLED DRAINAGE, THE PROBLEM SHALL BE FIXED AND THE ERODED AREA PROTECTED.

5.MONITOR AND REPAIR THE RECP AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.

SKIMMERS - INSPECT SKIMMER SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (ONE-HALF INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO ONE SIDE SO THAT THE SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SURE VEGETATION GROWING IN THE BOTTOM OF THE BASIN DOES NOT HOLD DOWN THE SKIMMER.

REPAIR THE BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM.

IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK, PULL THE SKIMMER OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS.ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IF IT IS CLOGGED; IF SO, REMOVE THE DEBRIS.

IF THE SKIMMER AND/ OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER.

CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE

GRASSED LINED CHANNEL- DURING THE ESTABLISHMENT PERIOD, CHECK GRASS-LINED CHANNELS AFTER EVERY RAINFALL.AFTER GRASS IS ESTABLISHED, PERIODICALLY CHECK THE CHANNEL; CHECK IT AFTER EVERY HEAVY RAINFALL EVENT. IMMEDIATELY MAKE REPAIRS. IT IS PARTICULARLY IMPORTANT TO CHECK THE CHANNEL OUTLET AND ALL ROAD CROSSINGS FOR BANK STABILITY AND EVIDENCE OF PIPING OR SCOUR HOLES. REMOVE ALL SIGNIFICANT SEDIMENT ACCUMULATIONS TO MAINTAIN THE DESIGNED CARRYING CAPACITY. KEEP THE GRASS IN A HEALTHY, VIGOROUS CONDITION AT ALL TIMES, SINCE IT IS THE PRIMARY EROSION PROTECTION FOR THE CHANNEL (PRACTICE 6.11, PERMANENT SEEDING).

RIP-RAP CHANNEL - INSPECT CHANNELS AT REGULAR INTERVALS AS WELL AS AFTER MAJOR RAINS, AND MAKE REPAIRS PROMPTLY. GIVE SPECIAL ATTENTION TO THE OUTLET AND INLET SECTIONS AND OTHER POINTS WHERE CONCENTRATED FLOW ENTERS. CAREFULLY CHECK STABILITY AT ROAD CROSSINGS, AND LOOK FOR INDICATIONS OF PIPING, SCOUR HOLES, OR BANK FAILURES. MAKE REPAIRS IMMEDIATELY. MAINTAIN ALL VEGETATION ADJACENT TO THE CHANNEL IN A HEALTHY, VIGOROUS CONDITION TO PROTECT THE AREA FROM EROSION AND SCOUR DURING OUT-OF-BANK FLOW.

OUTLET STABILIZATION STRUCTURE - INSPECT RIPRAP OUTLET STRUCTURES WEEKLY AND AFTER SIGNIFICANT (1/2 INCH OR GREATER) RAINFALL EVENTS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE, OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE

TEMPORARY SILT DITCH - SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EVERY SIGNIFICANT RAINFALL. IF SIGNIFICANT EROSION OF THE DITCH IS HAPPENING IT SHALL BE RE-GRADED. ANY BREACH OF THE DOWNHILL SIDE BERM SHALL BE FIXED IMMEDIATELY.

WATTLES/COMPOST SOCK - INSPECT COMPOST SOCKS WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL EVENT (1/2 INCH OR GREATER). REMOVE ACCUMULATED SEDIMENT AND ANY DEBRIS. THE COMPOST SOCK MUST BE REPLACED IF CLOGGED OR TORN. IF PONDING BECOMES EXCESSIVE, THE SOCK MAY NEED TO BE REPLACED WITH A LARGER DIAMETER OR A DIFFERENT MEASURE. THE SOCK NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED. THE COMPOST SOCK SHALL BE INSPECTED UNTIL LAND DISTURBANCE IS COMPLETE AND THE AREA ABOVE THE MEASURE HAS BEEN PERMANENTLY STABILIZED

ROCK PIPE INLET PROTECTION - INSPECT ROCK PIPE INLET PROTECTION AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (½ INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE SEDIMENT STORAGE AREA TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE CONTAMINATED PART OF THE GRAVEL FACING.

CHECK THE STRUCTURE FOR DAMAGE. ANY RIPRAP DISPLACED FROM THE STONE HORSESHOE MUST BE REPLACED IMMEDIATELY.

AFTER ALL THE SEDIMENT-PRODUCING AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL THE UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS AND PROVIDE PERMANENT GROUND COVER (SURFACE STABILIZATION).

DATE: 12/02/2024

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the


City. This electronic approval may not be edited once issued. Any modification to this approval once


City of Raleigh Development Approval

issued will invalidate this approval.

Raleigh Water Review Officer

North 8 Carolina *** 3 Days Before Digging * North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry





STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE. NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE O EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSE ARCHITECTS AND ENGINEERS, REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

SERVE **FARM**

JOB NUMBER: 21-002 CHECKED BY: JK


DRAWN BY: RC & SM

SHEET TITLE:

GENERAL NOTES

SHEET NO.

C2.1



AMERICAN
American Engineering Associates - Southeast, P.A.4020 Westchase Boulevard Suite 450





STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE
AT
MOODY FARM
ROLESVILLE ROAD
WAKE COUNTY, NC

JOB NUMBER: 21-002

CHECKED BY: JK

DRAWN BY: RC & SM

DATE: 12/02/2024

SHEET TITLE:

OVERALL EC STAGE 1


SHEET NO.:
C3.0


*** 3 Days Before Digging ***
North Carolina 811


811 or 1-800-632-4949 Remote Ticket Entry


http://nc811.org/remoteticketentry.h


City of Raleigh Development Approval











EROSION CONTROL LEGEND **EXISTING TOPOGRAPHY EXISTING BOUNDARY** EXISTING WETLANDS AREA EXISTING 50' NEUSE RIPERIAN BUFFER PROPOSED LOT LINE PROPOSED EASEMENT _____ PROPOSED 25 x 50 GRAVEL CONSTRUCTION ENTRANCE PROPOSED RIP RAP BASIN WEIR PROPOSED SEDIMENT BASIN PROPOSED INLET PROTECTION PROPOSED PIPE INLET PROTECTION PROPOSED CHECK DAM PROPOSED SF OUTLET SERVE GREENWAY TRAIL HATCH PROPOSED BASIN MAINTENANCE PAD PROPOSED WATTLE PROPOSED SILT FENCE PROPOSED TREE PROTECTION FENCE LIMITS OF DISTURBANCE DIVERSION DITCH DRAINAGE PROPOSED DIVERSION DITCH PROPOSED JUNCTION BOX PROPOSED CATCH BASIN PROPOSED YARD INLET PROPOSED DROP INLET

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

*** 3 Days Before Digging ***
North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.ht

PROPOSED STORM WATER

SHEET NO.: C3.5

ENGINEERING ASSOCIATES southeast



STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR US


THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


ROLESVILLE ROAD WAKE COUNTY, NC THE PRES AT MOODY


JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM

DATE: 12/02/2024 SHEET TITLE: **OVERALL**

STAGE 2







STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT MOODY FARM

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024


SHEET TITLE:


EC STAGE 2 -**AREA A**


C3.6

http://nc811.org/remoteticketentry.h

North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry







STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR PRUSE ON OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT MOODY FARM

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:


EC STAGE 2 -**AREA B**


North Carolina 811 C3.7 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.h


CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval







Required Ground Stabilization Timeframes many calendar Timeframe variations days after ceasing and disturbance f slopes are 10' or less in length and are not steeper than 2:1, 14 days are 7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW -10 days for Falls Lake Watershed davs for perimeter dikes, swales, ditches, perimeter slopes and HQW Zone -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground

- 1. THIS PAGE IS SUBMITTED TO COMPLY WITH THE NPDES GENERAL STORMWATER PERMIT
- STORMWATER PERMIT NCG010000 ONLY.
- GENERAL STORMWATER PERMIT NCG010000.
- THE TOWN IS NOT AUTHORIZED TO ENFORCE THIS PAGE OF THE PLANS AND IT IS NOT A PART OF THE APPROVED PLANS FOR PURPOSES OF ENFORCEMENT ACTION UNDER THE

NPDES STABILIZATION LEGEND				
	NPDES STABILIZATION AREA 1			
	NPDES STABILIZATION AREA 2			
	NPDES STABILIZATION AREA 3			

STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR US ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

ENGINEERING

SOUTHEAST

ASSOCIATES

SERVE

MOODY

JOB NUMBER: 21-002 CHECKED BY: JK

DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

NPDES PLAN

North Carolina, *** 3 Days Before Digging ** SHEET NO. North Carolina 811 C3.10 811 or 1-800-632-4949

Remote Ticket Entry

http://nc811.org/remoteticketentry

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

ANCHOR - ASPHALT EMULSION @ 300 GALS/ACRE

9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND

SUPERPHOSPHATE - 500 LB/ACRE - 20% ANALYSIS MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW

6. SEED ON FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING

EQUIPMENT OR CULTIPACK AFTER SEEDING.

7. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.

120 lb./acre

25 lb./acre

Tall Fescue and ***Browntop Millet

***or Sorghum-Sudan Hybrids

July 15 - Aug 15

35 lb./acre

conditions; other seeding rate combinations are possible.

before mowing to keep fescue from being shaded out.

*Bahia grass shall not be used in City maintained areas.

Consult Erosion Control Officer or NRCS for additional alternatives for vegetating

denuded areas. The above vegetation rates are those which do well under local

***Temporary - Reseed according to optimum season for desired permanent

vegetation. Do not allow temporary cover to grow over 12 inches in height


Sept 1 - Mar 1


Tall Fescue

Add Abruzzi Rye or Annual Rye

8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 60% DAMAGED, RE-ESTABLISHED FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.

FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED. AGRICULTURAL LIMESTONE - 2 TONS/ACRE (3 TONS/ACRE IN CLAY SOILS) FERTILIZER - 1,000 LB/ACRE - 10-10-10





(IN FEET)

1 inch = 50



ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE


North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry


http://nc811.org/remoteticketent


Raleigh Water Review Officer


SHEET NO.:


C4.1
















CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

*** 3 Days Before Digging ** North Carolina 811

http://nc811.org/remoteticketentry.h

811 or 1-800-632-4949 Remote Ticket Entry

SHEET NO.: C5.0

ENGINEERING SOUTHEAST OF AUTOMOTOR OTAL OF AUTOMOTOR OF A PRELIMINARY

STIPULATION FOR REUSE


THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

AD RO, ITY,


JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

> SHEET TITLE: **OVERALL DRAINAGE**

> > **PLAN**



CITE	LEGEND
SIIE	LEGEND
	OPEN SPACE
	EXISTING WETLANDS
(MK)	MAIL KIOSK
	LOT LINES
	SETBACK
	PROPOSED ROW
	PROPOSED EOP
	PROPOSED CENTERLINE
	PROPOSED BACK OF CURB
	50' NEUSE RIPARIAN BUFFER
	BUFFER ZONE 1 AND 2
	TOP OF CREEK
(==)	PROPOSED SCM
	PROPOSED FENCE
	SIGHT TRIANGLE



CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

Remote Ticket Entry http://nc811.org/remoteticketentry.h

North Carolina 811

SHEET NO.: 811 or 1-800-632-4949

C5.1

SHEET TITLE:

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

DRAINAGE

PLAN A

ENGINEERING SASSOCIATES SOUTHEAST C-3881


PRELIMINARY


STIPULATION FOR REUSE


THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME.


USE OF THIS DRAWING FOR REFERENCE OF EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED


ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.























10-YEAR EROSION & SEDIMENT CONTROL TEMPORARY DIVERSION DITCH CALCULATIONS (2:1 SIDE SLOPES)

-	TDD#	DRAINAGE AREA (AC)	AVERAGE SLOPE (%)	WIDTH (FT)	DEPTH (FT)	V ₁₀ (FT/S)	CALCULATED τ (LBS/FT³)	RECOMMENDED LINER	LINER ALLOWABLE τ (LBS/FT³)
	1	1.79	3.12	6	1.5	4.52	1.89	AM. EXCELISOR CO.; CURLEX II.98; 2 NETS	2
	2	0.89	8.08	4	1	5.60	3.28	E. COAST ERO. BLANK.; COIR, 3 NETS	3.50
	3	0.34	0.84	4	1	1.85	0.37	JUTE NETTING	0.45
	4	0.77	4.03	4	1	3.92	1.61	AM. EXCELISOR CO.; CURLEX II.73; 2 NETS	1.75

NOTE: ALL TEMPORARY DIVERSION DITCHES (TDD) ARE TRIANGULAR.

TRACTIVE FORCE, τ , IS CALCULATED USING: $\tau = (\gamma)(D_{CHAN})(S_{CHAN})$

γ IS THE UNIT WEIGHT OF WATER (ASSUMED TO BE 62.4 LB/FT³)

VALUES SHOWN IN TABLE ABOVE ARE MINIMUM QUANTITIES AND DIMENSIONS

WOD IS ABBREVIATION FOR WIDTH OF DITCH

DBL IS DOUBLE BARELL PIPE

D_{CHAN} IS THE DEPTH OF FLOW IN THE CHANNEL (FT/FT)


S_{CHAN} IS THE SLOPE OF THE CHANNEL (FT/FT)

			. 2.00	LIN CALCULA	HIION2 TO	O-YEAR STO	JKIVI		
OUTLET ID	PIPE DIAMETER (IN)	PIPE VELOCITY (FPS)	STONE CLASS	STONE DEPTH (IN)	STONE MATERIAL (TONS)	GEO-TEXTILE (SY)	START WIDTH (FT)	END WIDTH (FT)	LENGTH (FT)
FES 100	18	6.40	В	12	2	7	3	9	6
FES 125	24	3.36	В	12	3	11	4	12	8
FES OS 100	24	2.99	В	12	3	11	4	12	8
FES 110	15	3.65	В	12	2	7	WOD	WOD	5
FES 120	15	2.45	В	12	2	7	WOD	WOD	5
EW 101	42	4.69	I	18	13	30	7	21	14
FES OS 200	18	1.12	В	12	2	7	3	9	6
FES 203	18	2.53	В	12	2	7	3	9	6
FES 300	36	3.54	I	18	10	23	6	18	12
FES OS 300	24	8.21	I	18	4	12	4	12	8
FES 400	24	3.26	В	12	3	11	4	12	8
FES OS 400	24	6.40	В	12	3	11	4	12	8
FES 410	18	3.71	В	12	2	7	3	9	6
FES 420	15	0.49	В	12	2	7	WOD	WOD	5
FES 500	30	5.26	В	12	5	16	5	15	10
FES OS 500	24	3.88	В	12	3	11	4	12	8
FES 602	18	4.12	В	12	3	10	WOD	WOD	6
EW 610	60 (DBL)	7.33	I	18	52	112	16	48	32

SSW	/R - STRUC	TURE TABLE	
STRUCTURE NAME:	DESCRIPTION	PIPES IN:	PIPES OUT
MH 2307	SSWR MH 5' RIM = 391.23 INV IN = 377.89 INV OUT = 377.69	8" PVC INV.=377.89	8" PVC INV.=377.69
MH 2098	SSWR MH 4' RIM = 388.87 INV IN = 377.87 INV OUT = 377.67	8" PVC INV.=377.87	8" PVC INV.=377.67
MH 2203	SSWR MH 5' RIM = 387.82 INV OUT = 369.38		8" PVC INV.=369.38
MH 2099	SSWR MH 4' RIM = 387.14 INV IN = 378.73 INV OUT = 378.53	8" PVC INV.=378.73	8" PVC INV.=378.53
MH 2100	SSWR MH 4' RIM = 386.29 INV OUT = 379.29		8" PVC INV.=379.29
MH 2308	SSWR MH 4' RIM = 384.19 INV OUT = 380.00		8" PVC INV.=380.00
MH 2097	SSWR MH 4' RIM = 381.39 INV IN = 372.29 INV OUT = 372.09	8" PVC INV.=372.29	8" PVC INV.=372.09
MH 2304	SSWR MH 4' RIM = 380.19 INV IN = 372.33 INV OUT = 371.27	8" PVC INV.=372.33	8" PVC INV.=371.27
MH 2204	SSWR MH 4' RIM = 379.49 INV OUT = 366.88		8" PVC INV.=366.88
MH 2305	SSWR MH 4' RIM = 378.75 INV IN = 371.92 INV OUT = 370.72	8" PVC INV.=371.92	8" PVC INV.=370.72
MH 2306	SSWR MH 4' RIM = 378.50 INV OUT = 372.45		8" PVC INV.=372.45
MH 2303	SSWR MH 4' RIM = 377.58 INV IN = 370.14 INV IN = 370.50 INV OUT = 369.94	8" PVC INV.=370.14 8" PVC INV.=370.50	8" PVC INV.=369.94
MH 2202	SSWR MH 4' RIM = 377.50 INV IN = 365.86 INV IN = 366.45 INV OUT = 365.66	8" PVC INV.=365.86 8" PVC INV.=366.45	8" PVC INV.=365.66
MH 2302	SSWR MH 4' RIM = 376.97 INV IN = 369.64 INV OUT = 369.44	8" PVC INV.=369.64	8" PVC INV.=369.44
MH 2301	SSWR MH 4' RIM = 375.81 INV IN = 368.57 INV OUT = 368.37	8" PVC INV.=368.57	8" PVC INV.=368.37
MH 2110	SSWR MH 4' RIM = 375.00 INV IN = 366.12 INV OUT = 365.92	8" PVC INV.=366.12	8" PVC INV.=365.92
MH 2111	SSWR MH 4' RIM = 374.79 INV IN = 367.08 INV OUT = 366.88	8" PVC INV.=367.08	8" PVC INV.=366.88
MH 2409	SSWR MH 5' RIM = 374.76 INV OUT = 357.25		8" PVC INV.=357.25
MH 2112	SSWR MH 4' RIM = 374.00 INV OUT = 367.56		8" PVC INV.=367.56
MH 2503	SSWR MH 4' RIM = 373.79 INV OUT = 364.20		8" PVC INV.=364.20
MH 2096	SSWR MH 4' RIM = 373.78 INV IN = 363.42 INV IN = 364.03 INV OUT = 362.33	8" PVC INV.=363.42 8" PVC INV.=364.03	8" PVC INV.=362.33
MH 2300	SSWR MH 4' RIM = 373.31 INV IN = 366.20 INV OUT = 366.00	8" PVC INV.=366.20	8" PVC INV.=366.00
MH 2201	SSWR MH 4' RIM = 372.52 INV IN = 364.50 INV OUT = 362.80	8" PVC INV.=364.50	8" PVC INV.=362.80
MH 2502	SSWR MH 4' RIM = 370.88 INV IN = 361.52 INV OUT = 361.32	8" PVC INV.=361.52	8" PVC INV.=361.32
MH 2406	SSWR MH 6' RIM = 370.35 INV IN = 346.56 INV OUT = 346.36	8" PVC INV.=346.56	8" PVC INV.=346.36

STRUCTURE NAME:	DESCRIPTION	PIPES IN:	PIPES OUT
MH 2407	SSWR MH 6' RIM = 369.82 INV IN = 347.39 INV OUT = 347.19	8" PVC INV.=347.39	8" PVC INV.=347.1
MH 2091	SSWR MH 5' RIM = 368.52 INV IN = 356.32 INV OUT = 356.02	8" PVC INV.=356.32	8" PVC INV.=356.03
MH 2200	SSWR MH 4' RIM = 368.37 INV IN = 361.77 INV IN = 360.27 INV OUT = 360.07	8" PVC INV.=361.77 8" PVC INV.=360.27	8" PVC INV.=360.0
MH 2501	SSWR MH 4' RIM = 367.90 INV IN = 359.70 INV OUT = 359.50	8" PVC INV.=359.70	8" PVC INV.=359.50
MH 2092	SSWR MH 4' RIM = 367.80 INV IN = 357.02 INV OUT = 356.82	8" PVC INV.=357.02	8" PVC INV.=356.8
MH 2408	SSWR MH 5' RIM = 367.77 INV IN = 350.46 INV IN = 348.66 INV OUT = 348.46	8" PVC INV.=350.46 8" PVC INV.=348.66	8" PVC INV.=348.40
MH 2095	SSWR MH 4' RIM = 367.73 INV IN = 359.71 INV IN = 359.51 INV OUT = 359.31	8" PVC INV.=359.71 8" PVC INV.=359.51	8" PVC INV.=359.3
MH 2093	SSWR MH 4' RIM = 366.85 INV IN = 357.69 INV OUT = 357.49	8" PVC INV.=357.69	8" PVC INV.=357.49
MH 2094	SSWR MH 4' RIM = 366.59 INV IN = 358.90 INV OUT = 358.70	8" PVC INV.=358.90	8" PVC INV.=358.70
MH 2088	SSWR MH 5' RIM = 363.81 INV IN = 345.20 INV IN = 345.20 INV OUT = 344.54	8" PVC INV.=345.20 8" PVC INV.=345.20	8" PVC INV.=344.54
MH 2500	SSWR MH 4' RIM = 363.57 INV IN = 352.85 INV OUT = 352.65	8" PVC INV.=352.85	8" PVC INV.=352.65
MH 2087	SSWR MH 5' RIM = 362.30 INV IN = 345.06 INV IN = 343.50 INV OUT = 343.30	8" PVC INV.=345.06 8" PVC INV.=343.50	8" PVC INV.=343.30
MH 2410	SSWR MH 4' RIM = 359.99 INV IN = 349.74 INV OUT = 349.54	8" PVC INV.=349.74	8" PVC INV.=349.54
MH 2411	SSWR MH 4' RIM = 358.00 INV OUT = 350.47		8" PVC INV.=350.4
MH 2090	SSWR MH 4' RIM = 357.70 INV IN = 351.18 INV OUT = 350.98	8" PVC INV.=351.18	8" PVC INV.=350.98
MH 2089	SSWR MH 4' RIM = 357.54 INV IN = 349.32 INV OUT = 349.12	8" PVC INV.=349.32	8" PVC INV.=349.12
MH 2086	SSWR MH 4' RIM = 354.04 INV IN = 342.75 INV OUT = 342.55	8" PVC INV.=342.75	8" PVC INV.=342.5!
MH 2085	SSWR MH 4' RIM = 352.24 INV IN = 341.94 INV OUT = 341.74	8" PVC INV.=341.94	8" PVC INV.=341.74
MH 2084	SSWR MH 4' RIM = 348.65 INV IN = 341.01 INV OUT = 340.81	8" PVC INV.=341.01	8" PVC INV.=340.8
MH 2082	SSWR MH 4' RIM = 347.52 INV IN = 338.24 INV OUT = 338.04	8" PVC INV.=338.24	8" PVC INV.=338.04
MH 2083	SSWR MH 4' RIM = 347.50 INV IN = 340.17 INV OUT = 339.97	8" PVC INV.=340.17	8" PVC INV.=339.9
MH 2081	SSWR MH 4' RIM = 346.57 INV IN = 335.99 INV OUT = 335.79	8" PVC INV.=335.99	8" PVC INV.=335.79
MH 208	SSWR MH 4' RIM = 345.16 INV IN = 334.53	8" PVC INV.=334.53	





STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

SCHEDULE

*** 3 Days Before Digging ***
North Carolina 811 SHEET NO.: C7.0 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.htt

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

DOWNSTREAM	UPSTREAM	DIDE CIZE	LENCTH	CLODE	DOWNSTREAM	UPSTREAM
STRUCTURE	STRUCTURE	PIPE SIZE	LENGTH	SLOPE	INVERT (FT)	INVERT (FT
CB 101	FES 100	18"	229.12	2.20%	363.00	368.04
CB 102	CB 101	18"	27.00	0.52%	368.14	368.28
CB 103 CB 104	CB 102 CB 103	18" 15"	45.91 27.00	3.48% 0.52%	368.38 370.18	369.98 370.32
CB 105	CB 103	15"	244.37	2.96%	370.18	377.31
CB 106	CB 105	15"	27.04	0.63%	378.23	378.40
CB 106A	CB 106	15"	6.01	0.50%	378.50	378.53
CB 107	CB 105	15"	252.43	2.97%	377.42	384.92
CB 111	FES 110	18"	96.03	0.58%	380.50	381.06
CB 111A	CB 111	15"	5.93	0.50%	381.16	381.19
CB 114	CB 111	15"	107.82	1.00%	381.37	382.45
CB 115	CB 114	15"	27.00	0.67%	382.55	382.73
CB 115A	CB 115	15"	6.01	0.50%	382.83	382.86
CB 116	CB 115	15"	59.00	0.75%	382.83	383.27
CB 116A	CB 116	15"	5.99	0.50%	382.93	382.96
CB 121	FES 120	15"	94.32	0.56%	368.50	369.03
CB 122	CB 121 CB 122	15" 15"	59.04 68.95	1.00%	369.13 369.82	369.72 370.51
CB 123 DI 126	FES 125	24"	68.95 41.51	0.50%	369.82	363.71
D1 12U		l 24 M 1 Outfa] 303.71
DOM::	ī	ivi i Oulta	ripe 3	ΙΝΙΙΝΙΑ		LIBOTET
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT
OS 101	FES OS 100	24"	53.97	1.39%	359.00	359.75
	. 20 00 200		PIPE SUM		000.00	
	Ι	3CIVI 2 - I	TIPE SUIV	IIVIAKT		
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT
YI 204	FES 203	18"	64.79	1.16%	361.50	362.25
	SC.	∟ M 2 Outfa	ll ₋ DIDF 9	Ι <u></u> ΣΕΙΝΛΙΝΛΔ	RV	
	T					LIDGEDEAN
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT
OS 201	FES OS 200	18"	72.00	1.04%	357.00	357.75
		SCM 3 - I	PIPE SUM	IMARY		
	LIDSTDEANA	JCIVI 3			DOWNSTREAM	UPSTREAM
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	INVERT (FT)	INVERT (FT
CB 301	FES 300	36"	42.07	0.50%	361.00	361.21
CB 302		2.5"				
	CB 301	36"	27.00	0.48%	361.31	361.44
CB 302	CB 301 CB 304	36"	27.00 95.97	0.48% 0.68%	361.31 362.31	361.44 361.65
CB 302	CB 304	30"	95.97	0.68%	362.31	361.65
CB 302 CB 303	CB 304 CB 301	30" 18"	95.97 73.03	0.68%	362.31 361.30	361.65 361.65
CB 302 CB 303 CB 306	CB 304 CB 301 CB 305	30" 18" 15"	95.97 73.03 27.00	0.68% 0.48% 1.14%	362.31 361.30 364.89	361.65 361.65 364.58
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306	30" 18" 15" 24" 24"	95.97 73.03 27.00 50.86 27.00 43.54	0.68% 0.48% 1.14% 0.49% 0.52% 1.00%	362.31 361.30 364.89 362.56 362.91 363.99	361.65 361.65 364.58 362.81 363.05 363.55
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308	30" 18" 15" 24" 24" 24"	95.97 73.03 27.00 50.86 27.00 43.54 59.52	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91%	362.31 361.30 364.89 362.56 362.91 363.99 363.34	361.65 361.65 364.58 362.81 363.05 363.55 365.07
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309	30" 18" 15" 24" 24" 24" 24"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311	30" 18" 15" 24" 24" 24" 24" 18"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312	30" 18" 15" 24" 24" 24" 24" 18" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 0.67%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312	30" 18" 15" 24" 24" 24" 24" 18" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312	30" 18" 15" 24" 24" 24" 24" 18" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 0.67%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315	30" 18" 15" 24" 24" 24" 24" 18" 15" 18"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317	30" 18" 15" 24" 24" 24" 24" 18" 15" 18" 18"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 1.00%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176	30" 18" 15" 24" 24" 24" 24" 18" 15" 18" 18" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.48	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 1.00% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323	30" 18" 15" 24" 24" 24" 24" 18" 15" 18" 15" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.48 55.87	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.00% 1.00% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 18" 24"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.00% 1.01% 1.00% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 18" 15" 15" 24" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.00% 1.01% 1.00% 0.50% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 333	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 330	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 15" 24" 15" 24"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 0.50% 0.50% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 333 CB 334	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 330 CB 330 CB 333	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 15" 24" 15" 24" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 1.00% 0.50% 0.50% 0.50% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 334 FES INLET 302 A	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 330 CB 330 CB 333 CB 302	30" 18" 24" 24" 24" 24" 18" 15" 18" 15" 24" 15" 24" 15" 24" 18"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 0.50% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 334 FES INLET 302 A FES INLET 301	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 330 CB 330 CB 330 CB 330	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 15" 24" 15" 24" 18" 24"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96 24.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 0.67% 1.00% 1.01% 0.50% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94 362.32	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19 362.44
CB 302 CB 303 CB 306 CB 307 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 334 FES INLET 302 A FES INLET 331 FES INLET 335 JB 176 YI 310	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 330 CB 330 CB 330 CB 330 CB 334 CB 309	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 24" 18" 18" 24" 18" 18" 18" 18" 18" 18" 18" 1	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96 24.00 79.65 24.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.01% 1.00% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04% 0.50% 0.50% 0.50% 1.04% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94 362.32 363.73 373.45 365.80	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19 362.44 363.85 373.85 366.04
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 333 CB 334 FES INLET 302 A FES INLET 331 FES INLET 335 JB 176 YI 310 YI 314	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 331 CB 302 CB 330	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 24" 18" 18" 24" 18" 18" 15" 24" 18" 18" 15" 24" 18" 15" 15" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96 24.00 24.00 79.65 24.00 35.50	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.01% 1.00% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04% 0.50% 0.50% 0.50% 1.04% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94 362.32 363.73 373.45 365.80 369.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19 362.44 363.85 373.85 366.04 371.00
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 334 FES INLET 302 A FES INLET 331 FES INLET 335 JB 176 YI 310 YI 314 YI 316	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 317 JB 176 CB 323 CB 323 CB 302 CB 330 CB 331 CB 302 CB 315 CB 315	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 24" 18" 15" 24" 18" 18" 15" 24" 18" 15" 15" 15" 15" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96 24.00 24.00 79.65 24.00 35.50 24.00	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.01% 1.00% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04% 0.50% 0.50% 0.50% 1.04% 0.50% 0.50% 0.50% 1.00% 2.99% 5.00%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94 362.32 363.73 373.45 365.80 369.94 371.20	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19 362.44 363.85 373.85 366.04 371.00 372.40
CB 302 CB 303 CB 306 CB 307 CB 308 CB 308 CB 309 CB 311 CB 312 CB 313 CB 315 CB 317 CB 319 CB 323 CB 325 CB 330 CB 332 CB 332 CB 333 CB 334 FES INLET 302 A FES INLET 331 FES INLET 335 JB 176 YI 310 YI 314	CB 304 CB 301 CB 305 CB 304 CB 307 CB 306 CB 308 CB 309 CB 311 CB 312 CB 312 CB 315 CB 315 CB 317 JB 176 CB 323 CB 302 CB 330 CB 331 CB 302 CB 330	30" 18" 15" 24" 24" 24" 18" 15" 18" 15" 24" 18" 18" 24" 18" 18" 18" 15" 24" 18" 18" 15" 24" 18" 15" 15" 15"	95.97 73.03 27.00 50.86 27.00 43.54 59.52 63.41 59.35 27.00 73.13 57.69 60.77 60.48 55.87 123.52 27.00 66.36 85.14 23.96 24.00 24.00 79.65 24.00 35.50	0.68% 0.48% 1.14% 0.49% 0.52% 1.00% 2.91% 3.00% 3.00% 1.01% 1.00% 0.50% 0.50% 0.50% 0.50% 0.51% 1.04% 0.50% 0.50% 0.50% 1.04% 0.50% 0.50%	362.31 361.30 364.89 362.56 362.91 363.99 363.34 365.15 367.15 369.94 369.43 370.26 370.94 373.95 374.35 361.54 362.90 362.67 363.20 361.94 362.32 363.73 373.45 365.80 369.94	361.65 361.65 364.58 362.81 363.05 363.55 365.07 367.05 368.93 370.12 370.16 370.84 371.55 374.25 374.63 362.16 363.04 363.00 363.63 362.19 362.44 363.85 373.85 366.04 371.00

DOWNSTREAM	UPSTREAM	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM	UPSTREAM
STRUCTURE	STRUCTURE 555.00				INVERT (FT)	INVERT (FT)
OS 301	FES OS 300	24" SCM 4 - I	PIPE SUN	1.38% IMARY	357.00	357.75
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
CB 401	FES 400	24"	34.25	0.50%	357.00	357.17
CB 402	CB 401	24"	27.00	0.50%	357.26	357.40
CB 403	CB 402	15"	42.39	0.50%	357.51	357.72
CB 404	CB 403	15"	27.00	0.50%	357.82	357.96
CB 405	CB 404	15"	118.81	2.35%	358.07	360.86
CB 406	CB 405	15"	118.49	1.31%	363.06	364.61
CB 407	CB 402	24"	45.60	0.50%	357.50	357.73
CB 408	CB 407	24"	71.73	0.64%	357.95	358.41
CB 408	CB 408A	15"	27.00	0.72%	358.88	358.68
CB 409 CB 409	CB 408 CB 409A	18" 15"	35.77	0.50% 1.38%	358.54	358.72
CB 409 CB 410	CB 409A CB 409	15"	27.00 117.30	1.38%	359.06 358.86	358.68 360.25
CB 410	CB 410A	15"	27.00	0.96%	360.90	360.64
CB 411	CB 410	15"	109.50	3.41%	360.58	364.31
CB 412	CB 411	15"	47.14	0.51%	364.41	364.65
CB 413	CB 412	15"	27.00	0.50%	364.75	364.89
FES INLET 407A	CB 407	15"	78.21	0.51%	357.83	358.23
YI 413A	CB 413	15"	11.88	1.00%	364.99	365.11
YI 421	FES 410	18"	79.66	1.00%	356.95	357.75
	SC	M 4 Outfa	II - PIPE S	SUMMA	RY	Г
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
OS 401	FES OS 400	24" SCM 5 - I	72.49 PIPE SUM	0.51%	353.38	353.75
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
CB 502	YI 501	24"	163.56	3.24%	347.25	352.55
CB 503	CB 502	15"	27.00	0.52%	353.30	353.44
CB 504	CB 502	24"	215.40	4.00%	352.65	361.27
CB 505	CB 504	24"	48.26	0.99%	361.37	361.85
CB 506	CB 505	24"	27.00	0.52%	362.36	362.50
CB 507	CB 506	24"	47.06	0.53%	362.58	362.83
CB 507A	CB 507	15"	6.00	0.50%	363.58	363.61
CB 508	CB 507	18"	27.00	0.52%	362.93	363.07
CB 511	CB 510	15"	27.00	0.89%	364.24	364.00
CB 511	CB 504	15"	64.21	1.32%	362.27	363.12
CB 513 CB 514	CB 505 CB 508	15" 15"	117.76 187.90	1.00% 3.69%	362.69 363.26	363.87 370.19
CB 514	CB 508	15"	27.53	0.51%	370.29	370.19
CB 516	CB 517	18"	27.02	1.06%	367.17	367.46
CB 517	CB 511	18"	115.87	2.68%	363.77	366.88
YI 501	FES 500	30"	45.55	0.50%	346.92	347.15
YI 509	CB 508	18"	24.00	0.86%	363.18	363.39
YI 513A	CB 513	15"	38.50	1.00%	363.87	364.26
	SC	M 5 Outfa	II - PIPE S	SUMMA	RY	
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
OS 501	FES OS 500	24"	72.55	1.03%	343.00	343.75
	Ι	Crossing	- East - P	IPE SUN	<u> </u>	LIBSTREAM
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
HW FES 603 JB 602	JB 602 EW 101	42" 42"	82.14 67.94	2.51% 0.50%	364.44 364.00	366.50 364.34
35 002	l	Crossing -	<u> </u>	<u> </u>		504.34
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
HW 611	EW 610	60"	83.38	1.80%	346.50	348.00
HW 613	EW 612	60"	83.38	1.80%	346.50	348.00
	Γ	Bypass -	TIPE SUN	TIVIAKY		Γ
DOWNSTREAM STRUCTURE	UPSTREAM STRUCTURE	PIPE SIZE	LENGTH	SLOPE	DOWNSTREAM INVERT (FT)	UPSTREAM INVERT (FT)
OD 401	FES 420	15"	24.00	0.50%	356.16	356.28
CB 421 CB 422	CB 421	15"	27.01	0.50%	356.41	356.55

27.01 0.50%

79.19 4.36%

CB 422

FES INLET 601

CB 421

FES 602

356.41

356.55

369.51

CB 101 RIM = 373.98	SCM 1 - St	ructure Table ————————————————————————————————————
CB 101	Structure Maifle	
CB 102	CB 101	INV IN = 368.140 INV OUT = 368.04
CB 103	CB 102	RIM = 373.87 INV IN = 368.380 INV OUT = 368.28
RIM = 382.57	CB 103	RIM = 375.04 INV IN = 370.080 INV IN = 370.180 INV OUT = 369.98
CB 105 INV IN = 377.420 INV IN = 378.225 INV OUT = 377.31 CB 106 RIM = 382.57 INV OUT = 378.500 INV OUT = 378.350 INV OUT = 378.500 INV OUT = 378.500 INV OUT = 378.500 INV OUT = 378.550 INV OUT = 378.550 INV OUT = 384.92 INV OUT = 384.92 INV IN = 381.37 INV IN = 381.360 INV OUT = 381.160 INV OUT = 381.160 INV OUT = 381.160 INV OUT = 381.160 INV OUT = 382.450 INV OUT = 382.830 INV OUT = 382.930 INV OUT = 382.930 INV OUT = 382.930 INV OUT = 369.030 INV IN = 36	CB 104	RIM = 375.04 INV OUT = 370.32
CB 106	CB 105	RIM = 382.57 INV IN = 377.420 INV IN = 378.229 INV OUT = 377.31
CB 106A INV OUT = 378.53 CB 107 RIM = 390.04 INV OUT = 384.92 RIM = 386.00 INV IN = 381.37 INV IN = 381.37 INV IN = 381.16 INV OUT = 381.16 INV OUT = 381.19 CB 111A RIM = 386.00 INV OUT = 381.19 RIM = 387.03 INV IN = 382.55 INV OUT = 382.45 RIM = 387.04 INV IN = 382.83 INV OUT = 382.93 INV OUT = 382.93 INV OUT = 382.93 INV OUT = 369.03 RIM = 374.00 INV IN = 369.13 INV OUT = 369.72 CB 123 RIM = 374.04 INV OUT = 369.72 CB 123 RIM = 375.01 INV OUT = 363.70 FES 100 RIM = 366.50 INV OUT = 363.70 FES 110 RIM = 364.52 INV IN = 363.00 FES 120 RIM = 360.37 INV IN = 363.50 FES 120 RIM = 360.37 INV IN = 363.50 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 363.20 INV IN = 363.20 INV IN =	CB 106	RIM = 382.57 INV IN = 378.500 INV OUT = 378.39
CB 107 INV OUT = 384.92 RIM = 386.00 INV IN = 381.377 INV IN = 381.160 INV OUT = 381.06 CB 111A RIM = 386.00 INV OUT = 381.19 RIM = 387.03 INV IN = 382.55 INV OUT = 382.45 RIM = 387.04 INV IN = 382.830 INV OUT = 382.830 INV OUT = 382.830 INV OUT = 382.930 INV OUT = 369.72 CB 116A RIM = 374.00 INV IN = 369.72 CB 122 RIM = 374.04 INV OUT = 369.72 CB 123 RIM = 374.04 INV OUT = 369.72 CB 124 RIM = 366.50 INV OUT = 363.70 FES 100 RIM = 364.52 INV IN = 363.000 FES 110 RIM = 370.02 INV IN = 363.500 FES 125 RIM = 370.02 INV IN = 363.500 FES 120 RIM = 363.300 FES 120 RIM = 363.300 FES 120 RIM = 363.300 RIM = 363.300 FES 120 RIM = 363.300 RIM = 363.300 RIM = 363.49 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 363.29 INV IN = 369.225 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 RIM = 368.90 INV IN = 363.49 INV I	CB 106A	RIM = 382.92 INV OUT = 378.53
CB 111	CB 107	RIM = 390.04 INV OUT = 384.92
CB 114 INV OUT = 381.19 CB 114 RIM = 387.03	CB 111	RIM = 386.00 INV IN = 381.372 INV IN = 381.160 INV OUT = 381.06
CB 114 INV IN = 382.550 INV OUT = 382.45 RIM = 387.04 INV IN = 382.830 INV IN = 382.830 INV OUT = 382.86 CB 115A RIM = 387.04 INV OUT = 382.86 RIM = 387.94 INV IN = 382.90 INV OUT = 382.90 CB 116A RIM = 387.94 INV OUT = 382.90 CB 121 RIM = 374.00 INV IN = 369.130 INV OUT = 369.03 CB 122 RIM = 374.04 INV OUT = 369.03 CB 123 RIM = 375.01 INV OUT = 369.72 CB 123 RIM = 375.01 INV OUT = 363.70 FES 100 RIM = 366.50 INV OUT = 363.70 FES 110 RIM = 364.52 INV IN = 363.000 FES 120 RIM = 370.02 INV IN = 368.500 FES 120 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 368.29 INV IN = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 37.00 RIM = 368.90 INV IN = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table	CB 111A	RIM = 386.00 INV OUT = 381.19
CB 115 INV IN = 382.836 INV OUT = 382.73 CB 115A RIM = 387.04 INV OUT = 382.86 RIM = 387.89 INV IN = 382.93 INV OUT = 382.96 RIM = 387.94 INV OUT = 382.96 RIM = 374.00 INV IN = 369.03 INV OUT = 369.03 RIM = 374.04 INV OUT = 369.03 RIM = 374.04 INV IN = 369.820 INV OUT = 369.72 CB 123 RIM = 375.01 INV OUT = 363.70 RIM = 366.50 INV OUT = 363.70 RIM = 366.50 INV IN = 363.000 FES 100 RIM = 370.02 INV IN = 363.500 FES 125 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 363.29 INV IN = 363.29 INV IN = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 363.20 INV IN = 363	CB 114	RIM = 387.03 INV IN = 382.550 INV OUT = 382.45
CB 115A INV OUT = 382.86 RIM = 387.89 INV IN = 382.930 INV OUT = 383.27 CB 116A RIM = 387.94 INV OUT = 382.96 RIM = 374.00 INV IN = 369.130 INV OUT = 369.03 RIM = 374.04 INV OUT = 369.72 CB 123 RIM = 375.01 INV OUT = 363.70 RIM = 366.50 INV OUT = 363.70 FES 100 RIM = 364.52 INV IN = 363.00 FES 110 RIM = 382.02 INV IN = 363.00 FES 120 RIM = 370.02 INV IN = 363.500 FES 125 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES 203 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 363.79 INV IN = 367.000 RIM = 363.79 INV IN = 357.000 RIM = 358.79 INV IN = 357.000 RIM = 358.79 INV IN = 357.000	CB 115	RIM = 387.04 INV IN = 382.830 INV IN = 382.830 INV OUT = 382.73
CB 116	CB 115A	RIM = 387.04 INV OUT = 382.86
CB 121	CB 116	RIM = 387.89 INV IN = 382.930 INV OUT = 383.27
CB 121	CB 116A	RIM = 387.94 INV OUT = 382.96
CB 122	CB 121	RIM = 374.00 INV IN = 369.130 INV OUT = 369.03
DI 126	CB 122	RIM = 374.04 INV IN = 369.820 INV OUT = 369.72
FES 100 RIM = 364.52 INV IN = 363.000 FES 110 RIM = 382.02 INV IN = 380.500 RIM = 370.02 INV IN = 368.500 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES 0S 100 RIM = 361.33 INV IN = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.495 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 366.00 INV OUT = 362.25 RIM = 358.79 INV IN = 357.000 RIM = 358.79 INV IN = 357.000	CB 123	RIM = 375.01 INV OUT = 370.51
FES 100 INV IN = 363.000 RIM = 382.02 INV IN = 380.500 RIM = 370.02 INV IN = 368.500 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.490 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 366.00 INV OUT = 362.25 RIM = 368.79 INV IN = 357.000 RIM = 358.79 INV IN = 357.000	DI 126	RIM = 366.50 INV OUT = 363.70
FES 110 INV IN = 380.500 RIM = 370.02 INV IN = 368.500 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.499 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 367.000 RIM = 358.79 INV IN = 357.000	FES 100	INV IN = 363.000
FES 120 INV IN = 368.500 RIM = 366.37 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.499 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000	FES 110	INV IN = 380.500
FES 125 INV IN = 363.500 SCM 1 Outfall - Structure Table Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.495 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000 RIM = 361.43 RIM = 361.43		INV IN = 368.500
Structure Name Details FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.495 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000 RIM = 361.43 RIM = 361.43	FES 125	INV IN = 363.500
FES OS 100 RIM = 361.33 INV IN = 359.000 OS 101 RIM = 363.49 INV OUT = 359.75 SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.495 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000 RIM = 361.43		
OS 101	Structure Name	
SCM 2 - Structure Table Structure Name Details FES 203 RIM = 363.29 INV IN = 361.499 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000		INV IN = 359.000
Structure Name Details FES 203 RIM = 363.29 INV IN = 361.499 YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000		INV OUT = 359.75
FES 203 RIM = 363.29 INV IN = 361.499 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details RIM = 358.79 INV IN = 357.000		
YI 204 RIM = 366.00 INV OUT = 362.25 SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000		
SCM 2 Outfall - Structure Table Structure Name Details FES OS 200 RIM = 358.79 INV IN = 357.000	YI 204	
FES OS 200 RIM = 358.79 INV IN = 357.000	SCM 2 Outfall	
INV IN = 357.000		
INV IN = 357.000	FES OS 200	
US 201 INIVIOLIT 35775	OS 201	

	SCM 3 - St Structure Name	ructure Table Details
.98 3.140 8.040	CB 301	RIM = 366.14 INV IN = 361.310 INV IN = 361.303 INV OUT = 361.210
.87 3.380 8.280	CB 302	RIM = 366.04 INV IN = 361.542 INV IN = 361.940 INV IN = 361.654
0.080 0.180 09.980	CB 303	RIM = 366.75 INV OUT = 361.651
.04 0.320	CB 304	RIM = 366.98 INV IN = 362.560
.57 7.420 3.229 7.310	CB 305	RIM = 368.93 INV OUT = 364.893
.57	CB 306	RIM = 368.91 INV IN = 364.584
.92 8.530	CB 307	RIM = 363.987 RIM = 367.04 INV IN = 362.910
.04	CB 307	INV OUT = 362.810 RIM = 367.09
.00 372 160	CB 308	INV IN = 363.340 INV IN = 363.550 INV OUT = 363.050
.00 .1.190	CB 309	RIM = 370.04 INV IN = 365.150 INV IN = 365.800 INV OUT = 365.070
.03 2.550 2.450	CB 311	RIM = 373.03 INV IN = 367.150 INV OUT = 367.050
.04 2.830 2.830 2.730	CB 312	RIM = 374.74 INV IN = 369.430 INV IN = 369.942 INV IN = 369.936 INV OUT = 368.930
.04 2.860 .89	CB 313	RIM = 374.73 INV OUT = 370.122
2.930 3.270 .94	CB 315	RIM = 375.97 INV IN = 370.260 INV IN = 371.198 INV OUT = 370.160
.00 .130 .9.030	CB 317	RIM = 376.00 INV IN = 370.940 INV IN = 371.601 INV OUT = 370.840
.04 0.820 9.720	CB 319	RIM = 377.14 INV IN = 373.450 INV IN = 373.255 INV OUT = 371.550
.50 .3.708	CB 323	RIM = 378.04 INV IN = 374.350 INV IN = 374.750 INV OUT = 374.248
.52 3.000	CB 325	RIM = 378.78 INV OUT = 374.629
.02 0.500 .02 3.500	CB 330	RIM = 367.00 INV IN = 362.670 INV IN = 362.315 INV IN = 362.900 INV OUT = 362.160
.37 3.500 ole	CB 332	RIM = 367.03 INV OUT = 363.040
.33	CB 333	RIM = 367.90 INV IN = 363.200 INV OUT = 363.000
.49	CB 334	RIM = 368.63 INV IN = 363.730 INV OUT = 363.630
9.750	FES 300	RIM = 363.88 INV IN = 361.000
.29	FES INLET 302 A	RIM = 363.71 INV OUT = 362.190
499 .00 .2.250	FES INLET 331	RIM = 363.96 INV OUT = 362.435 RIM = 365.37
ole	FES INLET 335	INV OUT = 363.850 RIM = 378.03
.79 7.000	JB 176	INV IN = 373.945 INV OUT = 373.848
.43 7.750	YI 310	RIM = 372.06 INV OUT = 366.040 RIM = 378.00
- -	YI 314	INV OUT = 370.996 RIM = 377.58
	YI 316 	INV OUT = 372.398 RIM = 376.93
	YI 320	RIM = 378.58 INV OUT = 373.495
	YI 322	RIM = 385.27 INV OUT = 379.500
	YI 324	RIM = 382.30 INV IN = 377.698 INV OUT = 376.110
		1144 001 - 3/0.110

		SCM 3 Outfall	- Structure Table
		Structure Name	Details
		FES OS 300	RIM = 359.33 INV IN = 357.00
		OS 301	RIM = 361.38 INV OUT = 357.7
		SCM 4 - S1	tructure Table
		Structure Name	Details
		CB 401	RIM = 363.04 INV IN = 357.26 INV OUT = 357.1
		CB 402	RIM = 363.02 INV IN = 357.51 INV IN = 357.50 INV OUT = 357.40
		CB 403	RIM = 363.00 INV IN = 357.82 INV OUT = 357.7
		CB 404	RIM = 363.00 INV IN = 358.07 INV OUT = 357.9
		CB 405	RIM = 368.09 INV IN = 363.06 INV OUT = 360.80
		CB 406	RIM = 372.03 INV OUT = 364.63
		CB 407	RIM = 362.81 INV IN = 357.94 INV IN = 357.83 INV OUT = 357.73
		CB 408	RIM = 362.04 INV IN = 358.68 INV IN = 358.54 INV OUT = 358.40
		CB 408A	RIM = 362.03 INV OUT = 358.8
		CB 409	RIM = 362.04 INV IN = 358.68 INV IN = 358.86 INV OUT = 358.72
		CB 409A	RIM = 362.16 INV OUT = 359.0
		CB 410	RIM = 364.99 INV IN = 360.58 INV IN = 360.64 INV OUT = 360.25
		CB 410A	RIM = 364.99 INV OUT = 360.90
		CB 411	RIM = 368.85 INV IN = 364.41 INV OUT = 364.3
		CB 412	RIM = 369.03 INV IN = 364.75 INV OUT = 364.6
		CB 413	RIM = 369.03 INV IN = 364.99 INV OUT = 364.88
_		FES 400	RIM = 358.79 INV IN = 357.00
		FES 410	RIM = 358.47 INV IN = 356.95
		FES INLET 407A	RIM = 359.75 INV OUT = 358.23
		YI 413A	RIM = 369.90 INV OUT = 365.10
		YI 421	RIM = 363.00 INV OUT = 357.75
		SCM 4 Outfall	- Structure Table
		Structure Name	Details
		FES OS 400	RIM = 355.71 INV IN = 353.38
		OS 401	RIM = 357.50 INV OUT = 353.7
	I		

ructure Table	SCM 5	- Structure Table
Details	Structure Nam	ne Details
RIM = 359.33 NV IN = 357.000 RIM = 361.38	CB 502	RIM = 357.04 INV IN = 352.650 INV IN = 353.300
V OUT = 357.750	CB 503	INV OUT = 352.550 RIM = 357.04
ure Table	CB 303	INV OUT = 353.440
Details RIM = 363.04 NV IN = 357.265 V OUT = 357.170	CB 504	RIM = 366.04 INV IN = 361.370 INV IN = 362.270 INV OUT = 361.270
RIM = 363.02 NV IN = 357.510 NV IN = 357.503 V OUT = 357.400	CB 505	RIM = 367.77 INV IN = 362.360 INV IN = 362.690 INV OUT = 361.850
RIM = 363.00 NV IN = 357.820 V OUT = 357.720	CB 506	RIM = 367.48 INV IN = 362.580 INV OUT = 362.500
RIM = 363.00 NV IN = 358.070 V OUT = 357.955	CB 507	RIM = 367.03 INV IN = 362.930 INV IN = 363.580 INV OUT = 362.830
RIM = 368.09 NV IN = 363.060 V OUT = 360.860	CB 507A	RIM = 367.04 INV OUT = 363.610
RIM = 372.03 V OUT = 364.610 RIM = 362.81	CB 508	RIM = 367.03 INV IN = 363.260 INV IN = 363.180 INV OUT = 363.070
NV IN = 357.948 NV IN = 357.830 V OUT = 357.731	CB 510	RIM = 368.57 INV OUT = 364.240
RIM = 362.04 NV IN = 358.683 NV IN = 358.545 V OUT = 358.409	CB 511	RIM = 368.61 INV IN = 364.000 INV IN = 363.770 INV OUT = 363.115
RIM = 362.03 V OUT = 358.877	CB 513	RIM = 369.04 INV IN = 363.870 INV OUT = 363.868
RIM = 362.04 NV IN = 358.683 NV IN = 358.862 V OUT = 358.724	CB 514	RIM = 374.04 INV IN = 370.290 INV OUT = 370.190
RIM = 362.16 V OUT = 359.056	CB 515	RIM = 374.10 INV OUT = 370.430
RIM = 364.99 NV IN = 360.580	CB 516	RIM = 372.04 INV OUT = 367.458
NV IN = 360.643 V OUT = 360.250 RIM = 364.99	CB 517	RIM = 372.04 INV IN = 367.172 INV OUT = 366.880
V OUT = 360.903 RIM = 368.85	FES 500	RIM = 349.26 INV IN = 346.922
NV IN = 364.410 V OUT = 364.310 RIM = 369.03	YI 501	RIM = 350.00 INV IN = 347.250 INV OUT = 347.150
NV IN = 364.750 V OUT = 364.650	YI 509	RIM = 367.00 INV OUT = 363.387
RIM = 369.03 NV IN = 364.990 V OUT = 364.885	YI 513A	RIM = 369.89 INV OUT = 364.255
RIM = 358.79		tfall - Structure Table
NV IN = 357.000 RIM = 358.47	Structure Nam FES OS 500	RIM = 345.33
NV IN = 356.953 RIM = 359.75 V OUT = 358.232	OS 501	INV IN = 343.000 RIM = 347.43 INV OUT = 343.750
RIM = 369.90	Culvert Cross	sing - East - Structure Table
V OUT = 365.109	Structure Nar	
RIM = 363.00 V OUT = 357.750	EW 101	RIM = 367.96 INV IN = 364.000
ructure Table	HW FES 603	RIM = 370.46
Details		INV OUT = 366.500
RIM = 355.71 NV IN = 353.380	JB 602	RIM = 371.25 INV IN = 364.440 INV OUT = 364.340
V OUT = 353.750	M = 357.50 OUT = 353.750	
	Structure Na	me Details

	Bypass - Structure Table			
	Structure Name	Details		
)	CB 421	RIM = 360.04 INV IN = 356.414 INV OUT = 356.27		
, 	CB 422	RIM = 360.04 INV OUT = 356.54		
_	FES 420	RIM = 357.68 INV IN = 356.159		
)	FES 602	RIM = 367.85 INV IN = 366.056		
	FES INLET 601	RIM = 371.30 INV OUT = 369.50		
)				

Bypass - Structure Table		
Structure Name	Details	
CB 421	RIM = 360.04 INV IN = 356.414 INV OUT = 356.27	
CB 422	RIM = 360.04 INV OUT = 356.54	
FES 420	RIM = 357.68 INV IN = 356.159	
FES 602	RIM = 367.85 INV IN = 366.056	
FES INLET 601	RIM = 371.30 INV OUT = 369.50	

会。ASSOCIATES SOUTHEAST。

STIPULATION FOR REUSE THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

FARM

ROLESVILLE ROAD WAKE COUNTY, NC THE PRESERVE AT MOODY

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

SCHEDULE

C7.1

North Sill SHEET NO.:

North Carolina 811 811 or 1-800-632-4949

RIM = 352.08

INV IN = 346.500

RIM = 352.08

INV IN = 346.500

RIM = 353.58

INV OUT = 348.000

RIM = 353.58

INV OUT = 348.000

EW 610

EW 612

HW 611

HW 613

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.


Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once


issued will invalidate this approval.


City of Raleigh Development Approval


*** 3 Days Before Digging *** Remote Ticket Entry http://nc811.org/remoteticketentry.htt Raleigh Water Review Officer

























STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT FARM

MOODY


JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM


DATE: 12/02/2024 SHEET TITLE:


MULBERRY PLAN AND PROFILE


811 or 1-800-632-4949


SHEET NO.: C9.1














SEWER OUTFALL (B) AT VINTAGE VINERY COURT PROFILE

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

*** 3 Days Before Digging ***
North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.ht





STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

ROLESVILLE ROAD WAKE COUNTY, NC THE PRESERVE AT FARM

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM


DATE: 12/02/2024


SHEET TITLE:

SEWER OUTFALL

SHEET NO.:

C13.0







STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERNCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT MOODY FARM

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

SEWER OUTFALL

*** 3 Days Before Digging *** North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry

SHEET NO.: C13.1

http://nc811.org/remoteticketentry.htm

Raleigh Water Review Officer


CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION


Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.

Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once

issued will invalidate this approval.

City of Raleigh Development Approval





CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry Raleigh Water Review Officer http://nc811.org/remoteticketentry.htm

SEWER OUTFALL *** 3 Days Before Digging ***

SHEET NO.:

SHEET TITLE:

THE PRESERVE AT

MOODY

JOB NUMBER: 21-002 CHECKED BY: JK


DRAWN BY: RC & SM DATE: 12/02/2024

C13.2

STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

ROLESVILLE ROAD WAKE COUNTY, NC



ASSOCIATES



STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

ROLESVILLE ROAD WAKE COUNTY, NC THE PRESERVE AT FARM MOODY

JOB NUMBER: 21-002 CHECKED BY: JK

DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

SEWER OUTFALL

C13.3

*** 3 Days Before Digging *** North Carolina 811 811 or 1-800-632-4949

signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.


Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once


Raleigh Water Review Officer

issued will invalidate this approval.

City of Raleigh Development Approval

SHEET NO.: Remote Ticket Entry
http://nc811.org/remoteticketentry.ht





*** 3 Days Before Digging ***
North Carolina 811
811 or 1-800-632-4949
Remote Ticket Entry
http://nc811.org/remoteticketentry.htm

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans.

Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once

Raleigh Water Review Officer

issued will invalidate this approval.

City of Raleigh Development Approval ____

CONTROL DETAILS

sigging ***
811

SHEET NO.:

SERVE

THE PRES AT MOODY I

JOB NUMBER: 21-002

CHECKED BY: JK

DRAWN BY: RC & SM

DATE: 12/02/2024

SHEET TITLE:

EROSION

CD1

° AMERICAN

ENGINEERING

ASSOCIATES

SOUTHEAST

C-3881

STIPULATION FOR REUSE

HIS DRAWING WAS PREPARED FOR USIN THE SPECIFIC SITE, NAMED HEREON

CONTEMPORANEOUSLY WITH ITS ISSUE

SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME.

USE OF THIS DRAWING FOR REFERENCE OF EXAMPLE ON ANOTHER PROJECT REQUIRES

THE SERVICES OF PROPERLY LICENSEL

ARCHITECTS AND ENGINEERS. REPRODUCTION


F THIS DRAWING FOR REUSE ON

ANOTHER PROJECT IS NOT AUTHORIZED

AND MAY BE CONTRARY TO THE LAW.

FARM

DATE AS LISTED, HEREON. AND IT IS NOT




SHEET NO.:


811 or 1-800-632-4949


Remote Ticket Entry


http://nc811.org/remoteticketentry.


Raleigh Water Review Officer


























Raleigh Water Review Officer


*** 3 Days Before Digging ***
North Carolina 811
811 or 1-800-632-4949
Remote Ticket Entry
http://nc811.org/remoteticketentry.htm

AMERICAN

American Engineering Associates - Southeast, P.A. 4020 Westchase Boulevard, Suite 450
Raleigh, NC 27607







STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


THE PRESERVE
AT
MOODY FARM
ROLESVILLE ROAD


JOB NUMBER: 21-002
CHECKED BY: JK
DRAWN BY: RC & SM

DATE: 12/02/2024

EROSION
CONTROL
DETAILS

SHEET NO.:





*Horizontal staple spacing should be altered if necessary to allow staples to secure the critical points along the channel surface.

Instructions

- 1. Prepare soil before installing rolled erosion control products (RECPs), including any necessary application of lime, fertilizer, and seed. Ground surface must be free of debris, rocks, clay clods and raked smooth sufficient to allow intimate contact of the RECP with the soil over the entirety of the installation.
- 2. Begin at the top of the channel by anchoring the RECPs in a 6" (15 cm) deep X 6" (15 cm) wide trench with approximately 12" (30 cm) of RECPs extended beyond the up-slope portion of the trench. Use ShoreMax mat at the channel/culvert outlet as supplemental scour protection as needed. Anchor the RECPs with a row of staples/stakes/pins approximately 12" (30 cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Apply seed to the compacted soil and fold the remaining 12" (30 cm) portion of RECPs back over the seed and compacted soil. Secure RECPs over compacted soil with a row of staples/stakes/pins spaced approximately 12" (30 cm) apart across the width
- 3. Roll center RECPs in direction of water flow in bottom of channel. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes/pins in appropriate locations as shown in the staple pattern guide.
- 4. Place consecutive RECPs end-over-end (Shingle style) with a 4"- 6" (10 - 15 cm) overlap. Use a double row of staples staggered 4" apart and 4" on center to secure RECPs. 5. Full length edge of RECPs at top of side slopes must be anchored with a row of staples/stakes/pins spaced at S_T apart in a 6" (15 cm) deep X 6"(15 cm) wide trench. Backfill and compact the trench after stapling.
- 6. Adjacent RECPs must be overlapped approximately 4"- 6" (10 - 15 cm) and secured with staples/stakes/pins at S_T . 7. In high flow channel applications a staple check slot is recommended at 30 to 40 foot (9 -12m) intervals. Use a double row of staples staggered 6" (15 cm) apart and 12" (30 cm) on center over entire width of the channel.
- 8. The terminal end of the RECPs must be anchored with a row of staples/stakes/pins spaced at S_T apart in a 6" (15 cm) deep X 6" (15 cm) wide trench. Backfill and compact the trench after stapling.
- 9. Fasteners should provide a minimum of twenty pounds of pullout resistance. Six-inch (10 cm) X one-inch (2.5 cm) eleven gauge staples are typically adequate. In loose soils, longer staples may be necessary, twist pins can provide the greatest pullout resistance. In hard or rocky soils, straight pins may by used where staples or twist pins are refused, provided the minimum pullout requirements are met. Bio-degradable fasteners shall not be used with VMax (TRM) or TMax (HPTRM) materials.

Staple Pattern	
Guide	
4 - 6" 10 - 15 cm	
Plan View	
	•
	$\begin{array}{ c c c c c c c c c c c c c c c c c c c$
	\circ \uparrow S_T
W W	Unroll Direction
Underneath Roll Roll Overlap	

Pin / Staple / Twist Pin, as appropriate for field conditions

Upper Roll-

	Staple Pattern
Dimension	E
W _T	20" (50 cm)
L _T	20" (50 cm)
S _T	18" (45 cm)
Nominal Frequency	3.8 / SY

Instructions 1. Prepare soil before installing rolled erosion control products (RECPs), including any necessary application of lime, fertilizer, and seed. Ground surface must be free of debris, rocks, clay clods and raked smooth sufficient to allow intimate contact of the RECP with the soil over the entirety of the installation.

(10 - 15cm)

12" (30 cm)

2. Begin at the top of the slope by anchoring the RECPs in a 6" (15 cm) deep X 6" (15 cm) wide trench. Anchor the RECPs with a row of staples/stakes/pins spaced at S_T apart in the bottom of the trench. Backfill and compact the trench after stapling and fold the roll over downslope. Secure RECPs over compacted soil with a row of staples/stakes/pins spaced at S_T apart across the width of the RECPs.


3. Roll the RECPs (A) down or (B) horizontally across the slope. RECPs will unroll with appropriate side against the soil surface. All RECPs must be securely fastened to soil surface by placing staples/stakes/pins in appropriate locations as shown in the staple pattern guide. RollMax RECPs and ECBs should utilize Staple Pattern C, TRMs and VMax materials should utilize Staple Pattern D.

4. The edges of parallel RECPs must be stapled with approximately 4" - 6" (10 - 15 cm) overlap. 5. Consecutive RECPs spliced down the slope must overlapped with the upstream mat atop the downstream mat (shingle style). The overlap should be 4" - 6" (10 - 15 cm).

6. At the terminal end, secure each mat across the width with a row of staples/stakes/pins spaced at S_T . If exposed to flow, foot traffic, wind uplift or other disruption, trench the terminal end in as shown in

7. Fasteners should provide a minimum of twenty pounds of pullout resistance. Six-inch (10 cm) X one-inch (2.5 cm) eleven gauge staples are typically adequate. In loose soils, longer staples may be necessary, twist pins can provide the greatest pullout resistance. In hard or rocky soils, straight pins may by used where staples or twist pins are refused, provided the minimum pullout requirements are met. Bio-degradable fasteners shall not be used with VMax (TRM) or TMax (HPTRM) materials.

Staple Pattern Guide



Pin / Staple / Twist Pin, as appropriate for field conditions

	Staple	Pattern		
Dimension	С	D		
W_T	30" (75 cm)	24" (60 cm)		
L _T	30" (75 cm)	20" (50 cm)		
S _T	18" (45 cm)	18" (45 cm)		
Nominal Frequency	1.7 / SY	3.0 / SY		
Application	ECB (Degradable)	TRM (Permanent)		
*Note: Staple Pattern A and B used prior to 8/2019 have been discontinued.				

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer



HIS DRAWING WAS PREPARED FOR US N THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OF EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION F THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

STIPULATION FOR REUSE

° AMERICAN

ENGINEERING

ASSOCIATES

SOUTHEAST

THE PRESERVE AT MOODY FARM

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

EROSION CONTROL DETAILS

SHEET NO.:

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be

were delayed shall be noted in the Inspection Record. Inspect (during normal aspection records must include business hours) (1) Rain gauge Daily rainfall amounts If no daily rain gauge observations are made during weekend or maintained in good working holiday periods, and no individual-day rainfall information available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection i needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division 1. Identification of the measures inspected (2) E&SC At least once per 2. Date and time of the inspection 3. Name of the person performing the inspection, and within 24 hours of a rain 4. Indication of whether the measures were operating event > 1.0 inch in properly, 5. Description of maintenance needs for the measure 24 hours 5. Description, evidence, and date of corrective actions taken. (3) Stormwater At least once per Identification of the discharge outfalls inspected, outfalls (SDOs) and within 24 3. Name of the person performing the inspection hours of a rain 4. Evidence of indicators of stormwater pollution such as oil event > 1.0 inch in sheen, floating or suspended solids or discoloration. 24 hours Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken. (4) Perimeter of At least once per of the following shall be made . Actions taken to clean up or stabilize the sediment that has lef and within 24 hours of a rain the site limits. event > 1.0 inch in 2. Description, evidence, and date of corrective actions taken, and 24 hours 3. An explanation as to the actions taken to control future

If the stream or wetland has increased visible sedimentation or At least once per stream has visible increased turbidity from the construction

and within 24 activity, then a record of the following shall be made: hours of a rain Description, evidence and date of corrective actions taken, a event > 1.0 inch in Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit After each phase The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm of grading drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization

electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records. measures have been provided within the required timeframe or an assurance that they will be provided as Documentation to be Retained for Three Years soon as possible. All data used to complete the e-NOI and all inspection records shall be maintained for a period NOTE: The rain inspection resets the required 7 calendar day inspection requirement of three years after project completion and made available upon request. [40 CFR 122.41]

ediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather) Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

PART II, SECTION G, ITEM (4)

DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

(a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items, (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,

(c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,

(d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above, (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that Must be Reported

Permittees shall report the following occurrences: (a) Visible sediment deposition in a stream or wetland.

(b) Oil spills if:

122.41(m)(3)

SELF-INSPECTION, RECORDKEEPING AND REPORTING

The approved E&SC plan as well as any approved deviation shall be kept on the site. The

approved E&SC plan must be kept up-to-date throughout the coverage under this permit.

Documentation Requirements

Initial and date each E&SC measure on a copy

E&SC measure shown on the approved E&SC

plan. This documentation is required upon the

initial installation of the E&SC measures or if

the E&SC measures are modified after initial

Initial and date a copy of the approved E&SC

Initial and date a copy of the approved E&SC

plan or complete, date and sign an inspection

report to indicate compliance with approved

Complete, date and sign an inspection report.

Initial and date a copy of the approved E&SC

plan or complete, date and sign an inspection

report to indicate the completion of the

report to indicate completion of the

plan or complete, date and sign an inspection

The following items pertaining to the E&SC plan shall be kept on site and available for

and does not significantly deviate from the of the approved E&SC plan or complete, date

installation.

construction phase

corrective action

In addition to the E&SC plan documents above, the following items shall be kept on the

site and available for inspectors at all times during normal business hours, unless the

Division provides a site-specific exemption based on unique site conditions that make

b) Records of inspections made during the previous twelve months. The permittee shall

record the required observations on the Inspection Record Form provided by the

Division or a similar inspection form that includes all the required elements. Use of

(a) This General Permit as well as the Certificate of Coverage, after it is received.

ground cover specifications.

locations, dimensions and relative elevations | and sign an inspection report that lists each

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

Item to Document

shown on the approved E&SC plan.

(a) Each E&SC measure has been installed

(b) A phase of grading has been completed.

(c) Ground cover is located and installed

in accordance with the approved E&SC

(d) The maintenance and repai

have been performed.

to E&SC measures.

requirements for all E&SC measures

(e) Corrective actions have been taken

this requirement not practical:

2. Additional Documentation to be Kept on Site

inspection at all times during normal business hours.

They are 25 gallons or more,

They are less than 25 gallons but cannot be cleaned up within 24 hours,

 They cause sheen on surface waters (regardless of volume), or • They are within 100 feet of surface waters (regardless of volume).

Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

(e) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements			
(a) Visible sediment	Within 24 hours, an oral or electronic notification.			
deposition in a	Within 7 calendar days, a report that contains a description of the			
stream or wetland	sediment and actions taken to address the cause of the deposition.			
	Division staff may waive the requirement for a written report on a case-by-case basis.			
	If the stream is named on the <u>NC 303(d) list</u> as impaired for sediment-			
	related causes, the permittee may be required to perform additional			
	monitoring, inspections or apply more stringent practices if staff			
	determine that additional requirements are needed to assure compliant			
(I-) O:I:III	with the federal or state impaired-waters conditions.			
(b) Oil spills and release of	Within 24 hours, an oral or electronic notification. The notification whell include information objects the data time, nature values and			
hazardous	shall include information about the date, time, nature, volume and			
substances per Item	location of the spill or release.			
1(b)-(c) above				
(c) Anticipated	A report at least ten days before the date of the bypass, if possible.			
bypasses [40 CFR	The report shall include an evaluation of the anticipated quality and			
122.41(m)(3)]	effect of the bypass.			
(1)	effect of the bypass.			

 Within 24 hours, an oral or electronic notification. (d) Unanticipated bypasses [40 CFR Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass (e) Noncompliance Within 24 hours, an oral or electronic notification with the conditions Within 7 calendar days, a report that contains a description of the of this permit that noncompliance, and its causes; the period of noncompliance,

may endanger including exact dates and times, and if the noncompliance has not health or the been corrected, the anticipated time noncompliance is expected to environment[40] continue; and steps taken or planned to reduce, eliminate, and CFR 122.41(I)(7)] prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6). Division staff may waive the requirement for a written report on a

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING EFFECTIVE: 04/01/

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMI mplementing the details and specifications on this plan sheet will result in the constructio

activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

Required Ground Stabilization Timeframes Stabilize within this many calendar Timeframe variations Site Area Description days after ceasing and disturbance (a) Perimeter dikes, swales, ditches, ar None perimeter slopes o) High Quality Water (HQW) Zones (c) Slopes steeper than

SECTION E: GROUND STABILIZATION

flatter than 4:1

Rolled erosion control products with or

f slopes are 10' or less in length and are not steeper than 2:1, 14 days are 7 days for slopes greater than 50' in ength and with slopes steeper than 4:1 ·7 days for perimeter dikes, swales, (d) Slopes 3:1 to 4:1 ditches, perimeter slopes and HQW -10 days for Falls Lake Watershed days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zon (e) Areas with slopes -10 days for Falls Lake Watershed unless

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the

techniques in the table below: **Temporary Stabilization** • Temporary grass seed covered with straw or Permanent grass seed covered with straw or other mulches and tackifiers other mulches and tackifiers Hydroseeding Geotextile fabrics such as permanent soil

without temporary grass seed Hydroseeding Appropriately applied straw or other mulch
 Shrubs or other permanent plantings covered Plastic sheeting with mulch • Uniform and evenly distributed ground cover sufficient to restrain erosion

reinforcement matting

 Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.

Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions. Provide ponding area for containment of treated Stormwater before discharging

Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE Maintain vehicles and equipment to prevent discharge of fluids.

Provide drip pans under any stored equipment. Identify leaks and repair as soon as feasible, or remove leaking equipment from the

Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible) Remove leaking vehicles and construction equipment from service until the problem

has been corrected. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

Never bury or burn waste. Place litter and debris in approved waste containers. Provide a sufficient number and size of waste containers (e.g dumpster, trash

receptacle) on site to contain construction and domestic wastes. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available. Locate waste containers on areas that do not receive substantial amounts of runoff

from upland areas and does not drain directly to a storm drain, stream or wetland. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.

Anchor all lightweight items in waste containers during times of high winds. Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.

Dispose waste off-site at an approved disposal facility. 9. On business days, clean up and dispose of waste in designated waste containers.

Contain liquid wastes in a controlled area.

PAINT AND OTHER LIQUID WASTE

Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.

Containment must be labeled, sized and placed appropriately for the needs of site. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from

PORTABLE TOILETS

construction sites.

Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.

Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace


EARTHEN STOCKPILE MANAGEMENT

with properly operating unit.

Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably

Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile

Provide stable stone access point when feasible. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



ONSITE CONCRETE WASHOUT STRUCTURE WITH LINER

1. ACTUAL LOCATION DETERMINED IN FIELD 2. THE CONCRETE WASHOUT STRUCTURES SHALL BE REACHES 75% OF THE STRUCTURES CAPACITY. 3.CONCRETE WASHOUT STRUCTURE NEEDS TO BE LEARY MARKED WITH SIGNAGE NOTING DEVICE

1. ACTUAL LOCATION DETERMINED IN 2. THE CONCRETE WASHOUT STRUCTURES

AND/OR SOLID REACHES 75% OF THE ADEQUATE HOLDING CAPACITY WITH A MINIMUM 12 INCHES OF FREEBOARD 3.CONCRETE WASHOUT STRUCTURE NEEDS O BE CLEARY MARKED WITH SIGNAGE NOTING DEVICE.

BELOW GRADE WASHOUT STRUCTURE ABOVE GRADE WASHOUT STRUCTURE

CONCRETE WASHOUTS

Do not discharge concrete or cement slurry from the site.

2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.

Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence. 4. Install temporary concrete washouts per local requirements, where applicable. If an

alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail. Do not use concrete washouts for dewatering or storing defective curb or sidewalk

sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum,

install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow. Locate washouts in an easily accessible area, on level ground and install a stone

entrance pad in front of the washout. Additional controls may be required by the approving authority.

Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary

products, follow manufacturer's instructions. 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout

HERBICIDES, PESTICIDES AND RODENTICIDES

Store and apply herbicides, pesticides and rodenticides in accordance with label Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of


Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. 4. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

accidental poisoning

Create designated hazardous waste collection areas on-site. . Place hazardous waste containers under cover or in secondary containment.

3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.



CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

.arolina *** 3 Days Before Digging North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketen





STIPULATION FOR REUSE

HIS DRAWING WAS PREPARED FOR L I THE SPECIFIC SITE. NAMED HEREO CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR ÛSE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE XAMPLE ON ANOTHER PROJECT REGULER HE SERVICES OF PROPERLY LICENSE ARCHITECTS AND ENGINEERS. REPRODUCTION THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZE ND MAY BE CONTRARY TO THE LAW.


FARM PRESERVE MOODY Ш

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM

DATE: 12/02/2024 SHEET TITLE:


EROSION CONTROL DETAILS

SHEET NO.: CD5




- . SEE CITY OF RALEIGH STANDARDS FOR TRENCHES AND PIPE BEDDING W-3 FOR ADDITIONAL DETAILS 2. PAVEMENT CUTS WITHIN NCDOT ROW SHALL CONFORM TO THE APPROVED ON SITE ENCROACHMENT
- 3. THE PAVEMENT CUT SHALL BE DEFINED BY A STRAIGHT EDGE AND CUT WITH AN APPROVED SAW CUT MACHINE.
- 4. THE TRENCH SUBGRADE MATERIAL SHALL BE BACKFILLED WITH SUITABLE MATERIAL AND COMPACTED TO A DENSITY OF AT LEAST 95% OF THAT OBTAINED BY COMPACTING A SAMPLE OF THE MATERIAL IN ACCORDANCE WITH AASHTO T-99 AS MODIFIED BY NCDOT. 5. THE FINAL 6" OF FILL SHALL CONSIST OF ABC MATERAIL COMPACTED TO A DENSITY EQUAL TO 100% OF THAT OBTAINED BY COMPACTING A SAMPLE OF THE MATERIAL IN ACCORDANCE WITH AASHTO T-80 AS MODIFIED BY

	CITY OF RALEIGH					
	DEPARTMENT OF PUBLIC UTILITIES					
	STANDARD CONCRETE PAVEMENT PATCH DETAIL					
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE		
\// I	RRH	3-31-00	A.B.B.	10-29-10		
V V — I	l ABB	l 2-8-05	MAB	110-31-13		



- I. FIRE HYDRANT SHALL BE AS MANUFACTURED: MUELLER, AMERICAN DARLING, KENNEDY, M\$H,
- WATEROUS, CLOW, EAST JORDAN IRON WORKS, OR US PIPE.
- 2. BRANCH PIPE SHALL BE DUCTILE IRON AWWA C I 50-96 3. 6" GATE VALVE SHALL BE AWWA C500-86 OPEN LEFT
- 4. STEEL RODS AND BOLTS SHALL BE $\frac{3}{4}$ HOT DIPPED GALVANIZED 5. FIRE HYDRANTS WILL BE INSTALLED IN TRUE VERTICAL POSITION
- RODS SHALL NOT BE COUPLED MORE THAN ONCE. IF THE LENGTH FROM THE VALVE TO THE HYDRANT EXCEEDS 20' THEN A MECHANICAL RESTRAINING GLAND WITH A REBAR CAGE SHALL BE INSTALLED NO MORE THAN 10' FROM HYDRANT AND POURED IN CONCRETE.
- FIRE HYDRANTS TO BE LOCATED IN ROW OR 2 FOOT EASEMENT ADJACENT TO ROW

	ANYTIME SITE WORK, CONSTRUCTION, ROAD WORK, OR ANY OTHER WORK CHANGES THE GRADE OF THE FIRE HYDRANT, THE PERSON RESPONSIBLE FOR THE WORK IS RESPONSIBLE FOR				CITY OF	RALEIGH	
				DEPARTM	ENT OF	PUBLIC UTILITIE	S
				STAN	DARD F	FIRE HYDRAN	VТ
	ADJUSTING THE FIRE HYDRANT TO STA WITHIN COMPLIANCE.			INSTA	ALLATI	ON DETAIL	
	WITTHIN GOTVII EII (NGE.	DWG.	ND.	REVISIONS	DATE	REVISIONS	DAT
		\ /	1 -	ABB	4-6-04		
		W -	4 Q				




NOTES:

- I. THE PAVEMENT CUT SHALL BE DEFINED BY A STRAIGHT EDGE AND CUT WITH AN
- APPROPRIATE SAW CUT MACHINE. 2. THE TRENCH SUBGRADE MATERIAL SHALL BE BACKFILLED WITH SUITABLE MATERIAL AND COMPACTED TO A DENSITY OF AT LEAST 95% OF THAT OBTAINED BY COMPACTING A SAMPLE OF THE MATERIAL IN ACCORDANCE WITH AASHTO T-99 AS MODIFIED BY NCDOT.
- 3. THE FINAL I' OF FILL SHALL CONSIST OF ABC MATERIAL COMPACTED TO A DENSITY EQUAL TO 100% OF THAT OBTAINED BY COMPACTING A SAMPLE OF THE MATERIAL IN ACCORDANCE WITH AASHTO T-80 AS MODIFIED BY NCDOT.
- 4. THE ENTIRE THICKNESS/ VERTICAL EDGE OF CUT SHALL BE TACKED. 5. THE SAME DEPTH OF PAVEMENT MATERIAL WHICH EXISTS SHALL BE REINSTALLED, BUT IN
- 6. THE ASPHALT PAVEMENT MATERIAL SHALL BE INSTALLED AND COMPACTED THOROUGHLY WITH A SMOOTH DRUM ROLLER TO ACHIEVE A SMOOTH LEVEL PATCH. 7. REFER TO CITY OF RALEIGH STANDARDS FOR TRENCHES AND PIPE BEDDING, W-3. FOR
- ADDITIONAL DETAILS. 8. NO HAND PATCHING ALLOWED.

NO CASE SHALL THE ASPHALT BE LESS THAN 3" THICK.


9. PAVEMENT CUTS WITHIN NCDOT ROW SHALL CONFORM TO THE APPROVED ON SITE ENCROACHMENT PERMIT.

		CITY OF RALEIGH				
		DEPARTMENT OF PUBLIC UTILITIES				
STANDARD ASPHALT PAVEMENT PATCH DETAIL						
	DWG. NO.	REVISIONS	DATE	REVISIONS	DATE	
	W-2	RRH	3-31-00	A.B.B.	4-16-0	
	VV - Z	D.W.C.	11-1-99	J.P.S.	10-29-10	
D 7						




- . ALL PUBLIC FIRE HYDRANTS IN THE CITY OF RALEIGH AND THE MERGER TOWNS OF GARNER, ROLESVILLE, WAKE FOREST, KNIGHTDALE, WENDELL AND ZEBULON SHALL BE PAINTED CHROME YELLOW
- WITH HIGH REFLECTIVE ALUMINUM SILVER CAPS, BONNETS AND OPERATING NUTS. 2. ALL PRIVATE FIRE HYDRANTS SHALL BE RED.


	CITY OF RALEIGH DEPARTMENT OF PUBLIC UTILITIES				
	RALEIGH, GARNER, KNIGHTDALE, ROLESVILLE, WAKE FOREST, WENDELL & ZEBULON				
	STANDARD FIRE HYDRANT WITH 5" STORZ PUMPER NOZZLE				
DWG.	REVISIONS	DATE	REVISIONS	DATE	
NO.	MAB	6-30-16			
W-5	KΔT	9-15-17			



- I. TRENCHES REQUIRING SHORING AND BRACING, DIMENSIONS SHALL BE TAKEN FROM THE INSIDE FACE OF THE SHORING AND BRACING.
- 2. NO ROCKS OR BOULDERS 4" OR LARGER TO BE USED IN BACKFILL. 3. ALL BACKFILL MATERIAL SHALL BE SUITABLE NATIVE MATERIAL.
- 4. BACKFILL SHALL BE TAMPED IN 6" LIFTS.
- 5. ACHIEVE 95% COMPACTION IN BACKFILL


	CITY OF RALEIGH					
	DEPARTMENT OF PUBLIC UTILITIES					
	TRENCH BOTTOM DIMENSIONS & BACKFILLING REQUIREMENTS FOR DUCTILE IRON					
/G. NO.	REVISIONS	DATE	REVISIONS	DATE		
V-3	D.W.C.	9-3-99	ABB	2-15-05		
v - J	RRH	3-31-00	J.P.S.	10-29-10		





OUTLET THREADS

	CITY OF RALEIGH				
	DEPARTMENT OF PUBLIC UTILITIES				
	HYDRANT OPERATING NUT AND 2				
	1/2" QUILLET THREADS				
DWG. NO.	REVISIONS	REVISIONS	DATE		
W-6	RRH DHL 2-18-08				
VV-O	A.B.B	4-13-04	J.P.S	11-1-10	




- I. FIRE HYDRANT SHALL BE AS MANUFACTURED: MUELLER, AMERICAN DARLING, KENNEDY, M&H, WATEROUS, CLOW, EAST JORDAN IRON WORKS, OR US PIPE.
- 2. BRANCH PIPE SHALL BE DUCTILE IRON AWWA C I 50-96 3. 6" GATE VALVE SHALL BE AWWA C500-86 OPEN LEFT
- 4. STEEL RODS AND BOLTS SHALL BE $\frac{3}{4}$ " HOT DIPPED GALVANIZED
- 5. FIRE HYDRANTS WILL BE INSTALLED IN TRUE VERTICAL POSITION RODS SHALL NOT BE COUPLED MORE THAN ONCE. IF THE LENGTH FROM THE VALVE TO THE HYDRANT EXCEEDS 20' THEN A MECHANICAL RESTRAINING GLAND WITH A REBAR CAGE SHALL BE INSTALLED NO MORE THAN 10' FROM HYDRANT AND POURED IN CONCRETE.


FIRE HYDRANTS TO BE LOCATED IN ROW OR 2 FOOT EASEMENT ADJACENT TO ROW

ANYTIME SITE WORK, CONSTRUCTION, ROAD WORK, OR ANY OTHER WORK CHANGES THE GRADE OF THE FIRE HYDRANT, THE PERSON RESPONS FOR THE WORK IS RESPONSIBLE ADJUSTING THE FIRE HYDRANT TO

WITHIN COMPLIANCE.

	BLE	CITY OF RALEIGH				
FOR		DEPAR	TMENT OF	PUBLIC UTILITIES		
() STAY	STANDARD FIRE HYDRANT				
		INSTALLATION DETAIL				
	DWG. NO.	REVISIONS	DATE	REVISIONS	DAT	
Ī	W-4	ABB	4-6-04	PAP	2/17	
		DHL	2/14/08			





	6" - 36"	#5	2'-2"+ O.D. PIPE	1.043 LBS/FT	1'-	·1"	1.1 LBS. EACH	X-24, Y-12
	48" & greater	#6	3'-0"+ O.D. PIPE	1.502 LBS/FT	1'-	-3"	1.9 LBS. EACH	X-24, Y-12
THRUST COLLAR, AND THRUST SCHEDULE								
	I.D. PIPE	"A"	"B"	"C"			"D"	
	6" - 16"	1'-4"	1'-7"	2"			3/8"	
	20" - 24"	1'-4"	1'-7"	3"			1/2"	
	30" - 36"	1'-4"	1'-7"	4"			5/8"	
	48" \$ greater	1'-8"	1'-9"	6"			7/8"	

Raleigh Water Review Officer

- I. SEE STANDARD DETAIL W-9 FOR THRUST BLOCK LOCATIONS. CONCRETE SHALL BE 3000 PSI AND TRANSIT MIXED.
- REINFORCING BARS SHALL BE DEFORMED AND TIED TOGETHER.
- 4. TRENCH BOTTOM WIDTH IN VICINITY OF THRUST BLOCK INSTALLATION SHALL BE THE MINIMUM WIDTH AS SHOWN ON STANDARD DETAIL W-3.
- 5. BACKFILL TAMPED IN 6" LIFTS PER STANDARD DETAIL W-3.
- 6. THRUST COLLAR MUST BE FACTORY WELDED ON BOTH SIDES ALONG BOTH EDGES OF COLLAR AROUND CIRCUMFERENCE.

Н	CITY OF RALEIGH						
	DEPARTMENT OF PUBLIC UTILITIES						
	THRUST BLOCKING DESIGN DATA FOR WATER MAINS						
NO.	REVISIONS	DATE	REVISION	15	DATE		
-7	RRH	1-21-00	J.P.S.	11-1-10			
,	D.H.L.	6-18-08					

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.


City of Raleigh Development Approval ______


*** 3 Days Before Digging ' North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentr


North

arolina









KAMPLE ON ANOTHER PROJECT REQUIRES HE SERVICES OF PROPERLY LICENSEE RCHITECTS AND ENGINEERS. REPRODUCTION THIS DRAWING FOR REUSE ON NOTHER PROJECT IS NOT AUTHORIZED ND MAY BE CONTRARY TO THE LAW.

ш THE PRES AT MOODY I


OB NUMBER: 21-002


HECKED BY: JK DRAWN BY: RC & SM DATE: 12/02/2024


SHEET TITLE:

UTILITY **DETAILS**

SHEET NO.:










STIPULATION FOR REUSE HIS DRAWING WAS PREPARED FOR U N THE SPECIFIC SITE. NAMED HEREO CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME.


USE OF THIS DRAWING FOR REFERENCE EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSE ARCHITECTS AND ENGINEERS. REPRODUCTIO F THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.


JOB NUMBER: 21-002 DRAWN BY: RC & SM


CD9

http://nc811.org/remoteticketentry
















HIS DRAWING WAS PREPARED FOR U N THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSE ARCHITECTS AND ENGINEERS, REPRODUCTION F THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

FARM SERVE AT AT MOODY F

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM


DATE: 12/02/2024

SHEET TITLE:

SITE

DETAILS

SHEET NO.:




CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.


City of Raleigh Development Approval

Raleigh Water Review Officer

North: Carolina *** 3 Days Before Digging ** North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.l







CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OF EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT MOODY FARM


JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM


DATE: 12/02/2024


SHEET TITLE:

SITE **DETAILS**

SHEET NO.:







Evergreen shrub


Inkberry Holly

Cont.

#3 Gallon

llex glabra

0



STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF BRODERIY, LICENSED THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

THE PRESERVE AT MOODY FARM

ROLESVILLE ROAD WAKE COUNTY, NC

JOB NUMBER: 21-002 CHECKED BY: JK DRAWN BY: RC & SM

DATE: 12/02/2024 SHEET TITLE:

LANDSCAPE PLAN

SHEET NO.:

North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry

City of Raleigh Development Approval

Raleigh Water Review Officer

Car Olivaina ***

http://nc811.org/remoteticketentry.

(IN FEET) 1 inch = 30

REQUIRED CALCULATIONS

STREET BUFFER ALONG ROLESVILLE ROAD: (387.504 LF) PER UDO SECTION 14.4

REQUIRED: 30' WIDTH FROM ROW LINE

PER 40 LF: 1 STREET TREE AND 2 UNDERSTORY ORNAMENTAL TREES REQUIRED PLANTINGS: 10 STREET TREES, 20 UNDERSTORY ORNAMENTAL TREES

PROVIDED: 10 STREET TREES, 20 UNDERSTORY ORNAMENTAL TREES



STIPULATION FOR REUSE

THIS DRAWING WAS PREPARED FOR USE ON THE SPECIFIC SITE, NAMED HEREON, CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

JOB NUMBER: 21-002 CHECKED BY: JK

DRAWN BY: RC & SM DATE: 12/02/2024

SHEET TITLE:

BUFFER PLAN

North 81 *** 3 Days Before Digging ***
North Carolina 811 SHEET NO.:

http://nc811.org/remoteticketentry.h

811 or 1-800-632-4949 Remote Ticket Entry

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.


City of Raleigh Development Approval

Raleigh Water Review Officer

PLANT DETAILS


(FOR SINGLE AND MULTI-STEM TREES)

TYPICAL SHRUB PLANTING



NOT TO SCALE

NOT TO SCALE



PLANT NOTES

PLANT INSTALLATION & MAINTENANCE NOTES:

- 1. ALL LANDSCAPING SHALL BE OF NURSERY STOCK QUALITY AND SHALL BE INSTALLED TO ACCEPTED NC LANDSCAPE CONTRACTOR STANDARDS.
- 2. ALL LANDSCAPING SHALL BE ADAPTABLE TO CLIMATIC CONDITIONS OF THE AREA.
- 3. LARGE TREES SHOULD NOT BE PLANTED WITHIN EASEMENTS AND A MINIMUM OF 6' FROM UTILITY LINES. UNLESS OTHERWISE SPECIFIED BY REVIEWING AGENCY. SHRUBS MAY BE PLANTED IN EASEMENTS. BUT A MINIMUM OF 3' FROM UTILITY LINES, UNLESS OTHERWISE SPECIFIED BY REVIEWING AGENCY.
- 4. ALL LANDSCAPING SHALL BE MAINTAINED IN GOOD CONDITION.

THE TOWN, WHICHEVER OCCURS FIRST.

- 5. ALL LANDSCAPING SHALL AT ALL TIMES PRESENT A HEALTHY, NEAT, CLEAN, ORDERLY, DISEASE-FREE AND PEST-FREE APPEARANCE.
- 6. ALL LANDSCAPING SOIL AND FILL SHALL BE FREE FROM WEEDS, REFUSE, AND DEBRIS AT ALL TIMES.
- 7. EXCESS SOIL SHALL BE DISPOSED OF IN A LEGAL MANNER. 8. ANY DEAD PLANT MATERIAL OR MATERIAL THAT FAILS TO SHOW HEALTHY GROWTH MUST BE REMOVED WITHIN 30
- 9. REPLACEMENT OF REMOVED PLANT MATERIAL MUST TAKE PLACE WITHIN 90 DAYS OF REMOVAL OR NOTIFICATION BY
- 10. ANY REPLACEMENT PLANT MATERIAL MUST MEET THE SIZE AND OTHER CHARACTERISTICS OF NEWLY PLANTED
- 11. IF USING STAKES AND GUYS SUCH SUPPORTS SHALL BE DESIGNED SO AS TO PROTECT TREES AND SHRUBS FROM INJURY. TREES AND SHRUBS SHALL BE FASTENED TO THE SUPPORT WITH AN ACCEPTABLE COMMERCIAL TREE TIE OF PLASTIC OR HOSE-COVERED WIRE. AFTER THE WARRANTY PERIOD HAS ENDED, STAKES AND GUYS SHALL BE REMOVED.
- 12. CONTRACTOR IS RESPONSIBLE TO CONTACT MISS UTILITIES (811) 48 HOURS PRIOR TO COMMENCEMENT OF WORK. CONTACT LANDSCAPE ARCHITECT IF FIELD CONFLICTS/DISCREPANCIES ARISE.
- 13. CONTRACTOR RESPONSIBLE TO VERIFY PLANT COUNTS. PLANTING PLAN SHALL GOVERN IN THE CASE OF A CONFLICT.
- 14. ALL PLANTS SHALL MEET OR EXCEED STANDARDS AS DETERMINED BY THE AMERICAN STANDARD OF NURSERY STOCK.
- 15. CONTRACTOR SHALL WARRANTY ALL PLANTS FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE. 16. WHEN POSSIBLE, PLANTING SHALL BE INSTALLED BETWEEN SEPTEMBER 1 - JUNE 30TH AND IN FAVORABLE WEATHER
- CONDITIONS. WHEN PLANTING MUST BE PERFORMED OUTSIDE OF SPECIFIED DATES, PLANTS MUST BE WATERED ON A REGULAR BASIS TO ENSURE VIABILITY.
- 17. PLANT VARIETIES, SIZES AND LAYOUT SHALL CONFORM ACCURATELY TO THE LANDSCAPE PLAN. CONTACT LANDSCAPE ARCHITECT FOR FIELD CONFLICTS.
- 18. DISTURBED AREAS SHALL BE SEEDED ACCORDING TO THE NOTES FOUND ON THIS PAGE.
- 19. PLANT SUBSTITUTIONS SHALL BE BROUGHT TO THE ATTENTION OF AND APPROVED BY LANDSCAPE ARCHITECT PRIOR TO
- 20. MULCH USED ON-SITE SHALL BE OF A NON-DYED, NATURAL HARDWOOD VARIETY TO BE INSTALLED AT A MAXIMUM DEPTH OF 3", MINIMUM DEPTH OF 2".

TOPSOIL / PLANTING MIX MINIMUM REQUIREMENTS:

- 1. TOPSOIL/PLANTING MIX SHOULD BE NATURAL, FERTILE, AGRICULTURAL SOIL CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH, IT SHOULD BE UNIFORM COMPOSITION THROUGHOUT, WITH ADMIXTURE OF SUBSOIL, IT SHOULD BE FREE OF STONES, LUMPS, LIVE PLANTS AND THEIR ROOTS, STICKS AND OTHER EXTRANEOUS MATTER. TOPSOIL SHOULD NOT BE USED WHILE IN A FROZEN OR MUDDY CONDITION.
- 2. TOPSOIL/PLANTING MIX SHALL HAVE AN ACIDITY RANGE OF PH 5.5-7.0 AND THE FOLLOWING COMPOSITION:

CLAY (RED CLAY, WELL PULVERIZED)	MINIMUM 10%; MAXIMUM 35%
COMPOST*/ORGANIC	MINIMUM 5%; MAXIMUM 10%
SILT	MINIMUM 30%; MAXIMUM 50%
COARSE SAND (FREE OF ROCKS, 0.5 TO 1.0 MM F)	MINIMUM 30%; MAXIMUM 45%


- 3. ORGANIC MATERIAL SUCH AS SAWDUST OR LEAF MOLD THAT HAS COMPLETED THE DECOMPOSITION PROCESS
- 4. RECOMMENDATIONS:
- 5. ALL PLANTING AREAS SHOULD BE TESTED FOR PROPER DRAINAGE. DRAINAGE SHOULD BE CORRECTED AS NECESSARY TO INSURE PROPER TREE GROWTH AND SURVIVAL. THE FOLLOWING LEVEL OF NUTRIENT ELEMENTS IS RECOMMENDED FOR


CALCIUM	55 - 80%
MAGNESIUM	10 - 30%
POTASSIUM	5 - 8%


SEEDING SCHEDULE FOR LAWNS & SLOPES (MAXIMUM 3:1):

DATE	TYPE	PLANTING RATE
AUG 15 - NOV 1	TALL FESCUE	300 LBS/ACRE
NOV 1 - MAR 1	TALL FESCUE AND ABRUZZI RYE	300 LBS/ACRE OR ANNUAL RYE
MAR 1 - APR 15	TALL FESCUE OR HARD FESCUE	300 LBS/ACRE
MAR 1 - JUL 15	HULLED COMMON BERMUDA GRASS OR HYBRID BERMUDA GRASS OR CENTIPEDE GRASS OR ZOYSIA GRASS OR ST. AUGUSTINE GRASS	200 LBS/ACRE
APR 15 - JUN 30	WEEPING LOVE GRASS OR BAHIA GRASS	25 LBS/ACRE
JUL 1 - AUG 15	TALL FESCUE AND *** BROWNTOP MILLET *** OR SORGHUM-SUDAN HYBRIDS	120 LBS/ACRE 35 LBS/ACRE 30 LBS/ACRE









ON THE SPECIFIC SITE, NAMED HEREON CONTEMPORANEOUSLY WITH ITS ISSUE DATE AS LISTED, HEREON. AND IT IS NO SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE (EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTIO OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

SERVE Ŏ W

JOB NUMBER: 21-002 CHECKED BY: JK

DATE: 12/02/2024 PLANTING **NOTES AND DETAILS**

DRAWN BY: RC & SM

SHEET NO.:

CITY OF RALEIGH - PLANS AUTHORIZED FOR CONSTRUCTION

Electronic Approval: This approval is being issued electronically. This approval is valid only upon the signature of a City of Raleigh Review Officer below. The City will retain a copy of the approved plans. Any work authorized by this approval must proceed in accordance with the plans kept on file with the City. This electronic approval may not be edited once issued. Any modification to this approval once issued will invalidate this approval.

City of Raleigh Development Approval

Raleigh Water Review Officer

*** 3 Days Before Digging * North Carolina 811 811 or 1-800-632-4949 Remote Ticket Entry http://nc811.org/remoteticketentry.