

Preliminary Engineer's Opinion of Probable Construction Cost

Project Information

Project Information						
	Project Name:	Parker Rid	dge Phase 1A			
	BGE Project #: 8	8430-03				
	Designed by:	JWM	Date:	2/24/2025		
	Revised by:	JWM	Date:	2/24/2025	•	
	Checked by:	DF	Date:	2/24/2025	•	
	QUANTI) MATERIALS		
	# OF UNITS	UNIT		SUBTOTAL COST	T	OTAL COST
SITE IMPROVEMENTS						
STORM DRAIN						
JB or Drain Structure < 6' deep	15	EA	4,500.00	\$ 67,500	Ś	67,500
SCM Conversion	1	EA	21,075.00			21,075
15" Class 3 RCP	444	LF	45.00			19,980
18" Class 3 RCP	278	LF	51.00	\$ 14,178	\$	14,178
24" Class 3 RCP	606	LF	65.00	\$ 39,390	\$	39,390
12" FES, with Rip Rap	2	EA	1,525.00	\$ 3,050	\$	3,050
15" FES, with Rip Rap	1	EA	1,525.00	\$ 1,525	\$	1,525
24" FES, with Rip Rap	1	EA	2,200.00	\$ 2,200	\$	2,200
				TOTAL =	\$	168,898
WATERLINE						
Utility Adjustments	34	EA	525.00	. ,		17,900
	L			TOTAL =	\$	17,900
			SITE IMPROVEME	NIS SUBIOTAL =	\$	186,798
STREETS						
PAVING						
1.5" \$9.5B	5,372	SY	12.00	. ,	\$	64,464
				TOTAL =	\$	64,464
STREET SIGNS						
Stop Signs - City/County/State Standard	8	EA	325.00	\$ 2,600	\$	2,600
Street Signs - City/County/State Standard Handicap Parking Signs/ Symbols-	3	EA	250.00	\$ 750	\$	750
City/County/State Standards	3	EA	350.00	\$ 1,050	\$	1,050
Striping	1	LS	25,000.00	\$ 25,000	\$	25,000
Pedestrian Crossing signs	4	EA	250.00		\$	1,000
				TOTAL =	\$	30,400
SIDEWALK AND PEDESTRIAN NEEDS					Ŧ	00,100
10' Walking Trail	1890	SY	50.00	\$ 94,500	\$	94,500
6' Concrete sidewalk	704	SY	50.00	- /	\$	35,200
	704	51	50.00			
					\$	129,700
			STRE	ETS SUBTOTAL = TOTAL:	\$	224,564 411,362

Notes:

1. EOPC based upon progress noted on site vist date February 7, 2025

2. EOPC is for site related improvements and construction and does not include buildings and/or structures.

3. Unit costs used in this engineer's opinion of probable cost are based upon historical contractor bids and engineer's

experience. This opinion of probable cost shall be verified by a contractor licensed and qualified to perform the work prior to relying upon for final project budgeting decisions.